






The worst "beating" any print ever took!







Here is the same Ozaplastic print seconds later!
... As good as ever, simply cleaned with a damp cloth!

OZAPLASTIC eliminates 95% of your print replacement costs... is recommended whenever the going is tough ... where standard paper or cloth prints "fold up" after a short period of service.

You'll want to use Ozaplastic in the shop and field... around operations where grease, grime, or water abound ... where precision is of the utmost importance... where annoyances—such as having to wait for a new print—put a hitch in production.

When soiled, you need only rub a damp cloth over Ozaplastic and it's like new—all details sharp and clear, jet black on a glossy white background.

For this reason, OZAPLASTIC is also used in sales catalogs and presentation booklets—even laminated on machines, etc., when "on-the-spot" instructions or wiring diagrams are required.

Now . . . Make 16 Types of Ozalid Prints!

OZAPLASTIC is only one of the 16 different types of prints you can produce in an Ozalid machine.

For example, you can reproduce the lines and images of any translucent original in black, blue, red, sepia, or yellow colors. And make prints on white or tinted paper, cloth, foil, film, or plastic.

Thus, you can "color code" prints of different operations . . . and always

match the print to the job at hand.

Furthermore, all of these Ozalid prints are made in exactly the same manner—without interruption—in 30 seconds or less.

See the 16 different types of Ozalid prints. Learn how economical it is to make them in the new OZALID STREAM-LINER.

Write today for free booklet No. 274.



OZALID

DIVISION OF GENERAL ANILINE AND FILM CORPORATION
JOHNSON CITY, NEW YORK

Ozalid in Canada—Hughes Owens Co., Ltd., Montreal



Controlled Air Supply with "Freon" Safe Refrigerants Produces Better Printing . . . Promotes Employee Comfort and Efficiency

Officials of The Newman Rudolph Lithographing Company have reason to be proud of their new plant ... one of the first postwar commercial structures built in Chicago. It's an immense 4-story, virtually windowless building air conditioned throughout. Modern equipment, utilizing "Freon" safe refrigerants, insures ideal working conditions.

All 53,000 square feet of the plant, completed early in 1947, are maintained at a temperature of 72° to 76°F. with relative humidity of 41% to 43% or less. Thermostatic control holds both temperature and humidity within one degree or percent of the desired level for maximum working efficiency and employee comfort in different departments.


Uniformly controlled climate conditions are of the utmost importance


in quality color lithography. Paper is sensitive. Changes in temperature or humidity cause it to buckle, shrink or stretch. Presses, paper-folding machines and other production units are also affected by such changes and function at top efficiency only when both temperature and humidity remain constant. So, fully controlled air conditioning was a prime requisite in designing the plant.

The conditioning equipment, housed in the tower of the \$1,900,000 building, consists of a Carrier installation of 400-ton capacity. "Freon" is the refrigerant used because it is simple, safe, non-toxic, non-flammable, non-explosive. Its purity and uniformity further insure long, efficient and trouble-free performance of the system.

Whenever air conditioning plays

an important part in your plans, be sure specifications call for equipment in which "Freon" safe refrigerants are used. There is a "Freon" refrigerant for every commercial, industrial or household need. Technical data on request. Kinetic Chemicals, Inc., Tenth and Market Sts., Wilmington 98, Delaware.





PLASTER-"riveted"-to ROCKLATH*

and "welded," too. Perforated ROCKLATH plaster base holds plaster with a double grip—a mechanical key that clinches like a rivet—a suction bond which "welds" plaster to the lath. This results in a continuous barrier of gypsum from studs to finish.

What does this mean to the architect? Just this. Recognized testing laboratories give Perforated ROCKLATH and RED TOP* Plaster partitions a one hour fire rating with proper plaster proportion and thickness.

Specify Perforated ROCKLATH and RED TOP Plaster to obtain these added fire resistance and double grip advantages in addition to the beauty and durability of plastered surfaces—flexible to the will of the designer.

*ROCKLATH and RED TOP used above are registered trademarks which distinguish products manufactured only by the United States Gypsum Company.



United States Gypsum

For Building . For Industry

Gypsum · Lime · Steel · Insulation · Roofing · Paint



With a floor area 168'8" square, a roof 45' above grade at its high point and 17' at the eaves, and large, frequently-opened access doors, this hangar, like all such structures, presented a difficult heating problem. The designers solved it with radiant heating, which has been successfully used in a number of similar applications.

The floor area is divided into 20 individual heating sections, each with a sinuous coil of 1½" wrought iron pipe, welded and cold-bent to shape, embedded in an 8" concrete floor slab. In the sections along the sides and across the front, the pipe was spaced on 12" centers. In the remainder of the floor 24" spacing was used. Welding operations on the coils were facilitated by raising each indi-

vidual coil a few feet off the floor with tripod-mounted hoists.

To provide a level base, a $1\frac{1}{2}$ " rough concrete slab was first poured on the fill. Reinforcing rods were laid and angle iron supports placed above them, on which the coils rested. This positioned the pipe at approximately the neutral axis of the slab. Hot water is supplied to the system from two U-type heat exchangers, which are fed with steam at 5-lbs. pressure by two oil burning boilers. Two singlestage centrifugal pumps circulated the water. Temperature is controlled by a combination indoor-outdoor thermostat.

The use of wrought iron follows established engineering practice. For ten years, A. M. Byers Company has been collecting data on radiant heating as a service to designers, and has detailed information on a thousand or more installations. Over 90% of these use wrought iron . . and evidence indicates that the same proportion holds for the many thousands of other installations. Wrought iron's ease of fabrication, its high heat emission, its favorable thermal characteristics, and its demonstrated corrosion resistance make a vital contribution to a successful system. Ask for our bulletin, "Wrought Iron for Radiant Heating."

A. M. Byers Co., Pittsburgh, Pa. Established 1864. Boston, New York, Philadelphia, Washington, Atlanta, Chicago, St. Louis, Houston, Salt Lake City, Seattle, San Francisco.

Corrosion costs you more than wrought iron

"ETERNALLY YOURS" — professionally-produced 16mm sound motion picture. An entertaining saga of the wrought iron industry, available to technical groups. New, authentic, informative. Write Modern Talking Picture Service, Inc., 9 Rockefeller

BYERS

GENUINE WROUGHT IRON
TUBULAR AND HOT ROLLED PRODUCTS

ELECTRIC FURNACE QUALITY ALLOY AND STAINLESS STEEL PRODUCTS

Plaza, N.Y. 20, N.Y.

ARCHITECTURAL

RECORD



Copyright 1947 with all rights reserved F. W. DODGE CORPORATION • Vice-President in charge of Magazine Division, H. Judd Payne • EDITORS: Editor-in-Chief, Kenneth Kingsley Stowell, A.I.A.; Managing Editor, Emerson Goble; Senior Associate Editor, Douglas Haskell; Associate Editors, John W. Ragsdale, James S. Graham, Jr.; Associate in South America, Edmund J. Whiting, A.I.A.; News Editor, Florence A.

van Wyck • ART DEPARTMENT: Myron S. Hall, 3rd, Director; Peter Plening, Consultant; Sigman-Ward, Drafting • CONSULTANTS: Industry Relations Consultant, Thomas S. Holden; Statistical Consultant, Clyde Shute; Building Economics Consultant, Norbert Brown; Field Research Consultant, Clifford Dunnells, Jr.

Architectural Record (combined with American Architect and Architecture) is published monthly by F. W. Dodge Corporation, 10 Ferry St., Concord, N. H., with Editorial and Executive Offices at 119 West 40th Street, New York, N. Y. Thomas S. Holden, Pres.; Howard J. Barringer, Vice-Pres. and Treas, Irving W. Hadsell, Vice-Pres.; Chauncey L. Williams, Vice-Pres.; Sanford D. Stockton, Jr., Secy.; Walter F. De Saix, Asst. Treas, Edwin H. Freed, Asst. Treas. Member Audit Bureau of Circulation and Associated Business Papers, Inc. Architectural Record is indexed in Reader's Guide, Art Index and Industrial Arts Index. Subscription rates: United States and Possessions, Canada, Cuba, Mexico, Central and South America, and Spain, \$4.50 the year, \$7.50 for two years, \$9 for three years, elsewhere, \$6.50 the year, \$11.50 for two years, \$15 for three years. Single copy, \$1. Circulation Manager: Marshall T. Ginn. Every effort will be made to return material submitted for possible publication (if accompanied by stamped, addressed envelope), but the editors and the corporation will not be responsible for loss or damage. Other Dodge Services: Real Estate Record & Builders' Guide, Sweet's Files, Home Owners' Catalogs, Dodge Reports & Dodge Statistical Research Service.

VOL. 102 • NO. 1	July	1947
POOR RELATIONS — PUBLIC, THAT IS		. 69
MODERN MEXICO	eture.	. 70
IDEAS BORN OF WINDS AND WEATHER	• • •	. 84
MIRACLE (AND MECCA) ON 34TH STREET	ty. Ka	. 90
BUILDING TYPES STUDY NO. 127 RESTAURANTS AND BA	RS	. 96
ARCHITECTURE FOR EATING AND DRINKING		. 96
GRISON'S STEAK HOUSE		. 107
NEW HORIZON ROOM, HOTEL CONTINENTAL		. 108
MC ALPIN BAR AND RESTAURANT		. 109
MADISON ROOM, MANCHESTER DEPARTMENT STORE . Madison, Wis. Skidmore, Owings & Merrill, Architects		. 112
RENAISSANCE AT RIKERS'		. 116
ARCHITECTURAL ENGINEERING Technical News and Research		. 117
RESTAURANT LIGHTING WITH SLEIGHT-OF-HAND		. 117
RESTAURANT KITCHENS		. 119
TIME-SAVER STANDARDS		. 122
PRODUCTS for Better Building		. 124
MANUFACTURERS' LITERATURE		. 130
THE RECORD REPORTS News from the Field		. 7
CONSTRUCTION COST INDEXES		. 27
REQUIRED READING		. 28
EMPLOYMENT OPPORTUNITIES		186
INDEX TO ADVERTISEMENTS		202



THE RECORD REPORTS

Congress Faces Adjournment with some Housing Items Enacted, Some Pending • Restrictions Further Relaxed Rental Housing Volume Is Up • Production Is Higher

Congress neared its summer adjournment with some housing items enacted and some pending. There was no evident intention of writing into law the major Taft-Ellender-Wagner bill—the so-called National Housing Commission Act.

The lawmakers had approved a modified continuance of rent controls, but practical elimination of other controls, elimination of premium payments and guaranteed market plans, additional funds to complete emergency housing units, funds for the Apprentice Training Service to aid in provision of skilled workers, authorization for planning a new federal courthouse in the District of Columbia, and others. They had pending three bills on loan and insurance provisions (H.R. 2798, H.R. 2799, and H.R. 2800).

Housing Plan Pending

Pending, too, was President Truman's late-May recommendation for reorganizing the federal housing agencies. Succinctly, the President proposed a Housing and Home Finance Agency to include a Home Loan Bank Board, the Federal Housing Administration and the Public Housing Administration. He also suggested a National Housing Council on which the new agency and other federal units "having important housing functions" could be represented.

The plan calls for an administrator to head the overall agency, three members for the Home Loan Bank Board, and a commissioner each for FHA and PHA. (The Federal Savings and Loan Insurance Corporation falls under the Bank Board.)

As the reorganization plan arrived on Capitol Hill its chances for early approval were not promising. The last Congress, it will be remembered, looked with disfavor on an overall housing agency.

Permanent Bill Sought

Among measures getting attention is a Senate bill (S. 971) for \$250 million for FWA grants to educational institutions where there is a shortage of facilities to take care of war veterans. The bill was actively endorsed by educators at hearings before the Senate Committee on Labor and Public Welfare.

Meanwhile, the Senate Banking and Currency Committee had good words for the broad National Housing Commission Act. "The Committee believes it is high time to look to comprehensive legislation for the solution of our housing troubles," it told the Senate in urging passage of the bill (S. 866). "We should no longer yield to those who clamor for 'temporary solutions' and insist that permanent, comprehensive measures are too late to do any good."

Restrictions Relaxed

While Congress was arguing the continuation of rent and other controls, Housing Expediter Frank R. Creedon relaxed some existing restrictions. Beginning in June, federal housing permits were no longer required for builders of homes, the 1500 sq. ft. limit was expanded to 2000, and more than one bathroom could be installed. Other actions of the Housing Expediter include (1) stepping out of the surplus property picture July 1 because of dwindling amounts of surplus housing items, and (2) transfer of rent control, under a presidential order, from the Office of Temporary Controls to the Expediter's

More Rental Housing Noted

The federal housing agencies drew two points of consolation out of the slowing up of housing construction. Point num-


ber one was the uptrend in the volume of rental housing planned; FHA, which gets the applications for mortgage insurance, reported that the projects were running about four to one compared with 1946. Point number two was that the number of "completions" of houses as distinct from "starts" (which have been lagging) will exceed one million if conversions, trailers and temporary units are included. Of this number 750,000 will be permanent. He tied his prediction, however, to continuation of federal controls on non-residential construction.

As to the rental projects, FHA Commissioner Raymond M. Foley advises that the average provides apartments for 39 families, three out of every four containing less than 50 units. About seven of every eight are of the walk-up type.

Production Is High

While the Administration continued its efforts to talk down prices, reports came in of building material production remaining high. In lumber, for instance, total output in the first quarter ran 20 per cent above the 1946 period, indicating a 1947 total of 36 billion board feet or more. For fabricated structural steel, shipments in the first quarter exceeded the same quarter in 1946 by 46 per cent. Clay sewer pipe was running 66 per cent higher. On the other hand, the hardware trade, reports the Commerce Department, will not be able to fill consumer needs before 1948.

The building industry pointed to factors, in addition to the increasing supply (Continued on page 10)



"Are you the people who advertised for an upstairs maid?"

- Drawn for the RECORD by Alan Dunn



Double-duty INSULITE SHEATHING (for outside walls) does two things for the price of one:


(1st) It Sheathes

(2nd) It Insulates

One material — DOUBLE usage. One application — TWO important services to help your client get double for his money.

This is smart, modern progressive construction procedure—
functional and economical. It offers practical advantages over
wood sheathing horizontally applied. Greater bracing strength, less labor
cost, improved rigidity . . . PLUS insulation! Specify double-duty
Insulite Sheathing—the genuine.







Double-duty INSULITE LOK-JOINT LATH (for inside walls) does two things for the price of one:

(1st) Plaster Base

(2nd) Insulates

One material — DOUBLE usage. Your client gets a plus value with his purchase: — plastered walls — PLUS insulation and vapor control! Two things for the price of one! Specify double-duty Insulite Lok-Joint Lath.





What the United Nations Headquarters may look like: schematic rendering by Hugh Ferriss illustrating the general architectural scheme developed by the Headquarters Planning Staff. At left, on southerly edge of the six-block site, is the 40-story Secretariat Building; at right is the Specialized Agencies Building; meeting area is in center. Publication of the plan brought a storm of criticism (see page 69)

of materials, already operating to lower building costs—such as keener competition, regaining of prewar efficiency, increasing productivity of labor, and cost-reducing building techniques.

Research Stressed

Research is getting increased attention. The Commerce Department's Office of Technical Services has made a grant for studies at the University of Illinois of methods of erecting industry engineered housing, the type of project developed jointly by the Producers' Council and the National Retail Lumber Dealers' Association. To determine means of increasing efficiency, six identical houses are to be constructed one after the other with an eye to eliminating waste motion and effort.

Other funds have gone to aid an industrial non-profit program in standardizing dimensions of various types of building materials. The goal is to reduce building costs and speed construction by eliminating delays resulting from "the needless multiplicity of types and sizes of wood, clay, metal and other varieties of building materials and accessories." Also under development is an inexpensive building board.

NHA, too, has a Technical Office on housing research and testing. The Forest Products Laboratory at Madison, Wis., has been collaborating with the Office in preparing a technical reference book on wood prefabrication, covering characteristics of various woods, giving data on strength of materials, wood treating, processing, machinery, etc.

Plumbing Codes Studied

Government experts have counted the number of plumbing codes in the United States, coming up with the figure of 1500 — some of them state-wide, some country-wide, some for cities or villages. What one code insists on another forbids, while a third is neutral. To officials whose job is the working out of uniform codes, this is rich and inviting territory and half a dozen agencies are prospecting it.


The uniform plumbing code, once it appears, will be a prelude to something more, notably to standardizing products and reducing numbers of sizes, shapes, etc., as has been done in many other industries.


At the Bureau of Standards, NHA is installing sewers, drains, stacks, etc., made of transparent plastic, whose insides will be watched and photographed. Movies will be made. The pictures will be scrutinized for scientific value and shown around among local politicians for propaganda effects, perhaps, with a sound track that observes, "This, gentlemen, is what happens to sewage."


The code idea is intended, over the (Continued on page 12)



Above and below: Glen Oaks Village, a 3800-apartment rental community now under construction in the Borough of Queens, New York City, for the Gross-Morton Company. Buildings will cover only ½ of the 175-acre site. Benjamin Braunstein, architect







There are no puzzles to be worked out when installing Salter-Glauber Master-piece Fixtures. For they are designed with a minimum of parts and each unit is factory assembled, tested and guaranteed to be perfect in every respect. In addition, the standardization of most working parts and incidental trim, enables us to provide unprecedented quality in volume production. Plumbers, contractors and home owners all benefit by the extras found in Salter-Glauber Masterpiece Fixtures . . . Start specifying Masterpiece quality today.

S-500 — Compact Gothic Plate Diverter Bath and Shower Fixture. Cast one piece body with 23/4" center openings. Now furnished with polished chrome brass plate.





MASTERPIECES IN BRASS

10 Ninth Street, Marysville, Ohio

and division THE GLAUBER BRASS MFG. CO., Kinsman, Ohio

THE RECORD REPORTS

(Continued from page 10)

long pull, to reduce building and maintenance costs. Plumbing equipment production, presumably, would be made less costly since standard materials and shapes would lend themselves to mass production. Maintenance, too, would become cheaper since dealers could store fewer replacement parts, cutting their overhead costs.

Materials Tested

Agencies report that many materials with which they have been experimenting meet high performance tests. Among these they include:

Wallboard from saw-palmetto, a tree once considered useless and a pest; laminated flooring made of waste hardwood pieces, developed by TVA; kraft paper and resin wall panels, etc.

There are also all-aluminum houses, light weight concrete and others some day to be exhibited.

The agencies say that these have met "rigid performance" standards, but the physicists and chemists who developed the tests are more modest than the publicity writers. After all, they point out, the tests are artificial and must themselves be tested. A typical test seeks to reproduce the conditions of life - with its rain, wind, extremes of temperature. The piece of equipment is then exposed to all the contrived lightning, hail, snow, sleet and sunshine. But physicists point out that there may always be some condition which they have overlooked in framing their tests and that the final test still will be that of actual use - say for five or ten years.

Confer on City Growth


A joint conference on problems of city growth is planned in Washington for September 11–12 by the Urban Land Institute, the Automotive Safety Foundation, the American Transit Association and the U. S. Chamber of Commerce.

To be considered are various angles such as city planning as a tool; making the most of existing facilities in avoidance of traffic congestion and development of freeways and expressways; parking problems; slum clearance and offsetting of blight; relation of downtown business sections to the growing trend toward decentralization and suburban development.

Business Surveyed

The Survey on Business Expectations and Governmental Policies made for the Congressional Joint Committee on the Economic Report by Dun & Bradstreet,

(Continued on page 14)



It's EASY to plan a sound system with RCA's Unit-Built equipment

Now you can easily plan an efficient sound system for any project.

RCA's new Sound Systems are unit-built of standardized frames and panels matched to make up various combinations of basic units. These distinctly styled basic units assemble into master sound control consoles ... provide the desired requirements of sound services.

RCA unit-built sound installations range

from a simple paging system to complete facilities for the distribution of radio programs, recordings and paging. The same basic unit design is employed in all cases providing "custom-built" consoles within the price range of regular production equipment.

SPECIAL ARCHITECTURAL SERVICE—RCA's architects consulting bureau will be glad to work with you on sound system jobs of every kind. Write to Dept. 10-G.



places information on Sound Systems equipment at your finger tips.



RADIO CORPORATION OF AMERICA ENGINEERING PRODUCTS DEPARTMENT, CAMDEN, N.J.

In Canada: RCA VICTOR Company Limited, Montreal



... with Zefeley's Door A shower bath, representative of the best quality in cabinet construction available to the plumbing trade today. Recommended for installation in the better class of homes, institutions, hotels, and clubs. The Fiat Cadet Shower and Zephyr Door are products of fine workmanship and design, in harmony with modern bathroom architecture.

In Canada - Fiat showers are made in Canada by The Porcelain and Metal Products, Ltd.,

Littl Metal Manufacturing Company
Chicago 13, Illinois

THE RECORD REPORTS

(Continued from page 12)

Inc., brought out some interesting reactions on federal aid to housing.

To quote the summary of findings:

"Majorities of most groups of respondents favored reduction of federal encouragement of housing construction, primarily because they felt that government should not interfere in such an essentially private type of business, and because they felt that private construction would be encouraged if federal aid to housing were reduced.

"On the other hand, most of the labor leaders and the economists stated that federal aid to housing should be increased, both to relieve the housing shortage and because increased housing activity would help sustain a high level of employment."

Opinions were forthcoming also on rent control. The summary points out as

"Most of the groups of respondents showed substantial majorities in favor of maintaining and raising rent ceilings. This policy was advocated by most of the business groups, as well as by economists and newspaper editors. Their general feeling was that this would help the housing situation by encouraging expenditures by landlords in addition to encouraging new building in shortage areas. Many of the respondents combined the above stated recommendation with advocacy of elimination of rent ceilings on new construction only.

"In one of the business groups, a majority of respondents advocated complete elimination of rent ceilings. On the other hand, most of the labor leaders and 42 per cent of the farmers stated that rent ceilings should be maintained without change.


Survey questionnaires were mailed to a selected list of 908 names and questionnaires completed in time for inclusion in the report totaled 583 or 64 per cent. Groups contacted included manufacturers, mining, construction, transportation, communications and utilities, service industries, finance and insurance, wholesalers and retailers, farmers, labor leaders, economists and newspaper editors.



TO STUDY COSTS

The American Institute of Architects and the National Association of Home Builders are to collaborate in a program designed to improve the quality of low cost homes and to find ways to reduce building costs, Douglas W. Orr, A.I.A. president, has announced.

"The collaboration between the Institute and the National Association of (Continued on page 16)



Stran-Steel framing is a building product of Great Lakes Steel Corporation

Stran-Steel achieves its construction speed through unique engineering features. An efficient, simplified framing system, it requires only a few basic members and fittings. Members are delivered pre-cut to blueprint specifications, ready for assembly. Joining is accomplished with self-threading screws or by welding. Collaterals are attached simply by nailing them directly to the patented nailing groove, an exclusive feature of Stran-Steel. Joists and studs are readypunched at convenient intervals to admit pipes and conduits. With the members in place, the punched holes are always in alignment.

Stran-Steel appeals to prospective owners, since the advantages of a durable, non-sagging, fire-resistant frame are almost self-apparent. It appeals to architects and builders because it provides the strength of steel without curtailing freedom of design. For complete information on Stran-Steel framing, see Sweet's File, Architectural, Sweet's File for Builders, or the January Issue of Building Supply News.

BUILD WITH



GREAT LAKES STEEL CORPORATION

Stran-Steel Division • Dept. 36 • Penobscot Building • Detroit 26, Michigan OF NATIONAL STEEL CORPORATION



Propellairs are the simple solution to virtually every problem of volume air movement. They sweep out dust, moisture, heat, and fumes *quickly* and *completely*—improve working conditions, reduce labor costs, and increase production capacity. Functional designs for professional applications.

ENGINEERED EFFICIENCY

Scientifically designed Propellair fans have airfoil-section blades—actually *pull more air* than they push, for double-action efficiency. The *whole* blade surface works—with load *evenly* distributed from hub to blade tip—for axial-flow, high-velocity, high-volume air output.

REMOVES DUST AND MOISTURE

This roof installation of three Propellair Verti-Stacks at the Farmers' Dryer, Alvin, Texas, provides air-moving capacity of nearly 150,000 c.f.m. Its powerful exhaust clears the entire drying tower of troublesome dust and removes moisture as fast as it is given up by the rice. Discharge shoots high into outside air.



DIRECT-CONNECTED PROPELLAIR FANS

Each sturdy Verti-Stack includes a readily removable direct-connected Propellair fan. Direct-connected fans are also available for easy mounting in walls, windows, panels, ducts, and stacks. Sizes 12 to 60 inches diameter. Capacities to 88,000 c. f. m. Powered by fully enclosed, ball-bearing, heavy-duty Robbins & Myers electric motors.

Write today for detailed information.

PHOPHIAM

IVISION OF ROBBINS & MYERS . INC.

SPRINGFIELD . OHIO

THE RECORD REPORTS

(Continued from page 14)



"Cheesecake" — plaster and gold leaf panel by Robert Cronbach for Hollenden Hotel Bar, Cleveland. From "Architecture Needs Sculpture" exhibition by the Sculptors Guild at the Architectural League of New York recently

Home Builders," Mr. Orr said, "will include joint meetings of local chapters or their committees, an interchange of convention speakers, and the preparation of factual information to be disseminated among the memberships.

"This collaboration should point the way to some methods of reduction in the cost of housing, stimulated by the contribution which can be made by the members of the architectural profession to the solution of the problems of small home construction."

ON THE CALENDAR

May 22-Sept. 15: "Tomorrow's Buildings" exhibit of current work of members. Architectural League of New York, 115 E. 40th St., New York City.

June 13-indefinite: Exhibition of photographs, "Recent Discoveries in Chinese Architecture." Metropolitan Museum of Art, New York City.

July 7-12: 1st Annual Store Modernization Show, Grand Central Palace, New York City.

August 17–22: Annual meeting, American Society of Sanitary Engineering, Congress Hotel, Chicago.

Sept. 1-4: Fall meeting, American Society of Mechanical Engineers, Hotel Utah, Salt Lake City, Utah.

Sept. 10–12: Porcelain Enamel Institute Forum, Ohio State University, Columbus, Ohio.

Oct. 22-25: 1947 Convention, New York State Association of Architects, Hotel Commodore, New York City.

Oct. 30-Nov. 1: 15th Semi-Annual Meeting, American Society of Tool Engineers, Statler Hotel, Boston, Mass.

Nov. 3-7: 2nd International Lighting Exposition and Conference, Stevens Hotel, Chicago.

Dec. 2-5: Annual Meeting, American Society of Mechanical Engineers, Chalfonte-Haddon Hall, Atlantic City, N. J.

(Continued on page 132)



This man is looking at a convenience outlet. He never knew before how much "convenience" could mean to him. But now that he has changed to General Electric, he has discovered that easy handling, easy installation, and easy replacement give extra meaning to that term. He has learned that this outlet, GE 2679 — and a wide variety of other General Electric wiring devices — have been designed to help make plant wiring less difficult. Plaster ears are included to make mounting simpler. T-slots provide extra leeway in positioning. Durable brown or ivory color body improves appearance, and assures long service. Even more important, a wide range of sizes, types, and capacities allows him to select the proper outlet for any job from a single source of supply.

But the real convenience comes when this man (and thousands like him) mentions the name behind the product — General Electric. It shows his good judgment in the selection of wiring devices. It helps him to be sure that the wiring installed in his plant will give long-term service. And it makes it easy to specify the uniformly high-quality products that are typical of General Electric's full line. Take a tip from this man's experience the next time you order wiring devices from your supplier. Just say G.E., and he'll agree.

WIRING DEVICES by

GENERAL ELECTRIC

say "G.E." and he'll agree

Wiring Briefs from your G-E Distributors

Are you familiar with the great variety of products in General Electric's full line of wiring devices? Do you know the interesting features that help to make them easy to use and safe to specify? Keep an eye on this column, and you may discover a lot of useful facts and information. We'll keep dishing them out for you.

They Stay On The Job Till It's Time To Blow. This slogan tells in a flash why General Electric plug fuses cut your costs for maintenance and replacements. They aren't sissies — these fuses — liable to blow



unnecessarily and keep your repair crews on the run with fresh fuses. On the other hand, when they *should* blow — they *do* blow. Top-quality materials and fine workmanship combine to give outstanding protection — the kind that has made General Electric famous for fuses.

Here's a number that means "switches" to a good many quality-conscious and performance-minded users. It's GE 2841 —

the switch that's built to last. Don't take our word for it alone! Ask anyone who uses this sturdy switch. Our customers are our best salesmen, because they know that no other standard switch can measure up to good old.



GE 2841 in reliability, service, and long life.

Then try them yourself. We think you'll join the GE 2841 fans, too.

Even "cool" lighting sometimes has to operate in hot spots when ambient temperatures are high. That's why the new, high-

temperature rating of General Electric Watch Dog* starters means better operation for your fluorescent installations. Now rated at 160 F (instead of 140 F), Watch Dogs stay on the job to protect ballasts and to cut fail-




ing lamps out of circuits at the first flicker. After relamping, just push the reset button, and it's ready to go to work again.

If you want additional information on these, or other G-E Wiring Devices, ask us — your G.E. Merchandise Distributor — or write to Section D61-75, Appliance and Merchandise Department, General Electric Company, Bridgeport 2, Connecticut.

*Trade-mark Reg. U. S. Pat. Off.

Roddiscraft

The architect's door and plywood



Nationwide Roddiscraft Warehouse Service

Cambridge 39, Mass. . 229 Vassar St.
Chicago 8, III. . 1440 W. Cermak Road
Cincinnati 2, Ohio . . 457 E. Sixth St.
Dallas 10, Texas . . 2800 Medill St.
Deltroit, Mich. . 11855 E. Jefferson Ave.
Kansas City 8, Mo. . 2729 S.W. Blvd.
Louisville 10, Ky. . 1201-5 S. 15th St.

DEALERS IN ALL PRINCIPAL CITIES

architectural profession for more than fifty years. The Roddiscraft hardwood doors and plywood installed in buildings from coast to coast in accordance with architects specifications is a testimony to the reputation of Roddiscraft.


Roddiscraft has earned its reputation — by putting quality first — by never permitting production needs to become paramount.

Today's Roddiscraft solid core flush veneer doors and hardwood plywood are still a craftsman's product - a blending of fine workmanship and fine materials.

Remember - Roddiscraft beauty is more than veneer deep.

Roddiscraft Roddis Lumber & Veneer Co.

MARSHFIELD, WISCONSIN



For most efficient—and most economical—reinforcement...

specify American Welded Wire Fabric

• Efficient, because closely spaced steel members impart distributed strength to all parts of the concrete slab. That means crack control, resistance to stresses and strains in all directions.

Economical, because U·S·S American Welded Wire Fabric is a prefabricated, electrically-welded product, delivered in sheets and rolls. It does not have to be assembled on the job. It can be laid flat or shaped

American Steel & Wire Company

Cleveland, Chicago and New York
Columbia Steel Company, San Francisco, Pacific Coast Distributors
Tennessee Coal, Iron & Railroad Company, Birmingham,
Southern Distributors
United States Steel Export Company, New York

UNITED STATES STEEL

to the forms, stays in place when concrete is poured. It can be used on all types of concrete jobs, large and small. That means that you effect important savings in labor cost and in construction time.







FACTORIES SMALL HOMES







SCHOOLS

SKYSCRAPERS

HOSPITALS

STURDY CONSTRUCTION


... in both lines of Pittco Metal

• In addition to the two bars shown here, the Pittco line of Store Front Metal features a flush-type division bar for use where the architect does not want a protruding surface. It can be used with both the De Luxe and Premier I nes and may be backed up with five different reinforcing members ranging in weight from light to extra heavy. The two bars shown here can be used alone or with reinforcing steel tubes. From this wide selection of sturdy supporting members, architects can easily satisfy all ordinary structural requirements for vertical bars in modern store front work. Where unusual conditions demand special supporting members, our engineers will gladly help in their design.

Pittco Division Bars can meet successfully the most exacting demands of both engineer and designer. They have been planned and produced with the same careful attention to detail that has made both De Luxe and Premier mouldings and sashes so popular with architects and owners who appreciate distinctive, sales-winning store fronts.

All members of the Pittco De Luxe line are formed by the extruded process to assure utmost rigidity, sharp outlines and a satin-smooth finish. Pittco De Luxe is first choice for top quality installations. Pittco Premier is lighter in weight and more moderately priced than its distinguished companion line. It is easier to install than any other metal construction. These practical advantages plus its graceful contours make Pittco Premier ideal when style and economy are of equal importance.


PITTCO STORE FRONT METAL





"PITTSBURGH" stands for Quality Glass and Paint

PITTSBURGH PLATE GLASS COMPANY



Better switch to a Better Switch!

O^{NCE} a safety switch is installed, most everybody takes it for granted, at least until it starts to give trouble.

But one never has to give BullDog Vacu-Break Safety Switches more than a passing glance. These modern switches are designed and built to give long, trouble-free service under heavy use with the absolute minimum of maintenance.

No costly shutdowns on your clients' production lines . . . no delays for expensive switch repairs. Those are the reasons why thousands of architects and plant men

have agreed on BullDog Vacu-Break Switches.

You'll do well to follow their lead by switching to a better switch. There's a BullDog Field Engineer close by to show you BullDog installations near your own office and give you full technical details. Or you can write BullDog direct for descriptive folders. Do it today!

BullDog manufactures Vacu-Break Safety Switches—SafToFuse Panelboards— Superba and Rocker Type Lighting Panels—Switchboards—Circuit Master Breakers—"Lo-X" Feeder BUStribution DUCT—"Plug-in" Type BUStribution DUCT—Universal Trol-E-Duct for flexible lighting—Industrial Trol-E-Duct for portable tools, cranes, hoists.



BULLDOG

ELECTRIC PRODUCTS COMPANY



21

DETROIT 32, MICHIGAN. FIELD OFFICES IN ALL PRINCIPAL CITIES. IN CANADA: BULLDOG ELECTRIC PRODUCTS OF CANADA, LTD., TORONTO

JULY 1947

Where cleanliness is an absolute necessity...



specify Tile-Tex Asphalt Tile for hospital floors!

In hospitals, every unclean or hard-to-clean surface is a potential staging area for dangerous germ carriers. A sanitary surface that can be cleaned readily is consequently a paramount factor in the selection of floors.

One important reason why Tile-Tex Asphalt Tile is commonly specified by hospital architects is because of its outstanding cleanability. This top-quality asphalt tile has a smooth, closely textured surface which does not harbor dirt and is extremely stain-resistant. Normal maintenance methods keep Tile-Tex floors clean and bright at minimum cost.


Important, too, is the tough, asphalt-asbestos composition of Tile-Tex. It means you'll get extra years of wear under heavy traffic conditions. Your staff will enjoy walking and working on this resilient, easy-tread flooring.

All of these factors, plus the decorative possibilities in the wide range of Tile-Tex colors and sizes, have made it a favorite for hospital floors. The approved Tile-Tex contractor in your city will be glad to give you any additional data you may need. Write today for his name and a copy of "Tile-Tex Products for Today's Hospital."





TILE · TEX ASPHALT TILE



SELECTION OF FLOORS FOR MANUFACTURING PLANTS


During recent years there has been an increasing use of specialized resilient floors in all types of factory buildings. In a single factory it is not unusual to find widely different conditions, each of which can be met best with a resilient floor having specific characteristics. Certain factory floor areas must withstand the traffic of heavy rolling loads. In powder and chemical plants, where static electricity presents an explosion hazard, a conductive flooring is required. For floors in factory offices, corridors, and cafeterias it is often desirable to combine durability with attractive appearance.

Resilient floors, as a group, possess the many characteristics required to meet effectively the varying types of factory conditions. Resilient floors are comparatively inexpensive. They can be installed easily and quickly. This is a characteristic of particular importance in reconverting factory buildings, since it causes a minimum interruption to production. Resilient floors are economical to maintain, too. Their smooth surfaces do not catch and retain dust and dirt. And if repairs are ever necessary, they can be made with little trouble. With floors of resilient

tile, for example, repairs can be made simply by substituting new tile for those that become damaged.

Heavy Traffic Areas—For factory areas subjected to heavy rolling loads, industrial asphalt tile is recommended. This flooring material has unusual durability. Its resilience provides underfoot comfort and at the same time offers high resistance to indentation and crumbling. The nonslip surface of industrial asphalt tile makes it suitable for use also on ramps, in freight elevators and other spots that call for heavy duty flooring. The low cost of this material is an obvious advantage, especially when specified for large areas. Industrial asphalt tile is recommended for installation on grade level concrete subfloors as well as on suspended floors. It is not recommended for installation below grade.

Moderate Traffic Areas—In light manufacturing areas and for floors where traffic and wear are not excessive, roll-type flooring with a tough mastic surface, such as Armstrong's Accoflor, has proved to be as satisfactory as industrial asphalt tile. It can be installed either on or above grade and is





In general factory areas, industrial asphalt tile provides a durable, economical floor that's fast trucking, nonslip. Unlike troweled-on types of flooring, industrial asphalt tile can be put into use immediately after it is installed.



For light manufacturing areas, stock rooms, and general utility sections in factories, Accoflor is a durable and economical flooring. A roll form material, its tough mastic composition is bonded to an asphalt-saturated felt backing.



There's unlimited opportunity to design attractive floors for offices with asphalt tile, linoleum, Linotile, or rubber tile. Their smooth, lustrous surfaces are easy to keep clean with simple sweeping and occasional washing and waxing.

suitable for installation in storerooms, wrapping and packing rooms, drafting rooms, and locker rooms. This type of flooring is low in cost. And its thermoplastic property makes minor dents and cuts self-healing under traffic.

Overcoming Explosion Hazards—In powder or chemical plants and other places where combustible fumes or liquids are present, there is a need to dissipate static electricity. A floor of conductive asphalt tile does that job effectively since it has exceptionally low electrical resistance. Conductive plastic can be used in the joints to connect the tile, or the seams can be welded together to provide a monolithic surface. While a conductive flooring is desirable in paint spray booths, its conductivity is destroyed if a coating of paint or lacquer accumulates on the surface of the floor.

Traffic Markers—Insets and feature strips in various colors of standard and greaseproof asphalt tile are often used, in combination with other resilient flooring, to mark off traffic lanes and safety zones. Letters and numerals in standard asphalt tile also make it easy to establish permanently stock areas and production sections.

Offices and Corridors—Where color and design are desired and where heavy industrial wear is not encountered—in offices, corridors, display rooms, cafeterias, and other areas—such resilient floors as linoleum, asphalt tile, Linotile, and rubber tile should be considered. If cost is of primary importance, a choice can be made between asphalt tile and linoleum. While Linotile and rubber tile are more luxurious in appearance, their costs are correspondingly greater.

On-Grade and Subgrade Floors—Floor areas on or below grade present the problems of moisture and alkali. Industrial asphalt tile, conductive asphalt tile, and Accoflor are recommended for installation

on grade level concrete subfloors. Standard and greaseproof asphalt tile are the only types of resilient flooring recommended for below grade installation since these products have the ability to withstand the greater degree of alkaline moisture encountered here.

* * *

If you have a specific problem in recommending floors for factories and industrial plants, or desire further information on any Armstrong flooring material, write to Armstrong Cork Company, Floor Div., 2407 State St., Lancaster, Pa.

PLANT AREAS	ASPHALT TILE	ASPHALT TILE	ACCOFLOR	ASPHALT TILE	GREASEPROOF ASPHALT TILE	LINOLEUM, LINOTILE, RUBBER TILE
BASEMENTS & FLOORS BELOW GRADE			1	x	×	
CAFETERIAS	x		x	x	×	×
FOOD PROCESSING AREAS					x	
DRAFTING ROOMS			×	×		x
EXPLOSION— HAZARDOUS AREAS	x	x				I est
FREIGHT ELEVATORS	X				1	
LABORA- TORIES	×			×	×	
RAMPS	×					
LOCKER ROOMS, WASHROOMS	×		×	x		x
MANUFACTURING AREAS	x		x			
OFFICES, CORRIDORS			x	x		×
STAIR TREADS & LANDINGS	x			x		×
TOOL AND STOCK ROOMS	×		x	*.		
WAREHOUSES, SHIPPING AREAS	X					

ACCOFLOR AND LINOTILE ARE REGISTERED TRADE-MARKS



MONITOR TYPE ROOF VEN-TILATOR - 24" wide throat dimensions in any length.



VENT FLUE CAP-Available




SQUARE TYPE ROOF VENx 123" throat dimensions

Roof Ventilators Vent Flue Caps

One of our first steps before designing AIRJETS was to ascertain preferences of Architects and Engineers regarding natural draft ventilators.

Here is what we found predominant throughout the profession:



SEND FOR COMPLETE INFORMATION

A few territories still available for Exclusive Franchise Dealers

C. R. GELERT COMPANY 35 North Raymond Avenue Pasadena 1, California

Please send me your new catalog No. 446 on Airjet Roof Ventilators and Vent Flue Caps.

STATE

NAME

COMPANY

ADDRESS.

ZONE

HIGH EFFICIENCY WITHOUT DOWN-DRAFT

-so we designed AIRJETS to create a "jet of air" efficiently without down-drafts regardless of wind direction or turbulence caused by obstructions. Certified tests by California Institute of Technology guarantee this fact.

LOW SILHOUETTE-so we designed AIRJETS to conform to modern day architecture-low, modern, streamlined. AIRJETS never exceed 22" in height. Transition bases are never needed. AIRJET vent flue caps work 12" from roof regardless of obstructions. Largest unit weighs only 29 pounds in aluminum.

MODERATE COST-so we "machine-make" AIRJETS in VOLUME-THEY ARE THE LOWEST COST UNITS ON THE MARKET-Make us prove it. Certified tests prove they are the lowest cost per cubic foot of air moved. Comparative unit and installation costs prove AIRJETS most economical. AIRJETS eliminate insufficient ventilation by reason of costs!

> THESE UNITS AVAILABLE IN ALUMINUM-NOW! SOLD KNOCKED-DOWN AND PACKAGED!

> > MANUFACTURED BY

35 North Raymond Avenue, Pasadena I, California

CONSTRUCTION COST INDEXES

Labor and Materials

United States average 1926—1929 = 100

Compiled by Clyde Shute, manager, Statistical and Research Division, F. W. Dodge Corporation, from data collected by E. H. Boeckh & Associates, Inc.

NEW YORK

ATLANTA

	Resid	lential	Apts., Hotels, Office Bldgs. Brick and			Resid	lential	Apts., Hotels, Office Bldgs. Brick and	Fac	nercial nd tory dings Brick and
Period	Brick	Frame	Concr.	Concr.	Steel	Brick	Frame	Concr.	Concr.	Steel
1920	136.1	136.9	123.3	123.6	122.6	122.8	122.9	108.6	109.8	105.7
1925	121.5	122.8	111.4	113.3	110.3	86.4	85.0	88.6	92.5	83.4
1930	127.0	126.7	124.1	128.0	123.6	82.1	80.9	84.5	86.1	83.6
1935	93.8	91.3	104.7	108.5	105.5	72.3	67.9	84.0	87.1	85.1
1939	123.5	122.4	130.7	133.4	130.1	86.3	83.1	95.1	97.4	94.7
1940	126.3	125.1	132.2	135.1	131.4	91.0	89.0	96.9	98.5	97.5
1941	134.5	135.1	135.1	137.2	134.5	97.5	96.1	99.9	101.4	100.8
1942	139.1	140.7	137.9	139.3	137.1	102.8	102.5	104.4	104.9	105.1
1943	142.5	144.5	140.2	141.7	139.0	109.2	109.8	108.5	108.1	108.7
1944	153.1	154.3	149.6	152.6	149.6	123.2	124.5	117.3	117.2	118.2
1945	160.5	161.7	156.3	158.0	155.4	132.1	133.9	123.2	122.8	123.3
1946	181.8	182.4	177.2	179.0	174.8	148.1	149.2	136.8	136.4	135.1
Jan. 1947	195.4	198.0	183.9	186.2	183.0	161.9	164.2	145.7	147.1	145.8
Feb. 1947	204.7	208.9	194.7	193.5	191.1	165.8	166.8	148.8	149.9	148.8
Mar. 1947	211.2	217.2	196.2	194.4	192.9	178.7	182.9	153.4	152.0	153.1
Apr. 1947	217.6	220.8	204.7	205.9	202.4	179.2	183.3	154.4	153.5	153.5
			ease ove					ease ove		
Apr. 1947	76.2	80.3	51.6	54.3	55.5	107.7		62.3	57.6	62.0
		ST	. LOI	JIS		S	ANF	RAN	CISC	0
1920	118.1	121.1	112.1	110.7	113.1	108.8	107.5	115.2	115.1	122.1
1925	118.6	118.4	116.3	118.1	114.4	91.0	86.5	99.5	102.1	98.0
1930	108.9	108.3	112.4	115.3	111.3	90.8	86.8	100.4	104.9	100.4
1935	95.1	90.1	104.1	108.3	105.4	89.5	84.5	96.4	103.7	99.7
1939	110.2	107.0	118.7	119.8	119.0	105.6	99.3	117.4	121.9	116.5
1940	112.6	110.1	119.3	120.3	119.4	106.4	101.2	116.3	120.1	115.5
1941	118.8	118.0	121.2	121.7	122.2	116.3	112.9	120.5	123.4	124.3
1942	124.5	123.3	126.9	128.6	126.9	123.6	120.1	127.5	129.3	130.8
1943	128.2	126.4	131.2	133.3	130.3	131.3	127.7	133.2	136.6	. 136.3
1944	138.4	138.4	135.7	136.7	136.6	139.4	137.1	139.4	142.0	142.4
1945	152.8	152.3	146.2	148.5	145.6	146.2	144.3	144.5	146.8	147.9
1946	167.1	167.4	159.1	161.1	158.1	159.7	157.5	157.9	159.3	160.0
Jan. 1947	183.4	183.8	168.5	169.3	169.5	173.2	170.8	167.3	169.4	172.5
Feb. 1947	187.6	187.0	173.9	175.2	172.8	177.0	173.9	172.4	174.6	176.1
Mar. 1947	196.9	198.9	175.8	176.4	175.3	185.6	184.9	174.2	175.7	178.4
	190.9	200.3	178.0	179.0	176.9	188.6	187.0	177.8	180.4	180.7
Apr. 1947	177.1				170.7	100.0		ease ove		100.7
	00 /	, -	ease ove		40 /	70 /	, -			
Apr. 1947	80.6	87.1	49.9	49.5	48.6	78.6	88.4	51.4	48.0	55.1

The index numbers shown are for combined material and labor costs. The indexes for each separate type of construction relate to the United States average for 1926–29 for that particular type — considered 100.

Cost comparisons, as percentage differences for any particular type of construction, are possible between localities, or periods of time within the same city, by dividing the difference between the two index numbers by one of them; i.e.:

index for city A = 110 index for city B = 95

(both indexes must be for the same type of construction).

Then: costs in A are approximately 16 per cent higher than in B.

$$\frac{110-95}{95} = 0.158$$

Conversely: costs in B are approximately 14 per cent lower than in A.

$$\frac{110-95}{110} = 0.136$$

Cost comparisons cannot be made between different types of construction because the index numbers for each type relate to a different U. S. average for 1926–29.

Material prices and wage rates used in the current indexes make no allowance for payments in excess of published legal prices, thus, indexes reflect minimum costs and not necessarily actual costs.

These index numbers will appear whenever changes are significant.

REQUIRED READING

LE CORBUSIER AND THE U. N.

U.N. Headquarters: Practical Application of a Philosophy of the Domain of Building. By Le Corbusier. New York 18 (330 W. 42nd St.), Reinhold Publishing Corp., 1947. 7¼ by 9½ in. 80 pp. illus. \$3.50.

Here is Le Corbusier's inimitable philosophy of city planning applied to the problems of where and how to house the United Nations. M. Le Corbusier will have none of the term "world capital"; that, he says, is an expression which is "nothing but ambiguity, equivocation, uncertain dimensions, emphasis, and artificial acceptance. It is a source of error, bloated with false deductions. One has a vision of this capital burdened at the outset by the construction of a palace necessarily pompous. . . Sublime contours confirm its pretensions."

This is a discussion of the U.N.'s long search for a suitable site for its permanent headquarters. Here is a list of 13 "points of evaluation," drawn up by Le Corbusier, according to which every site considered was inadequate. Here is Le Corbusier's skillful argument that the entire U.N. could be adequately housed on a single square mile, and here is his description of what the headquarters should be like. Finally, here is the story of the eruptive decision for

a mid-Manhattan 17-acre site.

Le Corbusier, of course, was a member of the committee which for seven months looked, analyzed, discussed and theorized, which had the responsibility of reporting and recommending to the General Assembly prior to the vote on the several sites under consideration. This book, therefore, is in part a record of the proceedings, in that it is a summary of Le Corbusier's own arguments throughout the life of the committee. Presented chronologically, enlivened with numerous sketches, these arguments will be of lasting interest.

At the closing session of the Permanent Headquarters Committee Le Corbusier addressed his confrères: "Our decision was taken in 24 hours - and these 24 hours, set against the seven months of our former studies, startled many minds. But, what had actually happened was that the hour of the men of the profession, indeed the very hour of modern architecture, had come. . . Modern techniques furnish the solution for the urbanization of contemporary cities by establishing and maintaining values through the use of height." The East River headquarters, M. Le Corbusier said, will not be the cradle for the United Nations, but will be its "Battle-Post" - "a post comprising offices and meeting halls which

will thus be situated at the very focus of the great international arteries," which "should compel the formation of an integrated organism capable of fulfilling what you are setting out to do and controlling the functions of this organism to this end."

CAPITAL IN THE

MAKING

Thomas Jefferson and the National Capital: Notes and Correspondence. Edited by Saul K. Padover. Washington 25, D. C., Government Printing Office, 1946. 61/4 by 91/2 in. xxxvi + 522 pp. illus. \$1.75.

The part that Jefferson played in the building of the nation's capital has been much written about, but no previous volume has given so vivid a picture of his city-planner role as does this collection of letters and notes, many of them hitherto unpublished. Here are letters from Jefferson to Washington, to Madison, L'Enfant, Latrobe, and many others, and letters to Jefferson from them, dating from November, 1783 to April, 1818. Dating, in other words, from before the choice of a site for the proposed "Federal City" had been made to the selection of furniture for the "President's House."

The Jefferson who emerges from these letters and notes is a city planner of no mean ability. Having negotiated the choice of the Potomac site for the new city, he proceeded to lay down the basic needs and the general plan, then directed much of the entire project from the surveying to the landscaping.

As Charles W. Porter points out in his introduction to this volume, these letters show "how the education and experience of Jefferson ideally equipped him for many phases of city planning work." Before he was through with the building of Washington he had displayed and used a knowledge of surveying, a familiarity with the city plans of a number of European cities, legal training, a considerable knowledge of architecture and the fine arts, a good mechanical bent, innate tact and diplomacy and good taste. His letters constantly reveal the extent of his knowledge and the many facets of his character and often brilliant mind.

When Major L'Enfant needed plans of European capitals, it was Jefferson who supplied them: "I have examined my papers," he wrote, "and found the plans of Frankfort on the Mayne, Carlsruhe, Amsterdam, Strasburg, Paris, Orleans, Bordeaux, Lyons, Montpelier, Marseilles, Turin, and Milan, which I send in a roll by this Post. They are on large and accurate scales, having been procured by me while in those respective cities myself." When skilled

labor had to be imported from Europe, it was Jefferson who advised how best to go about it. It was Jefferson who straightened out financial tangles, who soothed wounded feelings, who served so often as the court of last appeal. This is the story told in these letters — history in the first person.

DREAMS INTO REALITY

How to Buy a House. By L. Douglas Meredith. New York 16 (49 E. 33rd St.), Harper & Brothers, 1947. 5½ by 8½ in. xii + 176 pp. \$2.50.

Of all the books on home ownership which have appeared in the past several years, this is likely to be one of the most useful in preventing foreclosures and heartaches. Dr. Meredith, as chairman of the National Life Insurance Company's committee on finance, is well acquainted with the pitfalls of home buying. He sees them for what they usually are — lack of knowledge or lack of foresight. His purpose here is to uncomplicate the whole procedure for the prospective purchaser, not to warn him away from the venture.

Dr. Meredith wastes little time on the usual preliminaries, devoting only four chapters to such subjects as whether to buy or to rent, new house or old, the needs of the family, the location, price, etc. His main theme, and the whole reason for this book, is the fool-proofing of the purchase. Go easy, he warns; be sure you are buying exactly the house you want; then arrange the financing in the way best suited to your requirements. Here Dr. Meredith is at his best. He describes in detail the various types of loans available, the types of lender, the terms. He explains the incidental and not always foreseen charges, he explains interest, insurance, deeds, the technicalities of title search, and so on, He tells how the construction of a new house can be financed. He stresses the need for a good architect. He gives, in other words, all the information the prospective home buyer should have.


TOWARD A BETTER LIFE

Communitas: Means of Livelihood and Ways of Life. By Percival and Paul Goodman. Chicago, Ill. (5750 Ellis Ave.), The University of Chicago Press, 1947. 11 by $8\frac{1}{2}$ in. x+142 pp. illus. \$6.00.

"This is not a book of physical plans, but of issues and ideas," the authors explain in their preface. Architect Percival and writer Paul have combined their talents "to raise the level of thinking about physical planning and once more to bring the fundamental issues to the fore." They are critical, they are very serious, they are idealistic, they are a little radical, they are sometimes sarcastic. But they do bring the fundamental issues to the fore.

This is a deliberately disturbing book.

(Continued on page 30)



PRESSURE - CREOSOTED
PILES


A common problem—providing a firm, enduring foundation in unstable soils—faced the designers of this large industrial building. To solve it, they chose a pile material whose permanence and economy have been conclusively demonstrated in thousands of applications—pressure-creosoted wood.


Koppers Pressure-creosoted piles were driven in the wall trench, and under the floor area. These multiple supports eliminate settling hazards. The treatment gives enduring protection against decay, permitting cut-offs above the water table to be safely made. It also fortifies the piles against insect attack.

The permanence of pressure-creosoted piles is demonstrated by the old buildings founded on them . . . and present-day economy and effectiveness are indicated by the many modern buildings that use this proven method of overcoming soil handicaps. Koppers Pressure-creosoted piles permit economical development of areas where water tables are below pile cut-offs.

They provide adequate bearing value in constructing foundations for heavy bridges or machinery. And they are an accepted means of equalizing support when part of the building is over filled or soft ground.

Koppers is equipped to treat piles up to 125 feet in length, and the delivery situation is excellent. If you have a foundation problem, get in touch with Koppers.





PRESSURE-TREATED WOOD

KOPPERS COMPANY, INC

PITTSBURGH 19, PENNSYLVANIA

Fewer resharpenings with MICROTOMIC VAN DYKE

exclusive rectangular shape Chisel Point Leads

Think of the better work you can do, particularly on big-scale plans and drawings. The efficient rectangular lead sharpens with 20% more graphite at its chisel point — and wears just that much longer.

It's the same HI-DENSITY graphite that gives roundlead VAN DYKES their great advantage in reproduction quality. Extra opacity for sharper, clearer points.

The special Chisel Point Leads come in 6H, 4H, 2H, HB, 2B and 4B. Clip the coupon, and try one!

I'd like to experiment with a FREE SAMPLE __degree Chisel Point VAN DYKE.

N	~	m	-		
	ч		•	-	

Street & No ...

City & State_

Dealer's Name_

REQUIRED READING

(Continued from page 28)

It discusses any number of city plans and finds them all bad. It rips into the American standard of living, finds America badly wanting in the amenities of life. It dissects, it criticizes. And,

finally, it suggests.

The suggestions are painted in with broad, bold strokes. Take, for instance, the idea of substituting for the many buildings of a city one gigantic "container," a cylinder a mile in diameter, whose corridors are continuous show windows, whose perimeter is given over to hotels and restaurants. Surrounding this cylinder is a mile-wide ring containing the "university" - the theaters, opera houses, museums, libraries, laboratories, etc. Next comes a residential zone, arranged in blocks of about 4000 population, in a continuous apartment house around an open space of 500 by 1000 feet. Here "space" is rented instead of apartments; each tenant takes his own area and develops it as he wishes: "what must be provided for the family is an empty shell without partitions and (under luxury conditions) two stories high, completely serviced with light, heat, water, etc., through the columns of the building, as in a sky-scraper." And beyond the residential area comes a zone of open country in which are located the junior colleges to segregate the adolescents!

This city plan, be it noted, is not seriously presented. It is radical, probably impossible of achievement. But that is the point the Goodmans are making: that city planning must be bold, that city planners of the antimacassar variety will get nowhere. Tradition, say the Goodmans, can have no place in plan-

ning for the city of tomorrow.


EBERHARD FABER.

(♦)"VAN DYKE"

SCHOOL DAYLIGHTING

Daylight in School Classrooms. By Hugh Paul. Toledo 1, Ohio (Ohio Bldg.), Insulux Products Division, Owens-Illinois Glass Co., 1947. 81/2 by 11 in. 74 pp. illus. Gratis.

The stated purpose of this book is "to promote a better understanding of the use of daylight and to provide a method for introducing daylight into classrooms to obtain maximum efficiency with minimum brightness contrast regardless of weather conditions and building orientation." To achieve this dual purpose, the author has assembled detailed performance data on a lightdirectional fenestration for school classrooms, and has evolved a formula and tables for applying the data to rooms of all sizes and lighting conditions. Diagrams are numerous and clear. Considerable meteorological information, charts and tables are included for easy computation of the brightness conditions to be expected in any given locality.



Here's a Newer, Better Way to Partition or Panel BUILDINGS

By use of a few standardized parts and fittings, M/P Methwals meet every wall paneling and partitioning requirement . . . eliminate the need for plaster in new construction . . . and permit fast, clean, simple installation in dividing space. They combine rich beauty, quiet and fire resistance with low initial cost and permanent economy.

Pre-Fabricated . . . Pre-Decorated

Made in lifelike wood grains and soft color finishes . . . providing an all-flush surface from floor to ceiling . . . eliminating the need for filler boards of other materials at ends or above the cornice level . . . M/P Metlwals of Bonderized steel make possible an endless variety of new, modern decorative effects. And you can use these distinctive interiors for executive, factory and general offices, stores, banks, theatres, hotels, hospitals, schools, residences and other buildings of every kind.

Write or Phone For Demonstration

The nearest M/P Distributor listed at the right is ready to give you a 10-minute demonstration of the unique features of M/P Metlwals. Write or phone him today. Also, for your A. I. A. file, send for booklet No. 35-H-6, containing Metlwal specifications, drawings and installation photographs. Address: Martin-Parry Corporation, Fisher Bldg., Detroit 2, Michigan. Plants: Toledo, Ohio; York, Pennsylvania.






YOUR M/P DISTRIBUTOR

BirminghamAcousti Engineering Co.
MobileAcoustics & Specialties Co. ARKANSAS
CALIFORNIA Los AngelesThe Harold E. Shugart Co.
Oakland SacramentoF. K. Pinney, Inc.
San Francisco)
DenverLauren Burt, Inc.
CONNECTICUT
DELAWARE
Wilmington (Eastern Shore) The W. M. Moyer Co. DISTRICT OF COLUMBIA WashingtonJohn H. Hampshire, Inc. FLORIDA
WashingtonJohn H. Hampshire, Inc.
Jacksonville I Acousti Engineering Co.
Miami of Fla. PensacolaAcoustics & Specialties Co.
GEORGIA
ILLINOIS
Decatur
Evansville Ft. Wayne Hugh I Boton & Co
Indianapolis [nugn J. baker & Co.
Wabash KENTUCKY
LouisvilleE. C. Decker & Co.
New Orleans Acoustics & Specialties Co.
PortlandPitcher & Co.
BostonPitcher & Co. SpringfieldThe C. A. Bader & Co., Inc. MICHIGAN
Detroit
minieaponsinsulation Sales Co., Inc.
MISSOURI
St. Louis
NEW JERSEY ElizabethJacobson & Co. TrentonThe W. M. Moyer Co.
Trenton The W. M. Moyer Co.
Albuquerque The Jay Grear Corp.
Albany) NEW YORK
Albany Buffalo
Albany Buffalo Jamestown RochesterCollum Acoustical Co.
Albany Buffalo Jamestown Rochester Syracus
Albany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co.
Albany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas
Alhany Buffalo Jamestown Rocliester Syracuse New York City
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Supply Co.
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Unioninati
Alhany Buffalo Jamestown Rochoster Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Cincinnati Jumply Co. E. C. Decker & Co.
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA Charlotteof the Carolinas OH10 Cleveland Columbus Toledo Cincinnati Dayton Altoona Altoona Altoona
Alhany Buffalo Jamestown Rochester Syracuse New York Charlotte
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteSounti Engineering Co. of the Carolinas OH10 Cleveland Columbus Toledo Cincinnati Dayton Altoona Pittsburgh Sharon Harrisburgh Harrisburgh Harrisburgh Harrisburgh Harrisburgh Harrisburgh Harrisburgh Harrisburgh Harry C. Leezer Co. Philadelphia The W. M. Mover Co.
Alhany Buffalo Jamestown Rochoster Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteOf the Carolinas Of
Alhany Buffalo Jamestown Rochoster Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteOf the Carolinas Of
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Clincinnati Dayton Altoona Altoona PENNSYLVANIA Pittsburgh Sharon Harrisburg Philadelphia Scranton RHODE ISLAND Providence. SOUTH CAROLINA Co.
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Cincinnati Dayton Altoona Pittsburgh Sharon Harrisburgh Sharon Harrisburgh Harry C. Leezer Co. RHODE ISLAND Providence. SOUTH CAROLINA CharlestonAcoustic Engineering Co. of the Carolinas
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OH10 Akron Cleveland Columbus Toledo Cincinnati Dayton PENNSYLVANIA Altoona Pittsburgh Sharon Harrisburgh Harry C. Leezer Co. Sharon Harrisburgh Harry C. Leezer Co. Scranton RHODE ISLAND Providence. SOUTH CAROLIPItcher & Co. South Carolipitcher & Co. CharlestonAcoustic Engineering Co. of the Carolina SOUTH DAKOTA Sioux FallsInsulation Sales Co., Inc.
Alhany Buffalo Jamestown Rochoster Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteJacobson & Co. Of the Carolinas OHIO Akron Cleveland Columbus Toledo Cincinnati Dayton Altoona PENNSYLVANIA Altoona Pittsburgh Sharon Harrisburgh Sharon Harrisburgh Scranton RHODE ISLAND Providence SOUTH CAROLINA CharlestonAcoustic Engineering Co. Of the Carolinas South Dakon Pitcher & Co. SOUTH CAROLINA South Carolinas South Dakon South Dakota Sioux FallsInsulation Sales Co., Inc. TENNESSEE
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Cincinnati Dayton Altoona PENNSYLVANIA Harry C. Leezer Co. Sharon Harrisburgh Philadelphia Scranton RHODE ISLAND ProvidenceOHIO CharlestonAcoustic Engineering Co. of the Carolinas SOUTH CAROLINA CharlestonOf the Carolinas SOUTH DAROTA Sioux FallsInsulation Sales Co., Inc. TENNESSEE Knoxville Len Herndon Co.
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Cincionati Dayton Altoona PENNSYLVANIA Harry C. Leezer Co. Sharon Harrisburg Philadelphia Scranton RHODE ISLAND ProvidenceAcoustic Engineering Co. of the Carolinas SOUTH CAROLINA CharlestonAcoustic Engineering Co. of the Carolinas SOUTH DA KOTA Sioux FallsInsulation Sales Co., Inc. TENNESSEE Chattanooga Knoxville MemphisAcoustics & Specialties Co. TEXAS
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Cincionati Dayton Altoona PENNSYLVANIA Harry C. Leezer Co. Sharon Harrisburgh Philadelphia Scranton RHODE ISLAND ProvidenceAcoustic Engineering Co. of the Carolinas SOUTH CAROLINA CharlestonAcoustic Engineering Co. of the Carolinas SOUTH DA KOTA Sioux FallsInsulation Sales Co., Inc. TENNESSEE Chattanooga Knoxville Mashville MemphisAcoustics & Specialties Co. TEXAS Dallas HOUSTON S. W. Nichols Co.
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OHIO Akron Cleveland Columbus Toledo Cincinnati Dayton Altoona PENNSYLVANIA Harry C. Leezer Co. PENNSYLVANIA Harrisburgh Harrisburgh Philadelphia Scranton RHODE ISLAND ProvidenceAcoustic Engineering Co. of the Carolinas SOUTH CAROLINA CharlestonAcoustic Engineering Co. of the Carolinas SOUTH DAROTA Sioux FallsInsulation Sales Co., Inc. TENNESSEE Chattanooga Knoxville MemphisAcoustics & Specialties Co. TEXAS Dallas Houston S. W. Nichols Co. San Antonio S. W. Nichols Co. San Antonio S. The Jay Grear Corp.
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteAcousti Engineering Co. of the Carolinas OH10 Akron Cleveland Columbus Toledo Cincinnati Dayton Altoona Pittsburgh Sharon Harrisburg Scranton RHODE ISLAND Providence. SOUTH CAROLIPItcher & Co. South Carolipitcher & Co. South Carolipitcher & Co. South Carolipitcher South Carolipitcher Knoxville Nashville Nas
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteMid-West Acoustical & OHIO Cleveland Columbus Toledo Cincinnati Dayton Altoona Pittsburgh Sharon Harrisburgh Harry C. Leezer Co. SharlestonAcoustic Engineering Co. Of the Carolinas OHIO Concinnati Columbus Toledo Cincinnati Dayton PENNSYLVANIA Altoona Pittsburgh Harry C. Leezer Co. Sharon Harrisburgh Harry C. Leezer Co. Sharon Harrisburgh Harry C. Leezer Co. SOUTH CAROLINA CharlestonAcoustic Engineering Co. Othe Carolinas SOUTH DA KOTA Sioux FallsInsulation Sales Co., Inc. TENNESSEE Chattanooga Knoxville Nashville MemphisAcoustics & Specialties Co. TENNESSEE Chattanooga Knoxville MemphisS. W. Nichols Co. San Antonio EI PasoThe Jay Grear Corp. UTAH Salt Lake City. VIRGINIA
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteMid-West Acoustical & OHIO Cleveland Columbus Toledo Cincinnati Dayton Altoona Pittsburgh Philadelphia Scranton RHODE ISLAND Providence. SOUTH CAROLINA CharlestonAcoustic Engineering Co. ACOUSTIC Engineering Co. TENNSYLVANIA CharlestonAcoustic Engineering Co. ACOUSTIC Engineering Co. OHIO CharlestonAcoustic Engineering Co. ACOUSTIC Engineering Co. TENNESSEE Chattanooga Knoxville Nashville
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteMid-West Acoustical & Of the Carolinas OHIO Cleveland Columbus Toledo Cincinnati Dayton PENNSYLVANIA Altoona Pittsburgh Sharon Harrisburgh Harry C. Leezer Co. SharlestonAcoustic Engineering Co. Of the Carolinas OHIO Columbus Toledo Cincinnati Dayton PENNSYLVANIA Altoona Pittsburgh Harry C. Leezer Co. Sharon Harrisburgh Harry C. Leezer Co. SOUTH CAROLINA CharlestonAcoustic Engineering Co. Of the Carolinas SOUTH DA KOTA SIOUX FallsInsulation Sales Co., Inc. TENNESSEE Chattanooga Knoxville MemphisAcoustics & Speciatties Co. TENNESSEE Chattanooga Knoxville MemphisS. W. Nichols Co. San Antonio El PasoThe Jay Grear Corp. UTAH Salt Lake CityLauren Burt, Inc. WEST VIRGINIA
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA Charlotte
Alhany Buffalo Jamestown Rochester Syracuse New York City
Alhany Buffalo Jamestown Rochester Syracuse New York CityJacobson & Co. NORTH CAROLINA CharlotteMid-West Acoustical & Cleveland Columbus Toledo Cincinnati Dayton PENNSYLVANIA Altoona Pittsburgh Sharon Harrisburgh Harry C. Leezer Co. RHODE ISLAND Providence. SOUTH CAROLINA CharlestonAcoustic Engineering Co. of the Carolinas SOUTH CAROLINA CharlestonThe W. M. Moyer Co. SOUTH CAROLINA CharlestonThe W. M. Moyer Co. SOUTH CAROLINA CharlestonAcoustic Engineering Co. of the Carolinas SOUTH CAROLINA Coustic Engineering Co. of the Carolinas SOUTH CAROLINA Coustic Engineering Co. of the Carolinas SOUTH CAROLINA Coustic Engineering Co. The Larolinas SOUTH DAKOTA SIOUX FallsInsulation Sales Co., Inc. TENNESSEE Chattanooga Knoxville MemphisAcoustics & Speciatties Co. TEXAS Acoustics & Speciatties Co. TEXAS Lauren Burt, Inc. WIRGINIA HuntingtonE.C. Decker & Co. Clarksburg Wheeling WISCONSIM
Alhany Buffalo Jamestown Rochester Syracuse New York City

They send and to the cleaners instead of the merchandise



*Name furnished on request

SOOT and smoke were taking a heavy toll of merchandise in this large Southern department store.* To combat soilage and resultant mark-downs, a complete dry cleaning plant was installed which reduced losses materially.

Then they tackled the basic problem—elimination of atmospheric dust and dirt. Fully automatic, self-cleaning, electronic air filters were included as part of a new store-wide air conditioning system. The results were soon apparent. Soilage was reduced to a point where it was no longer economical to operate the dry cleaning plant; the need for frequent redecoration was eliminated; and store cleaning costs were cut appreciably.

Dust-laden air is the source of many product, processing and personnel problems that can be solved effectively by the right type air filters. Are your clients aware of the advantages of clean air and how it can be best obtained? If not, you will be doing them a lasting service to acquaint them with American Air Filters. Write today for your file on AAF equipment. There's a type and size to meet every requirement.

AMERICAN AIR FILTER CO., INC.

389 Central Ave., Louisville 8, Ky.

In Canada: Darling Bros. Ltd., Montreal, P. Q.



AIR FILTERS
AND DUST CONTROL EQUIPMENT




CRANE

CRANE CO., GENERAL OFFICES: 836 S. MICHIGAN AVE., CHICAGO 5

PLUMBING AND HEATING VALVES • FITTINGS • PIPE

NATION-WIDE SERVICE THROUGH BRANCHES, WHOLESALERS, PLUMBING AND HEATING CONTRACTORS



These roomy, attractive brick homes are part of a 114-house project being constructed at Sharon Hill, Pa., by Donald M. Love, Contractor, of Norwood, Pa. They were designed by S. Arthur Love, Jr., also of Norwood.

They have basements; two bedrooms, bath, kitchen, and combination living-and-dining room on the first floor; two bedrooms and bath on the second floor. Bethlehem Open-Web Joists are used in the floor construction of both the first and second floors.

Excellent for all types of light-occupancy structures because they eliminate shrinking and sagging, as well as open baseboards and squeaky floors, Bethlehem Open-Web Joists also go a long way toward making structures fire-safe. For when used with concrete floorslab and plaster ceiling, they provide a floor construction that prevents the spread of fire for at least two hours. They're also resistant to the passage of sound,

and they speed and simplify construction, as pipes, conduits and ducts can easily be run through the open webs.

Bethlehem Open-Web Joists come completely fabricated, ready for use without falsework. Two men can handle the standard Bethlehem joist. And the Longspan type of joist can be raised into place by means of a light gin pole.

If you are planning to design with open-web joists, it will pay you to have our new 36-page joist catalog on hand for reference. It gives design data and other important details, and shows typical installations. For your copy, contact the nearest Bethlehem district office, or write us at Bethlehem, Pa.


BETHLEHEM STEEL COMPANY, BETHLEHEM, PA.


On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation



* BETHLEHEM OPEN-WEB JOISTS









BRYANT DEVICES BRING ELECTRICAL LIVING

Outdoors

The out-of-doors has become the new "living room" in this age of electrical living. To provide adequate electrical service that will be unaffected by storms, heat or cold, Bryant weatherproof devices assure dependable, year 'round service.

For example, the Bryant 4421 line of flush tumbler switches is fully protected from moisture by a weatherproof rubber mat and a cadmium-finish brass plate. It is ideal for lighting control on porches, terraces and other exposed locations. "T" rated, it is available in single-pole, double-pole, three-way and fourway types.

FOR CONVENIENCE USE

When weatherproof convenience outlets are required for outdoor use, these three Bryant devices will answer every need. Bryant 3795 outlet has T slots and a thread-on cover. Recommended for use with this outlet is the Bryant metal cap cover 3797 equipped with a rubber bushing to make a weathertight seal for full safety in bad weather conditions. The popular Bryant 3880 for two-wire service has a quick-clamp cover that needs only a quarter turn to expose the receptacle.

BRYANT 3880 WEATHERPROOF OUTLET

BRIDGEPORT 2, CONNECTICUT
NEW YORK · CHICAGO · LOS ANGELES

SUPERIOR WIRING DEVICES

BRYANT 3797

WEATHERPROOF CAP COVER

GOOD WORKMANSHIP is EASY with BRIXMENT

Study the pictures below and you'll see the contrast between the usual head joint and a full head joint. . . . It is hard to get full head joints, of uniform width, unless the mortar is so soft and workable that it will ooze up out of the head joint. Brixment mortar is so rich and plastic that the bricklayer can use more than enough mortar to fill the head joint, and still "place" the brick easily and accurately.

Brixment mortar has greater plasticity, higher water-retaining capacity and bonding quality, greater resistance to freezing and thawing, and freedom from efflorescence. Because of this combination of advantages, Brixment is the leading masonry cement on the market. Louisville Cement Company, Incorporated, Louisville, Ky.

No. 3 OF A SERIES-

THE RIGHT WAY AND THE WRONG WAY-IN HEAD JOINTS





The brick should then be pushed into place



All head joints in both face brick and back-up work should be completely filled with mortar. One good method for doing this is to throw plenty of mortar on the end of the brick to be placed. (This should be done in such a way that the mortar is scraped off the trowel by the bottom edge of the end of the brick.) Then push the brick into place so that the mortar oozes out at the top of the head joint.







Only part of the head joint is filled with mortar.

If the head joints are not completely filled with mortar, in both face brick and back-up work, water may penetrate to the inside of the wall through openings in the joints.

A dab of mortar spotted on one corner of the brick is not nearly enough to fill the head joint.

INSTALLATION TIME REDUCED 50% to 80%

With Douglas Fir

PRE-FIT

Stock Doors

Save Time—Save Labor—and Get a Better Job . . . with These Improved Fir Doors!

NE BUILDER reports as many as seven installations in the time previously required for a single door! Savings of from 50% to 80% are common.

That's because Douglas fir stock doors are pre-fit to exact size at the factory. They reach the job trimmed and squared, ready to hang. No sawing or planing is required. Precious time is saved - and there's far less danger of on-the-job marring, "butchering" and poor alignment due to unskilled help or improper tools. Corners are clean, trim, true - scuff-stripped for protection. The result: a better, as well as a faster, job!

and PRE-SEALED, too,

for Protection and Better Finish

Douglas fir stock doors-featured in definite, plainly marked grades and a wide range of designs, including modern 3-panel layouts adaptable to all types of building-are also pre-sealed at the factory. They reach the job fully prepared for a better finish. They're protected against moisture and checking, with resulting improvement in dimensional stability.


MORE FIR DOORS SOON!

It is a fact that Douglas fir doors may continue in short supply for a number of months. Two factors make this true: the present overwhelming demand-and the shortage of essential raw materials. But production IS stepping up. Warehouse and dealer stock should soon reflect this in-creased production. We suggest that you keep in touch with your regular source of supply.



For Even Greater On-the-Job **Economies, Specify Fir Doors**

Durable, attractive Douglas fir doors may also be ordered completely precisionmachined-not only pre-fit and pre-sealed, but gained for hinges and mortised or bored for locks as well. Here again, cleaner, trimmer jobs are assured, because all work is done at the factory by high-speed precision tools. Time savings more than offset the slight additional cost,



No on-the-job mortising or boring required!

Remember! NATURE MAKES DOUGLAS FIR Durable!

> The National Association. of Fir Door Manufacturers


For Better, Faster Installations, Specify:

Douglas Fir DOORS


FIR DOOR INSTITUTE

Tacoma 2, Washington

Redesigned-Re-engineered TO INCLUDE THE FAMOUS



McQuay RIPPLE FIN COIL




Ripple Fin coils mean better heat transfer because tubes are hydraulically expanded into fin collars locking them together in a permanent mechanical bond. Wide fin collars give greater area of metal-to-metal contact. Spun collar surfaces give smoother quality of contact.

A greater unit heater...a greater value...than ever!

That's what McQuay, Inc. offers in its newly styled line of unit heaters. Redesigned to include all the advantages of exclusive Ripple Fin coil construction. Restyled for new beauty of line. Only Ripple Fin construction gives you maximum heat transfer surface... positive air wiping action. Only Ripple Tube design gives you the internal turbulence that means more heat... faster. And, included of course, are McQuay's famous elliptical copper headers to compensate for unequal expansion during the critical warm-up period.

Combined with Ripple Fin coils, McQuay unit heaters feature new silent operation, die-formed cabinet and fan ring, mountings to fit piping or overhead brackets, a model range of from 16,000 to 300,000 BTU's output. See the McQuay representative in your area today or write: McQuay, Inc., 1605 Broadway Street Northeast, Minneapolis 13, Minnesota. Representatives in principal cities.





6 PRACTICAL IDEAS for a MODERN STOREFRONT

There's more than beauty in this storefront by Architect Louis Redstone of Detroit. To mention just a few of its practical points:

- 1. It's a Visual Front. Note how the center section is open to full view through large windows of plate glass. This makes the store look more inviting—brings customers in. Daylight brightens the sales floor—and at night, the lighted interior makes the whole store a showcase.
- 2. The second floor is "opened" with a glass front. Merchandise displays can be seen from the street. This floor, too, is brightened by daylight.
- **3.** The *Tuf-flex** tempered plate glass doors lend a modern note to the entire front and accentuate the openness.
- 4. Display windows in the "wings" permit excellent model

room displays. Low bulkheads make the prospect feel almost as though he were in the room.

- 5. The roof extension keeps direct rays of the high summer sun out of the store. And at night, lights this in canopy flood the front and the sidewalk.
- **6.** Patterned Glass in second floor windows provides privacy where it is wanted—without sacrifice of daylight. Day and night, the glass adds a decorative note.

Not every storefront offers such design opportunity. But this one shows how glass was used to make a home furnishings store more attractive and a better business-getter.

For information on Visual Fronts, write for our storefront brochures. Just tell us which types of stores interest you most. Libbey Owens Ford Glass Company, 6577 Nicholas Bldg., Toledo 3, Ohio.

*Reg. U.S. Pat Off.



LIBBEY · OWENS · FORD

a Great Name in GLASS

At Least a

en Keasons

WHY YOU'LL LIKE

SHUTLBRAK SAFETY-TYPE ENCLOSED

There are many reasons for the mounting popularity of (A) Shutlbrak Switches. Some say, for instance, they like its easier, splitsecond speed of operation . . . its new shuttle mechanism feature that gives quick make and break connections. Others say it is the simplicity of design that appeals to them . . . ample knockouts and wiring space at top, bottom and back. Still others say it is its trouble-free service and many practical safety features . . . its long lasting economical operation.

Positive Make and Break

- Interlocking Fuse Door (With special release)
 - Front Operatio
- **Attractive Finis**
- **Removable Switch Unit**
- Kamklamp Fuse Holder
- **Full Range of Capacitie**
- Silver-Plated Contacts and Connection
- Ample Wiring Space and Knockout

Silver-Plated Solderless Pressure Connector

Approved by Underwriters' Laboratories

Can Be Used Singly or in Panelboard and **Switchboard Assemblies**

(Shutlbrak Switches are available in a full range of capacities ... from 30 to 1200 amps., for 250 volts AC or DC and 575 volts AC in 2, 3 and 4 poles.

Attractive pearl gray finish enclosures for flush or surface mounting, (B) Shutlbrak Switches can be used as single operating switches or assembled into panelboards and switchboards.

Whatever the reason, the fact remains that (A) Shutlbrak Switches embody the latest in design and construction, making them the popular choice for high quality, heavy duty switching. So the next time you need a good operating switch, ask your dealer to show you an (A) Shutlbrak or send for our 20-page Bulletin No. 70.

If it's 1 it's "OK"

MAKERS OF ... BUSDUCT PANELBOARDS **SWITCHBOARDS**

ECTRIC COMPANY St. Louis, Missouri

SERVICE EQUIPMENT SAFETY SWITCHES LOAD CENTERS ELECTRIC QUIKHETER

The PLANNING BOARD



The Truscon Planning Board Says,"Normal delivery on many of our Steel Building Products is now possible. In fact, on

all material for which raw material is readily available, a normal rate of production and delivery is currently in effect." However, since production and delivery schedules change from week to week, we suggest you contact the nearest Truscon sales office for the latest information.

47,354 Truscon Steel Casements for Stuyvesant Town Apartments

A big dent in the New York City housing shortage situation is being made as unit after unit of the new Stuyvesant Town Apartments is being completed. The entire project will cover 75 acres, with 35 separate buildings containing 8,759 modern apartments.

In every room of each of these many apartments, Truscon Stee! Casement Windows will bring the occupants ample supplies of nature's free sunlight and fresh

nature's free sunlight and fresh air. The beautiful design of the windows themselves helped achieve outstanding architectural distinction in the structures, both for the exteriors and interiors.

Truscon Steel Casements, due to their individuality and flexibility of arrangement, meet the particular requirements of every type of room. Where windows are opened and closed frequently, or where ventilation needs are great and varied, Truscon Steel Casements fill a definite utilitarian need in addition to being highly decorative. Clean, bright, air-controlled kitchens are possible. The side-hinged casements can be adjusted by fingertip touch to invite or retard the flow of air, to suit the range of requirements in each room.

Truscon heavy steel construction, corner-welding of ventilators and frames, projection-welding of hinges and sturdy hardware assure the home-owner a long-time, trouble-free investment in windows with an economy of maintenance. There is no sagging, binding or warping in Truscon Steel Casements. Perfect fit and uniform contact give complete protection against inclement weather. Truscon's Bonderizing of all steel surfaces and the baked-on prime coat provide an excellent surface for finish coats of paint, and assure maximum protection against corrosion.

Truscon Casement Screens and Storm Sash are available for quick, convenient installation. Write for free descriptive catalog showing complete range of Truscon Steel Casement types and sizes.

Concrete Reinforcing Bars Proved Worth in 1906

An interesting fact is that the San Francisco earthquake disaster in 1906 served as a proving ground for Truscon's Reinforcing Bars. Among the buildings which did not crack or crumble from the quake were those constructed of concrete utilizing Truscon Bars.

Doorways to Skyways

Truscon Steel Hangar Doors are the product of 20 years of manufacturing experience and research combined with the best engineering skill, workmanship and materials. Their design, manufacture and erection is a highly developed art and must be undertaken by



Stuyvesant Town Apartments, New York City, a Development of the Metropolitan Life Insurance Company

Roof Jobs Made Easy

Specify Truscon "Ferrobord" Steeldeck to get the quick, economical, permanent answer to any roof problem you may have.

"Ferrobord" Steeldeck consists of a parallel system of strong structural interlocking steel members, which present a smooth surface over which can be applied built-up roofing



Application of "Ferrobord" Steeldeck

of any type, with or without insulation. "Ferrobord" is made from 18-gauge copperbearing strip steel, having an ultimate strength of not less than 50,000 lbs. per square inch. Each unit is 6 inches wide and has a depth of either $1\frac{1}{2}$ or $1\frac{3}{4}$ inches.

With these specifications you can design a roof job that's got strength and effective area coverage at reasonable cost. The Truscon Steel Company will be glad to cooperate with local roof companies in selecting the proper type of insulation and built-up roofing to meet certain definite requirements of structures. Write for free catalog.

experienced men, in order to attain completely satisfactory installations.

The success of a hangar door installation depends to a great extent on the experience and good judgment of the manufacturer's field organization. Truscon's field crews are

comprised of specially trained men who "know how" through years of experience with many installations, to do just the right things to make the job a success.

Truscon designs and manufactures Straight Slide Doors; Tail Doors; Braced,

Unbraced and Bifold Doors; Vertical Lift Canopy Doors and Three-Section Vertical Lift Type Doors. Write for free descriptive literature.



New Literature

A new 8-page folder on light Industrial Steel Doors, Series 31. Complete with construction and installation details, specifications, sizes and types. Write for your free copy today.

TRUSCON STEEL COMPANY

YOUNGSTOWN 1, OHIO
Subsidiary of Republic Steel Corporation



NATIONAL HEAT EXTRACTORS

...for Coal, Oil or Gas Firing



"100" SERIES

Smart and compact for small home installation in kitchen, basement or utility room.






"300" SERIES

For larger homes, small apartments and various commercial installations where more heat is needed.



"400" SERIES

The "400" and "500" are designed for very large installations where plenty of heat is required to serve many purposes. Characteristic HEAT EXTRACTOR construction.



Big boiler performance for homes of medium size and some commercial installations.

MORE Heat from Every Fuel Dollar!

That is the aim of National's design and research engineers—and their success is reflected in this new line of famous HEAT EXTRACTORS. A new, better generation of a distinguished family—the result of more than seven years of engineering design and research.

You'll Want ALL the Facts!

Contact your nearest National Radiator Company Heating Sales Branch, or write directly to The National Ra-

diator Company, 221 Central Avenue, Johnstown, Pennsylvania for full NRC product information—without obligation.

"HEAT EXTRACTOR" is the modern term for heating boilers made by National which take full advantage of the "Heat Extractor Principle"—extended heating surface and multiple flue passes.

SMART APPEARANCE marks the complete new 100, 200, 300 and 400 Series National HEAT EXTRACTORS. Jackets are in colorful flame-red (crinkle finish) contrasting with the jet black crinkle finish cast into base and platework.


ECONOMICAL cost of operation is a feature of National HEAT EXTRACTORS. National engineers have designed each Series for fuel economy regardless of the type of firing or fuel recommended.

CONVERTIBILITY from hand firing to fully automatic firing is a feature of the HEAT EXTRACTOR line. Conversion may be easily accomplished after installation.



The NATIONAL RADIATOR Company

JOHNSTOWN, PENNSYLVANIA



QUESTION: What is the best way to determine locations of

expansion joints in sheet copper construction?

ANSWER: Use the chart on

Use the chart on page 28 in Revere's Manual of

Sheet Copper Construction*

ACHART which makes it easy for you to determine the correct gauge copper for any gutter lining as well as the maximum distance that may safely be used between an expansion joint and a fixed point is one of the important results of Revere's extensive sheet copper research program. This chart and simple instructions for using it are on pages 28-29 in Revere's 96-page manual of sheet copper construction.*

This booklet is filled with new facts which enable you to design or install gutter linings, flashings and roofs that give *extra* years of service. It is complete with charts, illustrations and detailed information so arranged that you can read and apply final figures that insure the finest sheet copper construction.

This book has been widely distributed to archi-

*"Research Solves Problems of Stress Failures in Sheet Copper Construction."

tects and sheet metal contractors, and in all probability it is in your office files. Be sure to refer to it. If you do not have a copy, write for one now on your office letterhead.

For further information or assistance with the design or installation of sheet copper, the Revere Technical Advisory Service, Architectural, will be glad to help you.



COPPER AND BRASS INCORPORATED

Founded by Paul Revere in 1801 230 Park Avenue, New York 17, New York

Mills: Baltimore, Md.; Chicago, Ill.; Detroit, Mich.; New Bedford, Mass.; Rome, N. Y. Sales Offices in Principal Cities, Distributors Everywhere.



- G-E Slimline lamps recessed in the ceiling in continuous lines are shielded by etched plastic tiles and are engineered to illuminate side walls.
- 2. G-E Slimline lamps in coves along side walls bathe the ceiling with cool over-all lighting.
- G-E projector spotlamps and floodlamps are recessed in the ceiling at strategic points to provide both concentrated downlight and dramatic highlighting for furniture groups.

are gathered an array of modern light sources which can be used singly or in combination to create atmospheres of comfortable living. Here, in the G-E Lighting Institute Horizon House, architects may study new uses for G-E Lamps, fluorescent and filament, for easier seeing and for decoration.

- 4. G-E Fluorescent lamps in door and window valances add light, glamour and loveliness.
- 5. The soffit above the sofa contains two rows of G-E Slimline lamps to provide flexible and comfortable reading light.
- **6.** Bookcase lighting is supplied by G-E Slimline lamps placed vertically within side trim.
- 7. G-E Circline lamps are used in the wall brackets. They are shielded by pleasing and decorative glass.

GENERAL GO ELECTRIC

Whatever the lighting needs of your client, specify G-E Lamps, the ones that benefit from unending research to . . .

Brighter Longer

G-E LAMPS GENERAL % ELECTRIC

Write for free copy of "Horizon House", a descriptive booklet of architectural and installation de-tails of this room. Address General Electric, Nela Park, Dept. AF1, Cleveland 12, Ohio.



Don't you hate to see a home owner "behind the 8-ball"?

• Bituminous Coal has no equal when it comes to providing a home with uniform, dependable, low-cost heat. Every architect and builder knows that!

So even when a client of yours *insists* on using some other fuel for his new home, be sure you give him the chance to change his mind in the future—and turn to coal!

Otherwise, he'll be "behind the 8-ball" when cost differentials, stoker developments, and local coal services convince him he should get the benefits of coal heat.

Simply make sure his house plans include: (1) A chimney with sufficient flue capacity to burn coal efficiently; (2) Sufficient space adjacent to the heating unit for eventual coal storage and stoker installation.

The cost of such sensible precautions is negligible. And they constitute valuable insurance on the future value of a house.

Coal supplies uniform, *steady* warmth throughout every portion of each room. For there's always a fire in the furnace—no "pop on and pop off" periods that permit accumulated heat to rise to the ceilings and leave floor areas dangerously cold. That, plus its low cost, is why more than 4 out of every 7 homes in the United States now heat with coal!

BETTER AND BETTER THINGS ARE COMING FROM COAL!



As you undoubtedly know, the modern research facilities of the Bituminous Coal industry are hard at work not only to make coal a still better fuel, but also to devise new, low-cost automatic equipment that will make coal-heating even cleaner, more comfortable, more convenient, and more economical. This makes it all the more important that every new home built today be planned to permit the eventual burning of coal—no matter what fuel may initially be selected.

BITUMINOUS 🕮 COAL

BITUMINOUS COAL INSTITUTE
Washington, D. C.

Affiliate of NATIONAL COAL ASSOCIATION

The Architect Recommended

Ferro-Therm STEEL INSULATION

Residence and business premises of C. Metzroth, Babylon, L. I.



1. Minimum heat storage capacity

2. Quick temperature pull down

5. Does not adsorb odors or gases 6. Positive vapor barrier with steel

sheets resulting in permanent

against atmospheric moisture 8. Absolutely vermin-proof

3. Increases pay space

insulating efficiency 7. Tin alloy coating protects

Definite fire protection

4. Saves weight

More and more architects are recommending Ferro-Therm Steel Insulation for home and industry. Because, being a sheet of alloy coated steel, its high reflectivity keeps heat just where you want it—inside or out as required. All your insulation problems can be solved by using Ferro-Therm Steel Insulation.

Ferro-Therm

Fully Protected by U. S. and Foreign Patents issued and pending

AMERICAN FLANGE & MANUFACTURING CO., INC. 30 ROCKEFELLER PLAZA, NEW YORK 20, N. Y.

AMERICAN TEATOE & MANUEL ACTION OF THE CONTROL OF T	
AMERICAN FLANGE & MANUFACTURING CO., INC. Ferro-Therm Division, Dept. AR, 30 Rockefeller Plaza, New York 20, N.Y.	
Please send me, without obligation, complete information on Ferro-Therm Steel Insulation.	
Name	
Street	,
CityZoneState	

HERE'S WHY THE GAS LEFRIGERATOR STAYS SILENT... ASTS LONGER




Whether you're building apartments or private homes, it will pay you to study the simple explanation shown above before placing any orders for new refrigerators.

The chart shows why Servel's method of operation is simpler, different . . . and better. There is not a single moving part in the freezing system. That means there's nothing to cause mechanical humming or clicking. The entire freezing job is done by a tiny, silent gas flame.


That explains why there's an increasing trend toward the Servel Gas Refrigerator. Today tenants and owners expect new household refrigerators to operate silently. Many architects and builders realize that it's good business to install Servel Gas Refrigerators NOW... for once the housing shortage is eased, freedom-from-noise will be an important factor in renting apartments and selling homes.

And—equally important—Servel lasts longer. Since the freezing system has no moving parts, there's nothing to wear or break down. Servel's repair and replacement bills are remarkably low. Operating costs remain low too. After years of dependable, trouble-free service, the depreciation of the Servel Gas Refrigerator—compared with a mechanical refrigerator—is much less. For complete information, consult Sweet's Catalog . . . or write today to Servel, Inc., Evansville 20, Indiana.

STAYS SILENT Servel The GAS



hat keeps the weather clement for a clam can keep your clients happy, too!



Over 90 years of successful roofing experience has demonstrated the sound value of the gravel or slag wearing surface of a Barrett Specification Roof:



1. It holds in place the heavy-poured (not mopped) top coat of coal-tar pitch—providing a doubly thick waterproof covering.



2. It provides protection against the sun's actinic rays which otherwise dry out the valuable oils in roofing bitumens.



3. It protects the roof against mechanical damage, hail and wind, wear and tear.



4. It interposes a surface of fireproof rock between the building and flying embers—makes a roof that carries Fire Underwriters' Class A Rating.

Rain or shine, the Clam doesn't care. He's happy all the day. Whenever trouble looms he pulls his roof up over him...he's safe inside his armored wearing surface.

The Barrett Specification* Roof, with its armored wearing surface of gravel or slag, provides comparable protection for building structures. It's so tough and long-wearing it can be bonded against repairs and maintenance expense for as long as 20 years.

Built up of alternate layers of coal-tar pitch and felt, topped by a thick *pouring* of pitch to *anchor* the gravel or slag wearing surface, it is the toughest, longest-lasting built-up roof made. It is waterproof, fire-safe, sunresistant, and *armored* against mechanical damage.

As a service to your clients, recommend Barrett Specification Roofs on the buildings you design. The Atomic Bomb Plant at Oak Ridge, Tenn., the Empire State and R.C.A. buildings in New York, and many other famous American buildings—all Barrett-roofed—confirm the soundness of your recommendation.

THE BARRETT DIVISION Allied Chemical & Dye Corporation

40 Rector Street, New York 6, N. Y.

2800 So. Sacramento Avenue Chicago 23, III.

Alabama

In Canada: The Barrett Company, Ltd., 5551 St. Hubert Street, Montreal, Que.

*Reg. U. S. Pat. Off.

UNITED STATES RUBBER COMPANY

SERVING THROUGH SCIENCE



Some people are just different!

And the same goes for electrical wire. Laytex (Type RU) branch circuit wire stands out from the mob because it is the world's smallest diameter, lightest weight natural rubber-covered building wire.

The small diameter of Laytex permits more circuits per conduit. The 90% unmilled, grainless natural rubber insulation is applied in laminated walls that form an electrically safe sheath. The conductors are perfectly centered, eliminating chances of thin spots. Dielectric and tensile strengths are high.

Laytex (Type RU) is more than just different. In physical and electrical qualities, there is no other wire to compare with it.

UNITED STATES RUBBER COMPANY
1230 Avenue of the Americas · Rockefeller Center · New York 20, N. Y.

U.S. LAYTEX - - -

Specify RU Laylex

ELECTRICAL WIRES AND CABLES

RU?

it's the coming "Code" wire

SAFETY FACTORS THAT PUT



BULL'S EYE

The conductor is on dead center throughout every inch of the wire.



ELEPHANT

Laminated walls of natural rubber insulation mean Laytex (RU) is safe.



SMALLER O.D.


Allows more circuits per conduit than in ordinary wire. Lighter weight.



Air Conditioning and igeration Report

Worthington Pump & Machinery Corporation, Harrison, New Jersey

SAVE 90% WATER COST



NEW EVAPORATIVE CONDENSERS WITH MANY FEATURES FOR EFFICIENCY

Corrosion Minimized - Greatly improved protective treatment guards against costly corrosion. All parts exposed to moisture are of zinc-coated steel, bonderized and coated with a rubber-base enamel containing special rust-inhibiting powder.

Easy to Clean, Stays Clean Longer - Prime surface, with no fins to clog. Accessibility through panel construction to every part makes cleaning simple and fast.

Water Treatment Device — Available for use where water is unusually hard or where corrosives are present.

Made in five sizes, Worthington Series ECZ Evaporative Condensers combine practicability with heavyduty durability to join the long list of Worthington 'firsts' for efficient, lowcost refrigeration. Worthington Pump and Machinery Corp., Harrison, N. J. Specialists in air conditioning and refrigeration for more than 50 years.





Before It's "Southern Fried" It's "Worthington Refrigerated"

Typical of many up-to-the-minute firms supplying the nation's food, the Jewell Poultry Company of Gainesville, Ga., makes Worthington refrigeration an important factor in its processing. Above is the main processing room, where 100,000 lbs. of chicken are prepared daily.




A part of the Jewell Company's storage space, with cartons of chickens ready for shipment. The workers' heavy clothing and the iced-up pipes indicate the low temperature that must be permanently maintained by Worthington equipment to prevent spoilage.



Refrigeration equipment at the Jewell Company. In the right foreground is a Worthington Freon-12 Condensing Unit. In the left rear are three Worthington Vertical Ammonia Compressors. Worthington units of these types are widely used throughout industry.

Why Integration?

You get refrigeration and air conditioning at its best when all parts of a system "pull together" smoothly. And remember that Worthington, as makers of so many "inner compressors, condensers, turbines, pumps, valves, fittings, etc. - is better able to integrate these essential parts into a trouble-free, economical refrigeration or air conditioning system . . . It's another reason why there's more worth in Worthington. See your nearby Worthington Distributor for details.



For Varied Surface Beauty And Unvarying Efficiency!

The above design, sixth of a series, will appear in full-color in the July 12 "Saturday Evening Post." Note the effect of Reynolds Lifetime Aluminum Clapboard Siding, the contrast of naturally weathered aluminum shingles, the use of corrugated sheet between ground floor windows. The window frames and the roll-up garage door are also Reynolds Lifetime Aluminum Products.

Now add to these design advantages the lifetime permanence of fire-proof, rust-proof, termite-proof aluminum ... and you can see why more architects specify it. And there's radiant heat reflection! Right now, aluminum is keeping new homes amazingly cooler. It throws off the sun-load—won't

store heat as do other metals and wood. And it reflects heat back inside—for more warmth with less fuel in winter.

Best of all, this modern material is immediately available. Its easy application appeals to builders. So it means quick action and satisfaction all the way from designer to consumer. See Sweets or write for A. I. A. File brochures. Offices in principal cities. Reynolds Metals Company, Building Products Division, Louisville 1, Kentucky.




Today the base price of aluminum is 30% lower than pre-war!

REYNOLDS <u>lifetime</u> ALUMINUM BUILDING PRODUCTS


ALUMINUM SHINGLES - CLAPBOARD SIDING - SHEET ROOFING & SIDING - STUDS - TRUSSES - WINDOWS - GARAGE DOORS - REFLECTIVE INSULATION - UTILITY BLDGS.-HOUSES



Shingles. Interlocking, weather tight, covering all nails. Two sizes: 8 x 14½ and 5½ x 18½.



Clapboard Siding. Fitting together, covering all nails. 8" exposed surface, 12' lengths.



Casement windows. Underscreen roto-operators. Standard lights, all usual combinations.

There's a lot of unselfish thinking back of this campaign!

Of course, we hope this big full-color ad in the Gold Bond Saturday Evening Post series will sell more Gold Bond Building Products. But we hope, too, that it will get more folks-young couples especially - steamed up about owning a better-built home of their own, and soon! In other words, this campaign is doing a promotional job for the whole building industry. Thousands of people write us for details of the charming homes pictured in this series, and as usual our answer is "Consult your local architect!" National Gypsum Company, Buffalo 2, New York.



You can start building sooner if you start planning now. See your local Gold Bond Dealer

Closer to heaven than you may think ...

"Through all the long hard war years, when Ted was overseas, we dreamed about a heaven all our own. Our own house in our own yard. With a funny little garden out back... and a funny little toddler out in front selling mud pies..."

That's more or less the way thousands of couples That's more or less the way thousands of couples have felt and we know from our mail that it's been hard at times keeping your chin up. But if a home of your own is your idea of heaven we can assure you that you are a lot closer to it now.

Materials are flowing again. Not all you want, but more and better materials than have been available for years. Products developed by research to make

your new house superior to any you could have built before. You'll say it was worth waiting for!

For instance, you can build sturdier, weather-proof, more firesafe walls with Gold Bond gypsum sheathing under the clapboards, brick or other out-side finish. Costs no more than old-style sheathing!

side finish. Costs no more than old-style sheathing! You can keep summer heat out and furnace heat in with National Gypsum Company's new high efficiency, fireproof home insulation . . . Gold Bond Rock Wool. Pays for itself by cutting fuel bills as much as 40%. If you own your home now, you can have this same modern efficient insulation "blown" right into outside walls and top floor ceiling.

You'll have inside walls of lasting beauty if your architect specifies Gold Bond gypsum lath and plaster. And you'll have something new and beautiful room decoration if you use quick-drying Gold Bond Sunflex paint. Comes in a wide range of colors.

Your Gold Bond lumber and building material dealer is headquarters for over 150 Gold Bond building products, each researched and engineered by National Gypsum Company, to build better value into your new home or to make your remodeling job easier. For suggestions see your Gold Bond dealer.

NATIONAL GYPSUM COMPANY BUFFALO 2, NEW YORK

Over 150 tested Gold Bond Building Products for new construction or remodeling add greater permanency, beauty and five protection. These include wallboard, lath, plaster, lime, sheathing, wall paint, insulation, metal and sound control products.

EMAND GOLD BOND FEATURES YOUR NEW HOUSE













THE MOST COMPLETE LINE OF HEATING SPECIALTIES

It's smart business to concentrate on Hoffman Specialties . . . it's the only line that offers all these satisfaction guarantees. It's the complete line. For either steam or hot water installations, Hoffman Specialties provide a single source of supply for all necessary equipment. It's the tested, quality line. Hoffman superiorities of design, workmanship and dependability are well established. Yet Hoffman

Products cost no more than the ordinary kind.

Hoffman Specialties are handled through recognized heating and plumbing wholesalers throughout the country. There is always a stock at a convenient location. Hoffman sales-engineers are ready to serve you.



Guardian of Your Fuel and Comfort

HOFFMAN SPECIALTY CO., INC., Dept. AR-7, 1001 York St., Indianapolis 7, Ind.







MAIN VENTS HOT WATER VENTS

VENT VALVES

Venting requirements of both gravity and vacuum steam heating systems are satisfied by a complete selection of SIPHONLESS Hoffman Valves offering many time-tested and exclusive features. A selection of main air and vacuum vents is also available.



THERMOSTATIC

TRAPS

Low, Medium and High Pressure Traps have renewable thermal units and seats—assuring long life, low cost service.

.

SUPPLY VALVES

Reinforced Packless construction, with reversible cone disc, and in wide selection of patterns.



FORCED HOT WATER HEATING SYSTEM CONTROLS



Series 90 Comfort Controller balances supply water temperature to outdoor temp. changes.

Hoffman Control



Valve admits boiler water to circulating steam as needed.

Hoffman Circulator continuously circulates water through the systemprovides smooth, uniform comfort.

FLOAT AND THERMOSTATIC

............

TRAPS



All working parts are mounted on the cover and readily accessible without breaking pipe connections.

AND INVERTED **BUCKET TRAPS**


Bucket, valve and seat connected to bonnet and removed with it for cleaning. Straightthrough pipe connections. Working pressures to 200 lbs.



CONDENSATION AND VACUUM PUMPS

.............





Hoffman-Economy Pumps, both Vacuum and Condensation types, have established a sound reputation with exacting engineers for their ability to keep a heating plant clear of

condensate and air—quietly, economically and dependably.

NEWEST MEMBERS OF THE HOFFMAN LINE



Sizes from 1/2"

Steam pressures

to 11/2" inc.




fuel-oil, gasoline-"dead end" or con



TEMPERATURE REGULATORS

Temperature range from 80° F. to 250° F. For thermostatic water heaters, converters, cookers, plating tanks, processing tanks, sterilizers, fuel-oil pre-heaters, etc.

HOFFMAN HEATING SPECIALTIES ARE SOLD EVERYWHERE BY LEADING WHOLESALERS OF HEATING EQUIPMENT



Apartment House, 20 E. 74th St., New York City. Architect: Sylvan Bien, New York. Contractors: S. Minscoff & Sons, New York. Adapted from the original rendering in color by J. Floyd Yewell.

Compact planning, so necessary in apartment house construction, requires the conveniences and comforts available with Lupton Metal Windows. The narrow frames of Lupton Metal Windows increase glass area and harmonize with contemporary design, giving each room the appearance of spacious surroundings and gracious living. Controlled natural ventilation without harmful drafts, and simple operation increase tenant satisfaction. Modern in appearance, flexible in design, there is a Lupton Metal Window for every type of building. Write for our new 1947 Catalog or see it in Sweet's.

MICHAEL FLYNN MANUFACTURING CO. 700 East Godfrey Avenue, Philadelphia 24, Penna. Member of the Metal Window Institute

LUPTON METAL WINDOWS

AW FABER-CASTECE

LOCKTITE

ways better than any refill pencil you ever used...



A Refill Drawing Pencil to warm the hearts of Professional Men

Clean

One hand operation. No need to touch the lead. Hold lead to paper, press button release and adjust length you desire by quick upward or downward movement of your hand. Thus you avoid getting graphite on your fingers to smudge your drawing.

No Breakage

An exclusive collet, machined to a thousandth of an inch tolerance, supports the graded lead all around. Prevents breaking or snapping even when you bear down hard.

Non-Slippage

The same precision collet holds the lead in a bulldog grip. The lead positively cannot slide back into the holder.

Sturdy

Fine quality plastic and metal used in every part. Exposed metal parts are gold-plated. All expertly assembled.

Quick

Just press your thumb on the button to release clutch. Does away with two-handed screwing or turning operation.


Balanced

Every part is precisely proportioned, giving you a writing instrument which is perfectly balanced in your hand.

Guaranteed

If your LOCKTITE fails to give you perfect performance, return it to your Dealer or to us for immediate exchange.

at your Art Supply House, Drawing Material Dealer,
Blue Printer, Stationer or Photographic Supply Shop








they eat!

But how well they eat depends on whether or not you specify a Gas range. For nothing — absolutely nothing — can touch the live Gas flame for lusty, crusty

broiled meat flavor. As for baking . . . only a Gas range has an air-circulated oven. The one sure way to get evenly-browned cakes, rolls and feather-light biscuits!

they work!

But how hard the cook-of-thefamily works is up to you! See that she has a new Gas range for cooking that not only is faster and more flexible...but is also cooler and cleaner. No





But how often they play can be increased a hundred-fold by a completely automatic Gas range. This 20th century miracle has a clock control that turns the heat on at a specified time and temperature—cooks a delicious oven meal from soup to dessert—and turns itself off. Other automatic features in every Gas range built to "CP" standards include automatic lighting of top burners, oven,

and broiler and an oven thermostat that holds any heat from 250° to 550°.

they pay!

But how *much* they pay for what they get is *your* responsibility. Remember! No other automatic range can compare with a new automatic Gas



range in economy of initial purchase — or — in economy of operation.

they come back for more

people . . . when the appliances you specify give them more! This holds true not only in Gas for cooking but in Gas for all the other big jobs in the modern home . . . refrigeration, waterheating, house heating and airconditioning. For Gas is the dependable fuel no matter what it is used for. And Gas appliances are the most trouble-free to own and install of all modern automatic equipment.

See your local Gas Company for the latest technical information on modern Gas appliances and installations.






THE WONDER FLAME THAT COOLS AS WELL AS HEATS

AMERICAN GAS ASSOCIATION

Build for tomorrow with what they want today



THE comparisons pictured above are startling. The moral is simple and obvious. When a Wurlitzer Organ is chosen, both space and funds are saved for other wanted decorations and facilities.

Yet, thanks to Wurlitzer's electronic genius, not one bit of musical beauty is lost. This

superb instrument, employing a tone-producing principle used for centuries in pipe organs, creates the exact, rich, vibrant, family of organ voices traditionally associated with the worship service. Inquiries are

invited, addressed to Dept. AR 7.

Organ Division

THE RUDOLPH WURLITZER CO.

North Tonawanda, New York

Series 20
TWO-MANUAL



HAS YOUR BUILDING THIS WATERFOIL RAINCOAT?

One bad rainstorm may result in costly damage to an unprotected building and contents. To protect a building exterior and beautify it is now a simple process with Waterfoil. Unlike any other protective coating, Waterfoil is made of irreversible inorganic gels which bond both chemically and physically to masonry surfaces. By helping to impede water penetra-

tion into concrete, brick or stucco walls, Waterfoil prevents reinforcing bar rust, spalling or disintegration. Don't wait for the gale. Write for literature today—it's important to all building maintenance.

Horn products and methods protect millions of square feet of surface throughout the nation. Our field engineers consult with you and recommend materials and methods for the protection and decoration of any part of your structure in any climate or condition.




A. C. HORN COMPANY, Inc.

Established 1897 - 50th Anniversary

Manufacturers of Materials for Building Maintenance and Construction 43-36 Tenth Street, Long Island City 1, N. Y.

Houston, Texas • Chicago, Illinois • San Francisco, Calif. • Toronto, Canada Subsidiary of Sun Chemical Corporation



THROUGH THE YEARS...

Copper costs less

In HOMES large and small, hot water heating lines, hot and cold water lines and other pipe lines cost less by the year when they're copper.

The cost of a copper tube system installed very often approximates that of ordinary piping. This is because installation may be expedited with solder-type fittings. Because soft annealed copper tube is available in long lengths and may be bent around obstructions, fewer fittings are required. Because threading is eliminated and no allowance need be made for rust-clogging, copper tubes may be of relatively smaller diameter and lighter weight.

Anaconda Copper Tubes are made from specially deoxidized, 99.9+% pure copper, furnished soft in 60-foot coils, also hard and soft in 20-foot straight

lengths. Types K and L Tubes, trade-marked "Anaconda," are available from wholesale distributors throughout the country.


Publications B-1 and C-2 discuss copper tubes for general plumbing, and for heating lines, respectively. Copies will be mailed on request.



THE AMERICAN BRASS COMPANY

General Offices: Waterbury 88, Connecticut Subsidiary of Anaconda Copper Mining Company In Canada: ANACONDA AMERICAN BRASS LTD. New Toronto, Ont.

JULY 1947



"Steel construction costs are cut when welded joints and connections are used..."

says R. I. Ingalls Sr., Chairman, The Ingalls Iron Works Co.

He adds, "Many steel fabricators, due to their war experience, have developed a 'know how', background that can meet all the demands of welded construction — economically.

"Also, today, with the large pool of available competent war-trained welders, speedy, quality welding is definitely assured."

So it is all over the country. Architects and builders are finding that many prominent steel fabricators are going "all out" to cooperate with them in welded construction. So, why not take advantage of today's facilities to specify this modern construction process in present building plans — a process that affords unquestionable strength and maximum economy in construction costs.

Remember, a welded joint is actually stronger than the base metal.

For full information about this advanced construction technique, write: Dept. AR-6681, Air Reduction, 60 East 42nd St., New York 17, N. Y. In Texas: Magnolia Airco Gas Products Company, Houston 1, Texas.



HEADQUARTERS FOR OXYGEN, ACETYLENE AND OTHER GASES...CARBIDE...GAS WELDING AND CUTTING APPARATUS AND SUPPLIES...ARC WELDERS, ELECTRODES AND ACCESSORIES

GET ALL OF THESE IMPORTANT ADVANTAGES



Specify Decorative Micarta*

Use it to modernize and glamorize every working surface in your interior ... table-tops, counters, work surfaces, fixtures ... any place you want beauty, convenience and durability combined in one practical material.

But be sure you specify Decorative Micarta.* Only then will you get all 10 of these important advantages:

- Super-smooth surface makes cleaning a quick and easy task.
- Highly resistant to heat, moisture, mild acids and alkalies. Will not spot or stain from food, grease, alcohol, etc.
- At slight extra cost, Decorative Micarta is available in a "cigarette-proof" grade. Remains unmarred, even when cigarettes burn out on it.
- Finished surface is hard and durable. Highly resistant to abrasion and repeated wipings that mar and scratch ordinary surfaces.
- Decorative Micarta is a strong, dense material . . . guaranteed not to warp, chip or crack under ordinary service.
- Color-fast, permanent finish. Unusually clear, lustrous colors and patterns which won't fade or darken.

Flexwood**

Flexglass**

- Optional finishes. Brilliant high-gloss or lustrous
- Truwood Micarta, with surfaces of genuine wood veneers, combines the beauty of such woods as primavera, mahogany and walnut with all the practical features of Decorative Micarta.
- Exclusive "Beauty Mask" of tough Kraft paper protects the surface during shipping, machining and installation. Strips off easily when ready for use.
- For covering large surfaces quickly and with a minimum number of joints, Decorative Micarta is available in large 4 ft. by 8 ft. sheets. Smaller sizes also available for table tops and similar applications.

Get complete information on Decorative Micarta. Desirable colors and patterns are available now to blend right in with any interior style. Write:

UNITED STATES PLYWOOD CORPORATION 55 West 44th Street, New York 18, N.Y.

Weldwood Glue** and other adhesives Weldtex** (striated plywood) Decorative Micarta*

Weldwood** Hardwood Plywood Douglas Fir Weldwood Mengel Flush Doors Molded Plywood Armorply** (metal-faced plywood) Tekwood** (paper-faced plywood)

*Reg. U. S. Pat. Off., Westinghouse Electric Corporation **Reg. U. S. Pat. Off., United States Plywood Corporation



ASBESTOS CORRUGATED for

INTERIORS

THAT Sell

More and more architects are fitting "Century" Asbestos Corrugated into their interior decorative schemes for theatres, restaurants, offices, sales rooms, stores, other places of business. They have found that "Century" Corrugated can be used in numberless ways to create distinctive effects.

Use "Century" Asbestos Corrugated to carry out either masculine or feminine motifs. Use it in its natural light gray finish... or paint it to any desired color. Run the corrugations vertically or horizontally—according to the individual job.

Whether you use "Century" Corrugated for decorative or utilitarian purposes (exterior siding and roofing), you can choose from 19 available sizes to simplify installation and hold down costs. Once in place, "Century" Corrugated is easy to keep clean, won't buckle, crack or deteriorate. It resists fire, rodents, termites, rust, galvanic action.

Write us for more detailed information about "Century" Ashestos Corrugated. We'll give prompt attention to your inquiry.

Nature Made Asbestos . . .

Keasbey & Mattison has made it serve mankind since 1873.

KEASBEY & MATTISON COMPANY · AMBLER · PENNSYLVANIA



Senkins Practical Piping Layouts 24

How to Plan
SOOT BLOWER
CONNECTIONS
CONNECTIONS
ON A 250 POUND
STEAM BOILER

 High boiler efficiency necessitates periodic removal of soot deposits from the boiler tubes through the use of soot blowers.

Soot blowing may be accomplished either with compressed air or steam and this diagram shows a typical soot blowing installation in conjunction with a 250 pound boiler using superheated steam. Each soot blower head is provided with its own pressure reducing orifice since the pressure required depends on the location of the element, and different locations require different pressures.


Steam for the soot blowers is taken from a nozzle on the superheater. A vertical header from this point delivers steam to the various soot blower heads. The individual branches are all pitched down to the header to assure complete draining of the system prior to blowing.

Each branch feeder is provided with an emergency shutoff valve designed to take full boiler pressure. Should repair of a soot blower be necessary the emergency valve can be shut, the remainder of the system still functioning.

Consultation with accredited piping engineers and contractors is recommended when planning any major piping installation. Copies of Layout No. 24, enlarged, with additional information, will be sent on request . . . also future Piping Layouts. Just mail coupon.

A CHOICE OF OVER 600 JENKINS VALVES

To save time, to simplify planning, to get the advantages of Jenkins specialized engineering experience . . . select



all the valves you need from the Jenkins line, fully described in the Jenkins Catalog. It's your best assurance of the lowest cost in the long run.

Jenkins Bros., 80 White St., New York 13; Bridgeport, Conn.; Atlanta; Boston; Philadelphia; Chicago; SanFrancisco. Jenkins Bros., Ltd., Montreal.

LOOK FOR THIS JENKINS DIAMOND MARK

A 3		Jenkins Valve	Superheated Steam Supply to Soot Blowers			
		Fig. 990—Bronze Angle				
В	4	Fig. 990—Bronze Angle	Individual Element Emergency Shutoff			
с	2	Fig. 976—Bronze Globe	Drain of System			



JENKINS VALVES

For every Industrial, Engineering, Marine, Plumbing-Heating Service...in Bronze, Iron, Cast Steel, and Corrosion-resisting Alloys...125 to 600 lbs. pressure. Sold Through Reliable Industrial Distributors Everywhere

JENKIN	NS BRO)S., 80	White	St.,	New Y	ork 13	, N.	Y.
		ne a re						4
Name								
Address								



PHOTO BY FAIRCHILD AERIAL SURVEYS



• More efficient use of roof areas is the order of the day. Garden roofs, outdoor decks for convalescents, recreational space for office workers, heavy traffic and storage roofs for factories—these are typical examples of this trend in modern architecture.

Ruberoid engineers have analyzed all these new roof developments, divided them into three basic types, and worked out sound practical specifications for each. No unfounded theorizing or guesswork here—they've been tested and proved in actual performance! Copies of these specifica-

GARDEN ROOFS LIKE THIS ARE SIMPLE AND PRACTICAL

Flowers, grass, shrubs and even trees now grow where formerly the city dweller could only expect to see bare roof areas. Ruberoid's new specifications make installations like this not only simple but practical and efficient.

tions and full details are available from your local Ruberoid Approved Roofer.

Your Ruberoid Approved Roofer stands ready to help you in the solution of any roof problem. His "know-how" is backed by Ruberoid's years of experience and complete line of all types of built-up roofing materials.

The RUBEROID Co.

Executive Offices: 500 Fifth Ave., N.Y. 18, N.Y. Asphalt and Asbestos Building Materials

The RIGHT roof for any job-from one source!



Remember that Ruberoid makes every type of built-up roof— Smooth Surfaced Asbestos, Coal Tar Pitch with gravel or slag surfacing, or smooth or gravel-and-slag surfaced Asphalt in specifications to meet any need. Hence a Ruberoid Approved Roofer is not prejudiced in favor of any one type. His services assure you of one source for all materials, centralized responsibility, smoother operation, uniform quality!

RECORD

POOR RELATIONS - PUBLIC, THAT IS

PUBLIC relations are extremely important both to the United Nations and to the architectural profession. Newspaper publicity is perhaps the most important phase of public relations and the recent newspaper release showing one rendering (see page 10) is what leads us to use the words "poor relations."

The rendering itself is good, in Hugh Ferris' inimitable dramatic technique. It was the publicity that was poor, for this one drawing is not enough to give any adequate idea of the project. Little wonder that the public should be disappointed.

It should have been obvious to both the U.N. and the architects that the publication of this one rendering would produce not only misconceptions regarding the final architectural treatment of the project, but also would bring down on its head an avalanche of criticism ranging from wisecracks to pontifical profundity, with emphasis on the wisecracks. With only one rendering as a basis for critical judgment and therefore no opportunity to study the architectural problem and its solution, it was natural and unfortunate that the more facetious criticisms should be given prominence in the papers. It was also unfortunate that prominent architects were responsible for the humourous analogies, for however lightly they may have been tossed off, the general public has taken them seriously and frequent repetition belittles both the United Nations and its Planning Board.

The damage done is irreparable, but we hope at least one lesson will be learned from the incident. Henceforth when material regarding the plans and the architecture for the world capital are to be released, they should be so complete and so well-prepared that the public will see both the logic and the skill of the designers. The publicity should definitely be propaganda which will produce a favorable reaction and thoughtful criticism rather than clever catch phrases and witty similes. The designs themselves as shown in renderings and plans should certainly inspire the public as being worthy symbols as well as functional buildings and should justify the time and the talent that is being spent on the world's Number One architectural project.

It is devoutly to be hoped, and confidently expected, that when the design for the capital of the United Nations is again (and soon) shown to the public, there will be many drawings and a full and lucid explanation of the planning and design. The Planning Board and its group of competent international architectural consultants should see to it that their efforts are exhibited in a manner worthy of the magnitude and importance of the project. It is equally important that the design recommended in the report of the Director of Planning and the Planning Board shall be one which the public and the nations of the world will hail as a design expressive of its high purposes as well as being functionally efficient as a means for bringing about world unity and world peace.

Leweth K. Stowell

MODERN MEXICO

The fancier sections of Mexico City glitter with glass. Huge sheets, ribbon strips and inlaid bricks turn the façades of the countless "modern" buildings into shimmering light. These same sections are redundant with balconies, cantilevers, box windows and hanging gardens. The first breath the visiting U. S. architect draws is a gasp. After the reflected light has ceased to dazzle him and he has become accustomed to acres of balconies and ribbon windows, he can begin, more or less rationally, to examine and evaluate modern architecture in Mexico. The breadth and depth of his analysis will depend largely upon his understanding of the country itself. Because his analysis will involve esthetic criteria, it will necessarily be arbitrary and subjective.

Mexico City is a boom town — buildings are mushrooming throughout the city, jostling and crowding over
one another. Each building is brazenly indifferent to the
rights of its neighbors. Each structure tries to outstrut,
to be taller, more daring, to use more glass or cantilever
further than the rest. There is a good deal of visual
hysteria in the composite picture of Mexican architecture. Nearly three-fourths of the buildings going up
in Mexico City can be labeled "modern" if one defines

the term somewhat loosely. The same is true of new building in Monterrey. Even staid, introverted Quadalahara is beginning to adorn herself with masses of glass brick and sinuously curving concrete walls. There is no architectural coordination in Mexico because there is little urban planning. There is almost as much talk about it as in the U.S., with about as much action. One can deplore the fact that Mexico, which is becoming urbanized in the modern industrial sense a century later than the United States, is not profiting more by our mistakes; but since our own house is of less apparent but equally fragile glass, we have no right to blame Mexico for her failure to plan. We can gently suggest, however, that until she does, she amplify and enforce her building code for safety's sake, and enact a few setback restrictions to curb the greedy competition among buildings for a place in the sun. It is encouraging that the wild exuberance of Mexico's building shows signs of subsiding.

History. Modern architecture in Mexico began about 1925. The outstanding pioneer of this movement is José Villagrán García, whose tuberculosis sanatorium,



Personal Observations, Impressions and Appraisals of Current Architecture

By Ann Binkley Horn

built in 1929, seems to me architecturally still far in advance of many contemporary American hospitals, though of course the latter are more lavish and up-to-date in equipment. The architectural form of Villagrán's building and its obeisance to functional demands repudiated the formulas of the Spanish colonial and French neoclassic traditions which previously had dominated Mexican urban architecture.


The impetus of the new movement came from Latin Europe, particularly from France via Le Corbusier, who is still the prime outside source of architectural inspiration to Mexican architects. Awareness of German, Dutch, and other northern contributions to the movement has been somewhat vague. The Mexican temperament is rather unresponsive to what it considers the austerity and coldness of these non-Latin movements. Almost unanimously, Mexican architects ignore or disparage the architecture of Frank Lloyd Wright, though they manifest a little more polite enthusiasm for some other North American architectural names. They are impressed with the technical efficiency of architectural construction in the United States, and envious of the variety and quality of the building materials available



Guillermo Zamora Fhoto

Above, El Sagrario Church, Mexico City, an example of the rich baroque ecclesiastical architecture of the 18th Century. Below, street fronts from Mexico City's melange of modern architecture. Extreme right and extreme left, two recent apartment houses designed by architects Alvarez and Madaleno





to the North American architect.

Although the mainstream of cultural influence continues to come from Europe, the Mexican architect is becoming increasingly interested in the work of his North American counterpart. The architects who are working on the hospital construction program for the Ministry of Public Health have visited dozens of U. S. hospitals to study their physical and administrative organization. Our architectural magazines are as widely

read now as the French issues. The architects of both countries can learn much from each other. The American, more cautious, is perhaps more solid and certainly more disciplined; the Mexican is bolder, more sensuous, and perhaps more imaginative.

Social Context. The modern architectural movement in Mexico, as in all countries, cannot be divorced from its social context. Economic, political, and cultural forces have naturally been powerful determinant factors in the formation of the movement and will largely dictate its future direction.

Mexican architects have plunged audaciously and at times a little wildly into the world movement of modern architecture. Some of the precepts of this movement as expounded in other countries, they have ignored or deprecated; others they have seized upon with truly Latin fervor. Consequently, during its early stages the movement was dedicated with almost religious ardor to the cult of "functionalism." The Mexican architect was in a hurry, and did not analyze with painstaking thoroughness the meaning of this word. However, it became the battle cry of his revolution against the persistence of colonialism, the upper-class courtship of French neoclassicism and the extravagance of Mexico's unconquerable baroque spirit. The slogan of "functionalism" came to Mexico shortly before the government proposed through its federal school system to give a "rational and exact concept of the universe." The new movement found an eager welcome in a country where revolution, change and reform were watchwords. Its arrival coincided with the political culmination of the long struggle against feudalism. Mexico was to become scientific, modern, and internationally minded. The architectural counterpart of this program was clearly "functionalism" and the "international style." New buildings were stripped bare of ornament; structural materials were no longer camouflaged by marble or handpainted tiles; the colonial arch and the neoclassic cornice disappeared. Naked and shivering slightly, the new

Sanatorio de Huipulco, Mexico, D. F., 1929. The original buildings and tower of the tuberculosis sanatorium by pioneer modern architect José Villagrán García ''repudiated the formula of the Spanish Colonial and French Neo-Classic traditions'' in its clean-cut forms




buildings went up in defiance of tradition. These buildings were a necessary and important step in the creation of the new architecture. Unfortunately, they were hastily and often badly built; much of the time they were gaunt and bleak.

What the Mexican architect then, and his followers even today, failed to understand is that the philosophy of functional construction implies more than the exposing of materials or the denuding of surfaces. It requires the careful investigation of structural forms, a thorough understanding of the properties of materials, their possibilities and their limitations. The proper use of steel and concrete does not permit careless or sloppy connections, nor can the new construction afford them, for, by being exposed, they have become articulate elements in the visual expression of the building. Similarly, the Mexican architect did not take time to realize that the simplicity of the new buildings demands a far more searching study of proportional and spatial relationships than the old, which could conceal their failures under borrowed finery.

The economical appeal of "functionalism" was strong to the socially-minded architect of the Twenties and Thirties. Mexico is poor and her needs are immense. Economy of construction and the suppression of ostentation were among the most important contributions of the early functionalist movement. Today, unfortunately, the principle of economy is being overridden by the impulsive disciples of the lush new baroque trend.

Ever since 1910, urban Mexico has been in a hurry. This haste is often disorderly enough to sustain popular credence in the *mañana* myth, but sun-sleepy feudal Mexico is now an exclusively rural phenomenon.

First the feverish pace was a by-product of the Mexican Revolution, of its sweeping political, educational and land reforms which were often effected with bloodshed and sacrifice, but were always done in a hurry with no time for analysis or self-criticism. Today Mexico is in a different kind of hurry; she is struggling to industrialize; she is breeding a middle class; she is becoming




Guillermo Zamora Photo


technologically minded. Her government is full of new technicos who are fighting with old-time politicos for control of Mexico's destiny. The extreme left wing calls Mexico bourgeois and reactionary; the right wing dubs her progressive; the less militant left, a "progressive bourgeois democracy."

Whatever she is, she has launched into a period of materialist expansion, which more effectively than the revolutionary political period, will toll the doom of Mexico's medieval heritage. The architect is caught in this maelstrom. He is building frantically, but his buildings, though often elaborate, are of the boom-town variety. With a few brilliant exceptions these buildings are hastily contrived. They often are poorly constructed and pay mere surface homage to the modern idiom. This homage, however, they do pay with an enthusiasm and determination which is to the architects' credit.

Construction. Brand new and expensive buildings in Mexico settle with alarming unevenness on their foundations. The soil in Mexico City is a fearful obstacle to



Above, architect José Villagrán García's Frontones del Parque "Mundet" 1945. Mexico's popular handball game boasts a truly functional architectural pattern. Left, his surgical pavilion, built in 1940, not far from his original sanatorium buildings shown on the page opposite





Photographs of the model of the school, Centro Escolar Ribera de San Cosme, Mexico City, Enrique Yañez, architect. View from south

building. It is fantastic to watch workmen sending wooden pile after wooden pile, sometimes three or four on top of one another, as though they were pushing toothpicks into a bowl of jelly. On one building, the National Lottery, Engineer Cuevas has experimented with floating concrete foundations. This building has just been completed though it was some ten years in construction and it is too early to be sure of the results. It seems probable, however, in view of soil conditions and the city's susceptibility to earthquakes, that the possibilities of floating foundations should be seriously and intensively investigated. In the meantime, other

architects are experimenting with systems of transferable weights to compensate for settling of the buildings. Mexican buildings are blithely reaching higher and higher from their precarious foundations. In towering New York they would be lost, but on Mexico's uncertain soil they seem, at the least, very dangerous. Recently a visiting engineer from the U. S., an expert in foundation construction, murmured politely to a group of Mexican architects that they were inclined to be somewhat audacious, a remark which a few of the more self-conscious translated less kindly.

The Mexican architect is only in part responsible for





View of model from north. The school is designed to accommodate some 3000 students. Photographs of the actual buildings below

the almost uniformly poor quality of urban construction. First, he lacks materials of good quality. Almost all steel framing must be imported from the States. This restricts him in the vast majority of cases to the use of reinforced concrete. This concrete, while it probably meets minimum safety requirements, is apparently of neither uniform nor high quality. Standard grading, mechanical mixing, rigid adherence to specified formulas, and large scale uniform production are all extremely difficult things to obtain in Mexico where rule of thumb calculations and primitive modes of working predominate. Mexican labor is cheap but usually unskillful and

inefficient. The Indian craftsman tradition is not evident in the work of the urban mason or bricklayer. This is true even in the rural village. The Indian is a temple builder, not a house builder. He has a rather otherworldly attitude toward secular buildings and he underlines their transient nature by the casual, almost indifferent manner with which he constructs them. Nor are Mexico's newly rich, the architect's clients, particularly interested in sponsoring well-constructed buildings. They are concerned with show and not with the niceties of sound and careful construction. It is rather poetic to watch dozens of ant-like workmen crawling up




75





Normal School, Mexico City. 'Escuelas Normales de Maestros,' Mario Pani, architect. The model above shows the architect's conception of the school in the grand manner. Two great wings curving from the central tower provide classrooms for some 4500 students. The library is centrally located between the tower and the large open-air auditorium which is flanked by schoolrooms. The plan also calls for a stadium, swimming pool, tennis courts, etc. Left, tiers of classroom windows of one of the two main wings. Below, the open auditorium, and, on the opposite page, the great sweep of the main facade with the central tower and colonnade







makeshift ladders that lean dizzily on the towering skeleton of a skyscraper-in-construction carrying heavy cement sacks; or to watch them watering a concrete column by throwing up cupfuls of water from an old soup can. It is poetic but not very efficient. One feels as though the working crew of the Egyptian pyramids had been transported intact to the site of a twentieth century building and put to work without further ado.


The Mexican architect has very little wood at his disposal. There is enough wood in Mexico to export large quantities to the United States, but if the architect wants wood of reasonably uniform quality, accurately cut and sufficiently cured and aged, he must reimport it from the U. S. Some Mexican plaster walls are as resistant as cake frosting. Mortar is slapped on bricks in great quantities to make up in bulk what it lacks in strength.


On the other hand the small domestic plywood industry is growing rapidly. Mexico City produces a good quality asbestos cement building board. The new and expanded steel mills in the Monterrey district will soon turn out a wider range and better quality of rolled steel members.

There is relatively little the Mexican architects can do to correct the negative aspects of the construction picture. They can unite and protest to contractors and building suppliers. They can and should supervise more carefully the composition and mixing of concrete. But unless they convert themselves into composites of entrepreneur, client, contractor, foreman and laborer, as well as architect, they are at the mercy of time.


In January the giant fireproof San Cosme movie house collapsed with unequivocal finality a few moments after a fire which occurred in the building a few days (fortunately) before its formal opening. The flimsiness and unorthodoxy of much of Mexico's building construction literally shocks not only the visiting U. S. architect or engineer but the layman. Actually as a whole it is more solid than it seems, for most buildings stay up although they may sag and age prematurely.


Since Mexico's architects are bound for the time being almost exclusively to the use of reinforced concrete, they have the opportunity and the necessity to study, experiment with, and to develop reinforced concrete construction. Their efforts in this direction have not been startling. Most of the standards and formulas with which they operate are based on U. S. specifications and standards. They have limited themselves almost entirely to a standard beam and column construction without much further query, and it is certainly open to question





The Costa Rica school by José Villagrán García was built in 1946 to accommodate some 600 pupils in one of the poorest and most overcrowded sections of Mexico City. Classrooms are







oriented E. S-E. as most desirable. Classroom windows are recessed and protected from late morning sun. "Socially and esthetically the most satisfying school in Mexico City," A. B. H.

that the ultimate in concrete construction has been reached with the conventional skeletal system. Slab or structural skin construction has been pretty well ignored in Mexico. Many architects have confined their structural innovations to exotically shaped bays or occasionally to seeing how many different types of bays they can combine in one building. On the other hand there are architects who have used the skeletal system both logically and economically and who are well aware of the opportunity and need to study and experiment with concrete construction.

Nationalism in Architecture. Internationalism is not very popular in Mexico right now. Justifiably, Mexico is weary of being a source of easy money for restless foreign capital. Mexico is as aggressively nationalist as her status permits. Her architects, too, reflect this attitude. They are interested in creating a truly Mexican architecture.


The architect likes to build monuments; he is enamored of spectacular forms, and he challenges Mexico City's uncertain soil with his aggressive skyscrapers. At times fearful and disdainful of his own country's culture potential, he borrows the appearances of other cultures, particularly the French. In the last two decades the ardent promoters of "truly Mexican" architecture have vigorously opposed the reliance on culture imports. They sincerely want to become truly Mexican, but it is not easy for the simple reason that Mexican culture has been spawned by Europe and has not yet been weaned from her. Also it would be foolish and impossible for






Mexico to deny the European components of her culture. But Mexico can come to terms with other cultures in her own way by adapting and modifying these cultural components to meet her own specific needs and conditions.

It is never easy for an architect to express the national or regional culture values of his country. These values are difficult to define everywhere, but in Mexico they are particularly arbitrary. To the Mexican architect, "truly Mexican" probably includes recognition of Mexico's architectural heritage, of the solemn Indian pyramids, of the exuberant and sumptuous baroque churches, and of the gracefully restrained early colonial buildings. In addition, "truly Mexican" probably implies to the architect the expression of the Latin temperament, which, according to popular belief, is composed chiefly of passion, imagination and enthusiasm. More rarely the interpretation of "truly Mexican" would include the expression of the Indian temperament about which there is no generally accepted definition except that it has become almost axiomatic to credit the Indian with considerable — though primitive — artistic talent. Mexican culture defies definition. It is derived from a civilization composed of harsh dualities - white vs. Indian, conquistador vs. oppressed, bloated rich vs. prostrate poor, cultured class vs. illiterate masses. It is





a country where glamorous façades mask dingy interiors, idealized laws shun contact with less attractive realities, and cultural imports compensate for the imagined deficiencies of the indigenous product. For such a divergent and ambivalent civilization pattern it is hard to find common denominators.

The Mexican architect talks admiringly of the rich and unorthodox color sense of the peasant or artisan, and then, 80 per cent of the time, he paints his own buildings and interiors insipid greens, timid blues, or pallid pinks. He points out the fine old colonial buildings, yet many of his own architectural creations are unruly and ornate. He blames the weaknesses of modern Mexican architecture on the lack of variety and the poverty of available materials, yet the colonial towns are limited to two structural materials, adobe and stone, and two decorative elements, paint and grillwork, and the buildings are exciting and profoundly gratifying visually. They are sturdy and well-proportioned. The sun transforms their elemental volumes and forms into a vibrant three-dimensional pattern of light and dark. Age has been gentle with the warm and lovely colors of the walls, and the delicate linearism of the iron grillwork is intensified by the severely simple background of the architectural forms. The Mexican architect has a



National Conservatory of Music, Mexico City, Mario Pani, architect. The two auditoria, one open, the other enclosed, have their stages back to back so that one great organ serves both. A unique feature of the plan is the soundisolated arrangement of the studios which branch like leaves from the corridors flanking the open air auditorium





Model of the A.M.S.A. Insurance Building, Mexico City, Enrique del Moral and Mario Pani, architects. The reinforced concrete skeleton is exposed above the third floor where the glass walls are behind the columns. On the second and third floors, the glass wall extends in front of the columns

vastly rich if confused culture to draw from if he is both sufficiently sensitive and sufficiently critical, and if he can once take time to study calmly and consistently.

The very passion and enthusiasm which has led the Mexican architect to espouse the cause of modern architecture with an ardor which the North American admires, often betrays him. His buildings are redundant. He becomes intoxicated with forms and elements and adds them together in a profusion which frequently destroys the harmony of the whole. The Mexican tends to act impulsively and not reflectively, but above all, he is continuously and frantically active, as though by the fury of his activity he can escape taking stock of himself and his country. It would be absurd to suggest that the Mexican imitate the more calm, more disciplined, and sometimes more prosaic Northerner. On the contrary, the fertile and vivid Latin-Indian imagination can and should produce architectural works that will enrich the entire body of modern architecture. In the 16th and 17th centuries Mexico built magnificent baroque churches whose form and spirit were quite distinct from the European development. Ecstatic decorative elements are disciplined and invigorated by the conventionalizing influences of Indian art. Mysteriously, the integrity of the whole structure is maintained despite the recklessly rich decorative treatments and the open mockery of the two-dimensionality of wall surfaces and the solidity of

columns. These churches were not built or designed by the invading Spaniard alone. The Indian and Spaniard together created these buildings. One of the most beautiful baroque buildings in Mexico City, the Sagrario chapel, is reputed to be the work of a full-blooded Indian.

Stylistic Trends. The bleak interpretation of the doctrines of "functionalism" as expounded during the Twenties and Thirties has been almost universally rejected. In its place have sprung up new ideas and new trends. One of the most popular is somewhat baroque in character. It has been fostered by the work of Mario Pani, in whose architecture the determinant elements are neither structural nor social, but formal, plastic, even decorative. Under the leadership of the dynamic and undeniably talented Pani, this new "formalism" is threatening to engulf the architectural school of the University. It has upset the rigor of some of the oldtime functionalists, who, along with a host of others, are ornamenting their buildings with the mannerisms and modalisms of Pani's architecture. These mannerisms are initially derived from a curious and personalized blending of the architect's neoclassic Beaux Arts education and his admiration for the work of Le Corbusier.

There is considerable and often quite bitter opposition to the "formalist" movement. One of the most articulate spokesmen and gifted architects of this opposition is Enrique Yanez. Both Pani and Yanez have recently built normal schools in Mexico City. These two schools lie but a few hundred yards apart. Pani's school is lavish and grandiose; Yanez' is simple, almost austere. Many of the architects who oppose the new formalism object to its indifference to social or economical considerations. Knowing that Mexico is poor, they feel that schools, hospitals, and other public buildings should be constructed as economically and, therefore, as unpretentiously as possible. They further realize that this does not deny the possibility of creating rich and beautiful architecture. Many of them object to the formalists' emphasis on applied plasticity and on the arbitrary designing of structure to carry out an a priori formal idea. They feel that form and structure should develop integrally and that decorative elements derive from the articulation of structural components.

Architects on both sides are interested in creating "truly Mexican" architecture. One of the most devastating charges that the group, which for the sake of convenience we will label "functionalist," levels against the "formalists" is that their architecture is foreign or non-Mexican in character. The only apparent justification for this charge is that the initiator of the movement. Pani, was educated in France. Actually the situation is almost the reverse. The functionalists base their charge on two facts: first, that by building extravagantly the formalists mock Mexico's true economic situation, and second, that the architectural forms they use are French imports. There is no question that economically speaking, Mexico should construct modest and simple buildings but it simply isn't Mexican to do this. Love of lavishness and ostentation are very prevalent Mexican traits. Architects are continually complaining of the insistence of their clients, including the government, on having buildings designed in such a way as to appear at least twice as expensive as they actually are. Show, luxury and adornment run through Mexican history from yesterday's silver inlaid coaches to today's sleek Cadillacs, from sumptuous churches to marbleized office buildings and pompous monuments. It is ironical to watch the erection of the imposing "Monument to the Mothers" designed by architect Villagran while alongside it are passing the actual Mexican mothers, barefooted, weary, and quite neglected. In Mexico public buildings tend to become monuments and private houses, palaces.

Certainly the formalists have been influenced by French neoclassicism and modernism, but the way in which the Mexican has mixed these two elements—often superficially and unanalytically, yet with zest and skill—is "truly Mexican." Furthermore, Mexico has an old affinity for French culture and there is little doubt that the present imports are more palatable to her than the "international style" was. The avidity with which the general public as well as the architect have seized upon the new trend is proof of this.

The triumph of the modern vernacular is not uncontested in Mexico. Its greatest rival is a burlesque on colonial architecture. Giddily ornate, atrociously proportioned, and hopelessly unfunctional, it has a firm grasp on the newly filled wallets of a large part of Mexico's growing bourgeoisie. Probably they derive a certain reassurance from its lavish show and traditional respectability - which they wishfully convert into a vehicle for their imaginary entrance into the haughty world of the aristocratic criollo. Then, too, its faint colonial aroma, which persists despite dilution by Californianisms and dispersion by current Mexicanisms, gratifies the popular nationalist spirit. Until recently Mexico has been spared the Babbitt-like conservatism of the middle class because she had no middle class to speak of. Now that Mexico is sprouting a middle class, factories and department stores, the rising prosperous conservative group may put a sharp curb on the future growth of the modern architectural movement.

It has often been said that the Mexican lacks a sense of the future, that his time dimensions are limited to past and present. Clearly it takes an appreciation of the future dimension to build up a culture, for this is a slow and arduous construction and can only be sustained by a people conscious of the future and of their responsibility to it. Perhaps the greatest contribution of the Mexican modern architect to his country has been his attempt to plan — to encourage both regional and urban planning. He has raised his voice against the chaos which wildly agitated, but unreflective, activity has wrought in his country. He has pointed out the heavy price that short-term thinking exacts. The Mexicans have no monopoly on the sacrifice of the future for immediate ends (to be translated immediate gains). They have merely developed a more overt sacrificial ritual than their more cagey northern neighbor. The Mexican



Guillermo Zamora Photo

One of Mexico City's finest office buildings was designed by architects Augusto Alvarez and Juan Sordo Madaleno, Leonardo Zeevaert, Consulting Engineer. Glass walls, with sliding panels, extend completely across the north façade in front of the columns. The building is both fully air-conditioned and centrally heated

architect has demonstrated his determination and his capacity to combat this familiar situation in two well-conceived programs — for hospitals and for schools.

The premise of successful planning is an honest and accurate analysis of the needs and conditions of Mexico's people, her natural resources, her productive capacity, etc. The Mexican architect cannot be praised too highly for his attempt to direct the energies of his government and of private groups towards an objective evaluation of the economic and social conditions of the country and towards unhypocritical self-analysis. If he succeeds in stimulating honest self-appraisal and is able to divert the thinking of his people beyond immediate pecuniary ends to practical, but long-term and socially-minded planning, the Mexican Nation will owe him an incalculable debt.

Mexico is full of contrasts. This is so obvious that it has become a platitude. Mexico is searching; she is looking for new solutions to the century-old problems of land distribution, imperialist exploitation, soil poverty and lack of water, and of conflict between the masses and the classes, the white man and the Indian. She is in a hurry; she is passionate; she is confused; she is pregnant with eager promise. As is Mexico, so is her contemporary architecture. It must be criticized with the severity that any worth-while movement merits and on the same basis it must be respected and admired.

IDEAS BORN OF WINDS AND WEATHER

House for John R. Stone, Topeka, Kansas; Schweikher and Elting, Architects

While the owner of this house posed a great many positive requirements, the list clearly identifies him as the sort of client a progressive architect likes to have. The list seems not only to test the designer's ingenuity, but also to urge him to assume complete freedom to adopt whatever forms and technology seem indicated.

The client's list: view toward city — sunlight in living room and bedrooms — partially enclosed yard or garden — small bedrooms for children — small studyguest room — master bedroom, bath and lavatories all in same room, only watercloset separated — built-in refrigerator and deep-freeze in wood in kitchen — masonry floor throughout — room for heater, laundry and a servant on another level — local stone with a wood that required as little upkeep as possible — a house comfortable in winter but particularly cool in the very hot Kansas summers.

The result is a veritable houseful of ideas, not the least of which is a system of warm-air, floor-type radiant heating (see page 86).

The ridge ventilators were designed to give the house additional ventilation in the summer. They are


screened and lead directly to sliding wood panels in the sloped ceilings. Panels are counter-balanced, weather-stripped, hand operated. The louver design was complicated by prevailing winds: they were placed for a southwest breeze in summer, but the winter winds are northwest, and the sustained velocity is quite high.

Additional ideas developed naturally from site considerations. The land slopes upward toward the west, and neighboring houses and passing traffic look down somewhat on the property. Hence the blank walls to the northwest, with only small windows to the southwest in the children's bedrooms and the study, and the high windows in the owner's bedroom (the angling bedroom walls on the plans seem to indicate glass, but actually the openings are full-height louvers). The wide gallery to bedrooms was planned to give southeast light, and to allow an indoor play area for the children, where also their mother could sit to watch them in the southeast garden. In general, then, the form of the house and its space divisions were planned to face the view, get the sun, and turn away from the roadway.





Hedrich-Blessing


The house presents four full glass panels as a gesture of invitation toward guests approaching the entrance loggia, and a few living room windows face the road and the neighbors; otherwise it turns the other way, facing a view and a sun-bathed garden. It also turns its back on the northwest winds that blow so fiercely in the winter; bedrooms (not shown) have only louvers on this side




Views from the other side (southeast) show large glass areas to bring the sunshine into the bedroom wing and the living room, with overhangs to ward off blazing summer rays. The several doors throw the children's play area in the bedroom wing open to the outdoors








Ventilation louvers shown on the sections run the full length of the bedroom wing, similarly in the living room portion and kitchen. They are screened, and, while open in the summer, may be closed against the winter winds by sliding panels





Left: bookshelves and cabinets line the blank wall of the living room. The entrance hall in the background has sliding doors opening to the garden, is designed to be completely open to serve as a breezeway in the summer, also as a sheltered porch

There is very little movable furniture in the house; practically everything is built in. In the owner's bedroom, below, the outside walls are completely occupied with built-in furniture—beds, bedside furniture, cabinets, and window seat and wardrobe



Wood walls, ceilings and soffits inside and out are rough-sawn redwood. Exterior finishing nails are Monel metal. Roof shingles are cedar. Sash, frames and shelving are redwood. The sliding doors to wardrobes are redwood plywood. Large sheets of glass are single thickness, quarter-inch plate. Other glass is ordinary double strength. All finished hardware is brass. Floors throughout the main floor are red split brick pavers. Exterior terraces are red sandstone. Chimneys also are of red sandstone. Lighting fixtures are flush wood and glass





MIRACLE (AND MECCA) ON 34th STREET


NEW HEADQUARTERS
FOR CRAWFORD STORES

Hotel McAlpin, New York City

Kahn and Jacobs, Architects







Ben Schnall Photo

First, to insure free rein in making this a fount of prestige for all the Crawford clothing chain, the owners secured control of the Hotel McAlpin. Then, almost every existing activity of basement and groundfloor, on three street fronts, was reorganized to make way for the marble arcade and block-long sweep of selling space. Below the ground line, hotel kitchens, bakeries and machine rooms were reshuffled to accommodate the immense spaces for alterations and repair, and for storage of clothing awaiting these operations. On the Broadway, 33rd and 34th Street level, not only did a number of smaller, unrelated shops have to be moved, but many of the hotel offices and functions cleared out and set up elsewhere.

Provision of the arcade was originally much debated, on grounds that it would eat up such a quantity of valuable selling footage. But study of the photo at left, though taken on a Sunday afternoon, gives some idea of how stimulating this feature is to trade. Large portions of the usual Broadway throng are shunted naturally off the sidewalk into the arcade, to discover themselves caught in fascination by serrations of the continuous show window. Moreover, the new street-level façade, store, and associated features such as bar and restaurant (treated separately on pages 107 to 109) have given considerable lift to straight hotel business at the McAlpin.



JULY 1947










Photo above, left, is balcony of mezzanine as it appears to customers entering by main door, off corner of 34th St. and Broadway (lower left in plan). Smaller photo is view from opposite end looking along the Broadway wall toward main entrance



Photo above is general view immediately after passing outside pylon with show case (see photo, page 91, lower right), and through the clear-glass main-entrance doors. To secure proportions of height necessary for this sweep of nearly 200 ft., the architects used slide-rule ingenuity to minute inch fractions in reducing the depth of their dropped plaster ceiling to absolute minimum. Not only does it conceal air conditioning ducts and conduit for the store's incandescent "pots" and fluorescent

panels, but also pipage essential to hotel services. They feel certain they "couldn't have gone a quarter inch higher." Columns, of course, had to be circumvented, since they bear all the weight of the many hotel floors above. In plan at left, forward stock spaces were obtained by moving hotel functions originally therein, some to regions in upper right hand corner; some, such as the room and registry counter, were simply pushed forward into the lobby. For Bar region, in plan, see pages 107 to 109





Solid heart of the store is this enclosure of stairway and elevator in Appalachian marble. View above is from landing between basement and main floor



Display window at right of elevator is for special merchandise attractions. Above, right: a similar device at right of service doorway on 33rd St.









Universality of Crawford operations is expressed in metal sculptures representing the four elements: air, earth, water and fire. Show window, flanked by fluted-glass panel in upper-right photograph, is one of three by which outsiders may look through into store, and window dressers enter the outside display areas



RESTAURANTS AND BARS

ARCHITECTURAL RECORD'S

BUILDING TYPES STUDY NO. 127



Ben Schnall Photos

ARCHITECTURE FOR EATING AND DRINKING

By Herman H. Siegel

RESTAURANT: "An establishment where refreshments or meals may be procured by the public; a public eating house" — Webster. Actually it is a generic term embracing all kinds and manifestations of "public eating house." However, the word may also convey the special sense of a more or less elaborate type, where the service is predominantly by waiter or waitress.

At points where fashion and luxury become clearly subordinate to the customer's budget of time and money, we shall make further type differentiations as: Cafeteria, or predominantly self-service type restaurant; Luncheonette, or predominantly counter type restaurant. There are also such sub-types as: Drive-in, or roadside restaurants (see ARCHITECTURAL RECORD, Sept. '46, pp. 99–106, for detailed treatment); Oyster Bars, Ham 'n' Eggeries, Hamburger Heavens, and other similar forms of speciality service.

These sub-types, aside from their special functional requirements, involved chiefly the same planning and design considerations to be treated here under the primary classifications. Such pseudo types as 'Tea Rooms,' 'Rathskellars,' etc. differ mostly according to 'atmosphere,' and not essential function.

BARS, whether independent services or integral features in all the foregoing restaurant types, vary chiefly in degree rather than kind, and are treated in a comprehensive section.

LIGHTING and KITCHENS, foremost factors for commercial land esthetic) success in all types, are given separate analysis.

Photos left, right: Sakele's, Brooklyn. Top: Tropical Gardens, N. Y. City. Herman Siegel, Architect; Ernest D. Rapp, Designer. S. Y. Construction Co. were general contractors for Sakele's

The definition of Restaurant might really be extended to bring it under the broader concept of Store. For after all, restaurants of every type and sub-type are strictly in the business of merchandising food. The same fundamentals of planning and design are involved here as in any other selling operation — first, analyzing and organizing factors of receipt, storage, processing and delivery of the goods for sale, in this case cookery and drink items; then, the attraction, distribution, comfort and convenience of customers.

It seems to me, from the point of comparative advantage in experience with both, that the principal difference for the architect, between restaurants and stores in the more usual sense, is that there are more





This globe, one of three in Sakeles' main dining room, gives general light, relieves a disproportionately high ceiling, and transmits ineluctable attraction to the glimpser from street

inherent complications in the former. Foremost among these are architectural-engineering problems in the nature of the factory production line. This crucial element of food "manufactury," in planning kitchens in relationship to other restaurant areas, is discussed at length on pages 119 to 121.

The Restaurant General Plan. Every restaurant operation is of course unique, even among chains, in that it follows to some extent its own methods and notions in catering to a predominant client type, existing for a particular location. However, it may be said that all restaurants are subject to a general plan, almost always involving consideration of the following basic elements: entrance areas, dining areas, kitchen areas, and frequently bars and cocktail lounges.

Entrance Areas: Exteriors, Entrances and Anterooms. In all restaurant types - down to the most frenetic luncheonette - exterior appearance, as a first consideration, should imply the particular operation's essential character. Within this figurative limitation, elements of the exterior must then attract, advertise, and compel to the entrance, and then inside, the patronage desired. Further, and within material limitations, the exterior treatment must take in account the contingent nature of existing locations (a condition imposed on the architect in perhaps 75 per cent of cases). The restaurant front should be distinctive, not disharmonious, in its given surroundings.

As a possible example, I shall cite Sakeles' (see photos pp. 96, 97), where effort was made to achieve definite character and compulsiveness in the front, at the same time regarding it as a compositional element in a larger given setting. To an existing fascia of cast stone and glass brick, the marble pier was added as architectural background for vertical signs advertising name and function. Within a new plaster surround, large glass areas with stainless steel trim were put at glare-reductive

From this example, I believe it is possible to illustrate another cardinal tenet in treating the front. Restaurant windows should expose, where possible, to potential patronage outside, all manners and varieties of inducement to come and dine within. Among these is the spectacle of diners already on location, enjoying appetizing food amid conducive surroundings and brisk service. Perhaps this exposé technique is less applicable to restaurants (in the restrictive sense) of the larger and more fashionable type; certainly, it is less so in cases such as Sakeles', catering not so much to a transient trade which must be induced, as to a more or less repetitive clientele. Sakeles', however, will serve to illustrate the point. Note in the photographs that behind the windows of the right-hand (dining-area) half, the curtains are partially open, to disclose not only a suggestive view of the diners and services within but also of such compulsive internal features, projecting their attractions through to the outside, as the globe of light illustrated on this page. Note also that the curtains on the left-hand, or bar-area, side are tightly drawn, permitting no certain disclosures either of internal features or of imbibing patrons (about which nicety more will be said later). Field's Restaurant, illustrated on this page, shows these principles carried architecturally further.

Exterior treatment should reflect restaurant character, as we have shown, and as character varies further according to type, from the large restaurant with its

Field's, New York City. Large restaurant window (left) discloses features within; discreet bar window (right) discloses mostly bottles. Separate bar entrance, far right. (Siegel - Rapp)



Ben Schnall Photos


air of veiled dignity — perhaps even seclusiveness — through the lesser *chi-chi* varieties, down to the cafeteria and luncheonette, we find the tendency in fronts toward more and more openness and forthright disclosure of what goes on inside. *Chockfull o' Nuts* is a widespread example of a luncheonette chain disclosing its *all* to street visibility. (See also page 116.) The completely open front of Reed's, a cafeteria illustrated on this page, is intended to show off the food-selection counter to outside appraisal, as a major inducement to enter in and partake.

The technique of bringing the actual service and even preparation of food out as far as possible through the show window is by no means confined to self-service and counter types. Lindy's and the Brass Rail, famous big operations in New York City, have contributed to the fad of refrigerated show windows, in which the displays of meat, fish, and fowl and vegetable vary according to season. Other forms of such display are the featuring of liquor, where the cellar is celebrated, or pastries, where baking is a house specialty. And then there are all the processes of hamburger, griddlecake and do-nut making shown directly in the front window. Every one of the "glorifried" ham 'n' eggs served to patrons in the specialty sub-type houses of that name, are prepared in full view of the potential customer looking on from the sidewalk.

Entrances, the actual doors, obviously should be the operative climax of all the attractive and compulsive efforts put into the exterior as a whole — a flawlessly operating springboard to the inside. Architects generally, I should assume, are already enough aware of the many marketed possibilities in full or semi-glass doors, operating on gravity hinges, etc., and responding like gelatin to push or pull, that I need not enlarge on this point. However, I should like to emphasize that wherever possible, in my own practice, I plan separate outside entrances into bar and restaurant areas under one roof, as in Sakeles' and Field's.


Anterooms. These areas will be strictly defined, of course, only in the larger operations, perhaps as foyers, vestibules, lounges, etc. In the less elaborate restaurant types, they tend to become simply open space allowances for circulation and orientation of entering and departing traffic; and in these respects must be carefully calculated, according to seating capacity and internal circulation, to avoid conflicts detrimental to trade.

Checkrooms and cashier-counter fixtures in these spaces should be unmistakably evident, but, if possible, not obtrusive. Wash and retiring rooms for customers are sometimes provided in anteroom areas. Preferably these facilities should be as close as possible to dining room and bar, certainly on the same level at least, although in many cases they are tucked up or down stairs to conserve essential service or dining space. This is an equilibrium that every architect must work out for himself in each particular situation.



The design of Reed's Cafeteria, New York City, is intended to give theatrical starring to its biggest selling feature, the counter, with large areas of glass on both street sides making complete disclosure of the interior. Self-service and counter-type operations make a particular practice of this, as if to emphasize, with all their business and bustle, that no dirt can ever gather in hidden pockets and corners, as the observer from outside can readily see for himself.

In the section above, note use of acoustical material, especially functional in self-service operations where customers handle trays with less finesse than professional bearers. Counter back-wall is of tile for cleanliness. Fresh air, circulated from outlets indicated, returns to exhaust ducts over service counter (see sketch page 121). Marble slab adds front distinctiveness; demarks bar and dining areas (see plan page 106). Floors will be green and white terrazzo. Photo below shows progress as of June 6. Siegel, Architect; Rapp, Designer; Chase Construction Co., General Contractors. Sketches by Ernest D. Rapp.



Alfred Cook Photo





Alfred Cook Photos

Entrance-Area Materials and Equipment. A salutary trend here, I believe, is away from such veneers as porcelain enamel, and even architectural glass, toward more use of brick, terra cotta, cast stone, terrazzo and marble, the suitability and proportions of each in any application to be determined by existing building relationships and the intent and character of the particular operation. Where the novelty technique in exterior expression involves refrigeration — as in Gallagher's Steak House, with the raw primary product displayed in the front window — consideration must be given to impervious show-case linings such as tile, Carrara glass or marble. And, of course, the surrounding clear glass areas must be triple-glazed, or otherwise adequately insulative.


In designing windows for liquor display, remember that these items are highly subject to pilfer, and must be safeguarded in some form of secure enclosure.

Dining Areas. Here the architect frequently finds himself using his persuasive utmost to bring the owner down from dreams of numerical seating maxima to realistic figuring on the number and types of seats most effective for his kind of business. I believe that in any kind of operation (excluding the strictly counter-seat), so-called "Pullman booths," used entirely, will accommodate more customers than any other seating method. This solution, on the other hand, is obviously static and uninteresting and does not, in my opinion, provide an effective long-range maximum. Furthermore, the architect, in working with the owner on the seating question, must continually be thinking of relationships to kitchen-

area capacity, and to circulation allowances for customers and service between the seat and table combinations finally adopted. When, within these limitations, a workable numerical maximum has been calculated, the architect must then persuade the owner to let him make it really effective with variations and combinations among Continental settees, Hollywood settees, Pullman booths, and ordinary tables and chairs, whether stock or custom built. Seating variations cannot be overemphasized and the most fortunate architect in this respect is the one whose site and given circumstances permit him to vary his dining-room floor levels, enabling patrons to look up or down at their public eating companions. (For example, see project illustrated on page across.) Such variations in level are useful also in planning to make dining areas expansible or contractible in keeping with fluctuations of custom.

Dining-Area Equipment and Materials. Seating: the very best booths and settees, I believe, are those constructed of hardwood frames, coil-spring seats topped with "air-foam" cushions, and spring backs with "air-foam" pads. A popular and serviceable covering is leatherette. Numerous plastics are now being used as covering material, but I believe they should be regarded largely as still experimental. Mohair fabric is sometimes used, but it is not nearly so wear-resistant nor easily cleaned.

Left: Glorifried Ham 'n' Eggs, N. Y. City; Samar Construction Co., Dsnrs. Below: Hollywood settees in Sakeles'; Continental settees, Pullman booths, along left wall; Rubber tile floor





Settee and booth seats should be at least 18 in. deep and about 18 in. high. Standard booth width for one person is 26 in.; for two, 44 in. Back heights seldom should exceed 4 ft.

Chairs are preferably constructed of hardwood frames, with innerspring units covered by a layer of hair and at least 2 in. of "air-foam," then muslin and top covering. Backs and arms of chairs should be separated from seats to prevent débris collecting. Booth seats and backs, for like reason, should be removable.


Tables. Primary considerations here, as with other furniture, should be wear resistance and ease of maintenance. Hardwood tops are fine looking, particularly in "atmosphere" operations, but are greatly subject to stain and cigarette burns and require ceaseless attention. Thickness of hardwood tops should be between 7/8 and 11/8 in. In restaurants making full use of table cloths, unfinished plywood tops are a possibility.

Probably for all-around utility, linoleum or plastic tops are the best specification, with the latter being particularly impervious to wear and easily maintained. The architect, however, should be certain of what's beneath the surface. Best foundations for both linoleum and plastic are $\frac{7}{8}$ to $\frac{11}{8}$ -in. plywood panels, with the top layer hardwood to prevent ripples in the surface covering. Lumber should be kiln-dried and the glue waterproof. Edging should be stainless steel.

Chrome-plated pipe *pedestals*, of about 4-in. diameter, are quite satisfactory. Four-legged tables are no longer much in evidence, because of the irksomeness of cleaning around them. *Bases* are preferably one-solid piece, the



Left: plastic-top, chrome-pedestal table in Hollywood booth at Tropical Gardens. Curtain is glass fabric; floor, asphalt tile; color scheme, red, white and mahogany. Above: table tops in Field's are plastic ''real wood.'' Certain table units here (not those in center, see left and right) illustrate the principle of ''deuces,'' that is basic two-placers that can be almost endlessly combined, but do not permit space wastage by one or two patrons. Floor is asphalt tile; walls are mahogany wainscot. Below: restaurant project for Florida. Siegel, Architect; Rapp, Designer. Seating is on rising levels not only for variety and flexibility, but also for picture-window view. Arrangement for air conditioning outlet and intake system (see section) is considered close to ideal. Special sketches by Ernest D. Rapp





Ben Schnall Photo

heavier and broader, the more stable and desirable. Tables on carpet should have heavy bases with broad spread.

Floor coverings may be considered under two general headings: resilient, including asphalt tile (plain and greaseproof), plastic tiles, linoleum and linoleum tile, rubber tile, cork and carpet; rigid, including glazed tile, quarry tile, magnesium composition, colored concrete, terrazzo and slate. Bases for the resilient types must be smooth and even (nail heads and grains of sand will show up under rubber tile, blemishing the wax finish; uneven flooring will cause cracks in asphalt tile). A well-laid double wood floor is usually successful with resilient types; also, smooth concrete.

Asphalt tile gives long wear for low cost, and is much less subject to chair and table-leg indentation than linoleum. Obviously the greaseproof variety is preferable for restaurant use. It is available in a wide range of colors in three grades, of which "Deluxe" affords the best selection. Easiest obtainable sizes, currently, are 9 by 9-in. squares, and 9 by 4-in. strips for borders and divisions. Thickness of $\frac{3}{16}$ in. is recommended for wood bases; $\frac{1}{8}$ in., for concrete.

Plastic tiles give long grease-, acid-, and practically waterproof wear in a wide variety of colors, but are at

Top: ceiling in Field's is of stone-type acoustical tile, fissured surface; draperies are by Dan Cooper; Adler Construction Co., General Contractors. Below: decorations and murals in



present still hard to get in quantity. The resin types, in my experience, give best performance.

Linoleum is again available in many colors and patterns, and with burlap backing, the only type to be considered for restaurant use. It tends to disintegrate under standing water and excessive heat; in these respects the "lino tiles" (oil-bonded finish) are a major improvement.

Rubber tile, in my opinion, is the best looking and among the best wearing of all the resilient types. It is also a great aid in acoustical treatment.

Carpet, of course, is the richest appearing and most resiliently luxurious of all coverings, and the most expensive. In general, I might say that both wool and worsted Wiltons are preferable to Velvets and Axminsters where heavy traffic is expected. Chenille weaves are woven seamless up to 30 ft., in width, have great sturdiness, luxuriousness, and variety in color and design.

Quarry tile, among the rigid floorings, is practically a must for Tavern "atmosphere." It is extremely durable and easily cleaned.

Terrazzo is probably the most durable and effortlessly maintained of all materials, withstanding wear almost like solid marble. In addition, the marble chips can be "composed" in patterns and color effects. Size of the pattern squares is important; the smaller they are with more division strips, the better chance of contraction and expansion without cracking.

Almost all the foregoing flooring types are benefitted by faithful waxing, which seals the surface and helps maintain the original colors.

Wall-Finish materials to substantial degree may be considered as extensions of floor coverings, since many of these, like terrazzo and the various tiles, natural and synthetic, are used effectively in such application, particularly in self-service and counter operations. Also varieties of the table-top plastics are available, in special wall color patterns and "realwood" textures, for counter fronts and wainscoting. All of these materials can

Tropical Gardens were designed by Winold Reiss, executed by Imperial Painting Co.; Karl Egger was the General Contractor. Note in photo, right, the 'deuce' principle in Continental settee



"take it" and are easily maintained, absolutely indispensable qualities along with "attractiveness" in restaurant specification.

For the fancier operations, hardwood ply paneling, varnished or lacquered, still rates high in withstanding time and abuse, though requiring frequent refinishing. This material, where curved surfaces are a factor, can be very costly and, in this respect, the flexible veneers on canvas or metal effect great saving. A newcomer among these (on metal) has the further advantage of flexibility without wood filler.

Acoustical materials are conditioned by legal restrictions in certain metropolitan areas; for example, in Class I buildings, fire-resistant materials must be used throughout; in Class III, 50 per cent of materials may be combustible, but not to exceed 3000 sq. ft.


Acoustical tile of the stone type comes in both plain and fissured surfaces. Paint (other than water-base) causes appreciable loss in sound-absorbing efficiency.

Perforated acoustical tile comes in both fire-resistant and combustible forms, in two thicknesses for varying conditions; can be painted repeatedly.

Perforated cement asbestos board with "rock-wool" or glass-fiber filler pads also can be painted.

Offending restaurant noises center at a frequency of about 512; any material selected should have a high sound-absorbing coefficient at this cyclic rate.

Air Conditioning, as a dining-area factor, is discussed under this heading in the kitchen planning section.



Above: front door of Tropical Gardens illustrates the principle in bar design of compulsive expression on the exterior, proclaiming but not disclosing the functions within. Below, left: bar in Field's is set apart from dining area by dropped ceiling and open fin-and-fluted-glass partition; dome lighting is cold-cathode



BARS

FORTHRIGHT disclosure in this department is definitely not in keeping, even where the service is offered in connection with a self-service restaurant such as Reed's (see page 99 and plan, page 106). Although prominent citizens may properly assert they "have nothing to hide" in occasional temperate indulgence, still they don't really like to do it on manifest exhibition. For this reason the exterior of Tropical Gardens (see page 97, as well as photo above), though striving for attractiveness and compulsion in line with principles for the restaurant front, has much smaller window areas, with curtains as a rule nearly drawn, to reveal very little to the street of the activities and personages inside. Still the front should express, as Tropical Gardens attempts, particularly in the doorway, the essential nature and character of the

Sakele's bar front and stools are covered in a red plastic material, padded. Bar top, display frames and paneling are of Mexican mahogany. Ceiling is Burgundy; walls are a deep red, to give warmth and intimacy in an unusually spacious bar area. Above far end of the bar, note balustrade of mezzanine dining space




Ben Schnall Photos

Below: checkered bar front in Solly Krieger's, New York City, is padded maroon and beige leatherette; top is Mexican mahogany. Step in lieu of usual bar foot-rest gives variety





In both Solly Krieger's and Field's Bar (below), glassware and bottles are given emphatic play as essentially decorative bar-area elements, with bullet-type spotlights focussing directly on them. Field's bar front provides a variation in use of striped mahogany plywood; top is a solid slab of Mexican mahogany. Dropped ceiling, which not only gives bar intimacy but conceals conduit and air conditioning ducts, is of stone-type acoustical tile with a fissured surface






operation, projecting all possible inducements to make the customer enter.

Field's Bar (photos on page preceding and left, below) shows how this area may be sequestered, to give it the required air of intimacy and privacy, from the dining areas, at the same time maintaining all possible feeling of spaciousness in fairly close overall quarters. Sakele's Bar (photos, left), a genuinely spacious area, is separated from the main dining room (see pages 98 and 100) by an existing structural wall. Still, in this large space with a high ceiling, the essential feeling of intimacy is sought through use of warm dark colors and subdued lighting.


Ceiling height was also a problem in Tropical Gardens (right), this being a full 16 ft., with walls only 20 ft. apart. The bar canopy, in conjunction with cove lighting over Winold Reiss's mural on the wall opposite, most economically reduces this ungainly dimension to an apparent 10 ft., with everything above almost completely blacked out. Moreover, this device effectively sets off the bar area from the dining regions, with food here a subordinate service to liquor.







Tropical Gardens bar front, directly above, is red leatherette with mahogany top. The same materials were used on the bar of Lottie's Dogwood Room (below, left), New York City, where the problem was to provide an intimate new bar in an existing room with a set 'atmosphere.' This was accomplished by a suspended ceiling and special lighting fixtures in the domes, similar to 'pin points,' for low intensity. Photo top, left, is of service bar at Cafe Wienicke, New York City; patterns are linoleum cutouts on plywood. Below is the Wienicke patron's bar. Siegel, Architect; Rapp, Designer, for all jobs on these two pages











Plan of Sakele's, directly above, shows bar and dining areas demarked by existing wall. Dotted line indicates mezzanine with two dining areas especially adapted for private parties. Rear portion of main dining room can be screened off during lulls. Bar and dining areas in Field's, upper right, though more closely associated, are still distinct. Plan of Reed's Cafeteria, right, depends largely on relationship of counter to kitchen





Left: awkward arrangement of existing columns had to be overcome in providing intimate bar with hung ceiling for Lottie's Dogwood Room. Above: plan of Tropical Gardens






NEW "OUT-OF-DOORS" CAFE OYSTER AND LIQUOR BARS

Grison's Steak House, San Francisco
Hertzka & Knowles, Architects

Taking space from two adjoining shops on Pacific Avenue, the architects have added, to the facilities of this renowned steak-and-chop house, new sea food and liquor bars, a cocktail lounge, and dining room giving the illusion of an out-of-doors café, with its vine-covered trellis and murals suggestive of Palm Springs. The problem was "to provide attractions for new customers, without frightening away or offending old trade."

Walls are knotty pine, stained dark; covering suggest-






ing brick was designed by Van Luit. Ceiling is knotty pine and acoustical board, painted blue. Display case of oyster bar is copper and glass, with blue background wall on which are mounted crab and oyster shells gathered from local beaches. Top of cocktail bar is Scotch wool-plaid, made impervious to burns and stains with plastic impregnation; trim is copper. W. Adrian was Engineer; Elizabeth Banning, was the Color Consultant.









Hedrich-Blessing Photos

NEW HORIZON ROOM CONTINENTAL HOTEL

Chicago, III.

Holabird & Root, Architects



In providing new horizons for this bar and restaurant, the architects have carried the mirror technique to points of unusual refinement. In the main dining area (photo at top), primordial creatures are depicted directly on the glass, set into a mural of their natural habitat under a broad overhang of plaster canopy. The motif is echoed in the bar, where the canopy has less formality, and jungle vegetation flanks a mirror left clear to receive the images of stool-top patrons. A three-step descent reaches the interconnecting dining area.

Front of bar is a field of padded black patent leather, against which are set 2-in. yellow-leather buttons. Bar top and back-bar working surfaces are plastic. Base is black and white terrazzo with brass dividers.

BAR AND RESTAURANT FOR HOTEL MC ALPIN


New York City

Kahn and Jacobs, Architects

PLANNED and carried out as part of the major overhauling given to the McAlpin's entire first floor—to receive the Crawford Clothing chain's new headquarters store and arcade (see pages 90–95)—this bar and restaurant has given immense lift to the hotel business. Major feature is a 90-ft. serpentine bar, with a front of wood intarsia by Hildreth Meiere. Back-bar murals of glass-and-marble mosaic, representing the nation's four principal geographical regions, are also by Meiere. Michael L. Radoslovich, architect in the office of Kahn and Jacobs, coordinated all the McAlpin renovations.




Bar entrance is off 34th Street; marquee at top of photograph is that of Hotel's main entrance. In photo below, ceiling cove lighting is cold-cathode; bar cove has regular fluorescent tubes










Ben Schnall Photos


Paneling in bar alcove (left) and main area (below, left) is flexible plywood on metal, mahogany finish. Floor is black and

white terrazzo with stainless-steel dividers. Entrance off hotel lobby (below, right) is faced with Colorado Colorosa marble





JULY 1947





FOR DAY AND EVENING SERVICE IN A DEPARTMENT STORE

H. S. Manchester, Inc., Madison, Wis.

Skidmore, Owings & Merrill, Architects

This double operation is unusual for a department store—by day serving store customers, for the most part, and in the evening, general outside patronage. Opening at 10:00 every morning and closing at 9:00 p.m., it offers four basic services: luncheon, afternoon tea, pre-




Smith-Wollin Photos


Photos left and below show views of State Capitol and grounds afforded by the Manchester Madison Room, "unequalled by any other restaurant on Capitol Square, and particularly impressive at night." Draperies are by Angelo Testa; furniture is

natural-finish birch; light-brown grospoint carpet covers dining area. View above shows street-entrance vestibule, with checkroom, left, and settees for waiting patrons. Note 'Running Men' wallpaper at right; background wall is deep brown





Symbol, left, designed by Rainey Bennett, appears on the menu covers, china, flatware, place mats, match-folders, Petri-dish ash trays, and as a free-standing wall fixture against the 'Running Men' background (see top photo, page across). The two "M's", on compass axis, suggest Madison as the hub of the state, and Manchester's, near to the Capitol, as the center of the city





Smith-Wollin Photos


theater suppers, and full dinners. It is one of the first phases to reach completion in Manchester's considerable building-and-alterations program.

Located on the second floor of the store's new addition, the restaurant has one entrance directly from selling areas, and another by stairs from the street. During shopping hours, only the store entrance is open, to draw traffic through the selling departments; in the evening, access is from the street alone. The consequence is a daytime patronage predominantly of women, with a much greater representation of men at night, requiring the general design to have appeal in both directions, with avoidance of an atmosphere too "tea-roomy." Another design requirement was that decor be keyed to Madison's out-of-door and sports way of living.

In this spirit, the stairwell slab wall is covered with "Running Men" wall paper, a Danish import designed by Kirby; the same motif appears on the menu covers, by Chicago artist Rainey Bennett (see top page 112). The slab wall of natural-finish white ash, before the kitchen entrance, features depiction of a major regional sport, and in the street-entrance vestibule, casein paintings, also by Mr. Bennett, show scenes around Madison: the lake, State Capitol building, and other features of historical and sporting interest.

Photos on this page show stair entrance from street, right, and entrance from department store selling areas, below, with folding screen closed for night operation. Table lamps (right, see also page 110) were designed and executed by Isamu Noguchi; gooseneck fixtures (below) by Kurt Versen. Store-entrance and kitchen walls are gray; ceilings, oyster-white acoustical plaster






In the plan above, seating is provided for 160. Restroom facilities for men and women are convenient at store entrance; checkroom, used mostly at night, is directly opposite street entrance. The kitchen and service areas show many features certified by experts (see pages 110–121), with distinct "In" and "Out" doorways, efficient fixture layout and convenient employee facilities





Lionel Freedman: Pictorial Services Photos





RENAISSANCE AT RIKER'S

Broadway and 104th St. New York City By Daniel Laitin, A.I.A.

This newest link in the Riker's chain presents almost all the unique problems usually confronting an architect with a stool-type restaurant on his boards.

In the first place, the allowed space for such operations is always about as big as a postage stamp. In a tightly limited area, the architect must somehow manage to fit most of the amenities of a large restaurant, never losing sight of the fact that cleverness and tricks of design must always be subordinate to "Operation Food." Dishes must be cooked and brought to the customer with dispatch, yet looking attractive. And "turnover" in this type of eatery is the key to its success or failure. This unit is in a hotel with access from the lobby.

Employee locker facilities, storage of canned goods, compressors, etc., were relegated to the cellar. Nevertheless, it took considerable juggling and slide-rule manipulation to fit all the necessary equipment into the tight space, and still come out with seats for 32 paying occupants. It has long been accepted that no waitress can serve more than 10 customers with proper efficiency, so three U-shape counters were used, with two places at the far end near the hotel entrance for bellhop service. The girls at this station call their orders on a speaker and pick them up a minute or two later on a conveyor belt, which returns soiled dishes to the washer.

The owners gave the architect complete freedom in the design, merely stipulating that he use some panels of glass mosaic, seemingly de rigueur for New York restaurants just now. Lately, the orgy of abortive misuse of glass mosaic, an intrinsically beautiful material and expensive, too (\$7.00 a sq. ft.), has caused conscientious architects to writhe and fume. This opportunity to do something about it could not be muffed! Artist Max Spivak, a glass mosaic expert with an imagination like Miro and a sense of color precision like Stuart Davis, accepted the challenge and came up with several delightful and colorful abstracts. The architect and artist believe that here they have brought art out of the museum and onto the street to be judged forthrightly and critically by the public. The response to these frequently misunderstood spatial fantasies has been terrific. One customer marvelled at the fact that the shapes took on new character each time she came in to eat.

The vibrant colors of the abstracts are keynotes for the interior color scheme, which includes spinach green, carrot red and butter yellow. Ceramic mosaic tile on the rear wall and behind the stainless steel equipment is matt black. Cold-cathode cove lighting gives smooth primary light distribution, and bullet-type hanging reflectors supply incandescent light where necessary to give the food its proper colors for good appetite.

ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

RESTAURANT LIGHTING WITH SLEIGHT-OF-HAND

By Thomas Smith Kelly, Chairman, N. Y. Section, I.E.S.

CURRENT implications are that the general practice of lighting tends more and more in the direction of an exactly quantitative science. Probably this is most true in cases of laboratories or libraries, where critical seeing tasks are the factors of first importance. However, in restaurants and bars, the rather unscientific factor of "atmosphere" is at least equally ponderable. Strict standards of visibility come closest to being all-important in kitchen areas, and in cafeterias and luncheonettes, where customers select food directly as "merchandise," rather than from a menu. But otherwise, restaurant lighting experts not only must be methodical technicians, but must know the techniques of theater and stage-set, and downright sleightof-hand!

All practitioners do well, of course, to start within the framework of recommended lighting levels, such as those published by I.E.S., or by the larger manufacturers. Quoting a cross-sectional example: "for restaurants, lunchrooms, and cafeterias, it is recommended that corridors be provided with 5 f.c.; dining room areas, with 10 f.c.; kitchens, pantries and serving areas, with 20 f.c. Displays, 50 f.c."

But, first, on a particular job, the lighting expert must familiarize himself absolutely with every dimension, surface, material, color and other architectural specification involved in the areas to be lighted. In addition to the tool of light-source intensity, there is that of color; and in addition to both, there are many traps for the unwary in the way of their use. There are excessive brightness contrasts to be avoided between light and dark surfaces (anything over 10 to 1 is very questionable); and mirrors and other specular surfaces must be guarded to prevent reflected glare, inimical to customer mood and comfort.

Color, in this mood respect, is most important. Among the major reasons for fluorescent lighting's popularity is its efficiency of lumen output, and the most efficient of all fluorescent varieties is the so-called "daylight" lamp. But under this source alone, with its red spectrum deficiency, restaurant operators and customers find their coffee looking gray, their roast beef, anemic; and ladies' make-ups, de-glamorized.

Speaking generally, the incandescent lamp is the best source of light where food and facial complexions are concerned, since it provides the complete solar spectrum. Frequently it works well in this connection simply as a mixing element with fluorescent. For showcases, glass-faced refrigerators, etc., soft white fluorescent may be used, producing satisfactory color values, and at the same


time less heat against the refrigerant than equal-wattage incandescent.

Whatever the means chosen for various uses and effects, modifications will surely be necessary in recommended area levels. For example, in a dining room where the atmosphere is to be strictly *intime*, tabular recommendations of 10 f.c. may be way out of line.

Regarding intensity calculations in general, it is usually wise, in early planning stages, to figure on overlighting, since intensities as a rule can more easily be reduced than increased, once a job is completed. Ultimately, of course, even in self-service operations where intimacy and relaxation are not of the first order. avoidance of too much light in any area is the one absolute rule to be laid down. But at the outset, lighting experts cannot really anticipate what owners will judge in the end to be the effects that they want, nor what refinements the architect or decorator will make in ceilings, walls, flooring, table tops, draperies, etc., adding to the final problems of light reflection and absorption.

In his overall approach to the possibilities of a particular assignment, the lighting expert will certainly prescribe nothing that does not harmoniously complement the architect's efforts and effects, nor those of the decorator. He will start with the exterior in prescribing


Lighting at far end of Sakele's main dining room is designed to supplement globes in drawing customer circulation into this area








ARCHITECTURAL ENGINEERING


TECHNICAL NEWS AND RESEARCH











Above, left: in Hutton's bar ''pin-hole'' projectors, centered over table and bar tops, give areas of intimate 'isolation.' In main dining room, right, coves supply chief light, with two chandeliers for sparkle. Lowered area, under ducts, has ''pin-hole'' system. In plan, R represents pin-holes; S, surface mounted; U, indirect urns. H. H. Siegel, Architect; E. D. Rapp, Designer. Thomas Smith Kelly, Lighting Consultant

for architectural attraction, and for internal features of compulsion, possibly a chandelier or illuminated mural, magnetically visible to outside observers.

Sleight-of-hand makes its ultimate contribution in lighting for concealment, such as throwing displeasing but unavoidable structural features into obscurity, by accentuating attractive points of interest. An example is in Tropical Gardens (see also pages 92 and 95) where lighting effects are instrumental in reducing a disproportionate 16-ft.

ceiling to an apparent 10.

But here also, the lighting expert must be wary. The principle of architecturally built-in lighting is generally sound, but mistakes, or devices that lose their charm, are expensive to correct. Coves particularly can be disappointing. Remember that even with a matte-finish ceiling it is difficult to get from coves an advantage much greater than three to one. That is, to get a smooth spread across a 5-ft. ceiling, the coves on either side must be at least a foot down from the ceiling line (allowing for necessary overlap).

The expert who bears in mind these admonitions, and calculates all his factors with precision and imagination, still cannot be confident of his results until tested against public reaction. Lighting, like architecture itself, can be correctly executed according to every technical and artistic canon and still fall resoundingly flat before popular judgment. Close to supreme achievement, I think, is in a job recently offered to a prominent lady decorator's appraisal. "It's perfectly charming," she said, "but where are your lights?" She was answered by the flipping of a switch, plunging the room into darkness.

My own favorite incandescent tools are the PAR 38, the R-40, and the T-10 reflector showcase lamps. "Slimline," among the fluorescents, gives longer tube lengths with smaller diameters, instant start, variety of intensities, and the substantial single contact base is a big improvement over the fragile bi-pin. "Circline" is a great help in bar and restaurant lighting where curves are a factor. Cold-cathode fluorescents are more useful in decorative and display applications than where visibility is a prime consideration (less lumen output per running foot). It also requires careful planning and installation for its highvoltage operation, but has the advantage of longer life, compared with hot cathodes. It is very satisfactory, in a variety of shapes, lengths and colors, for use in domes, coves, along curved partitions, and with dropped ceilings of various irregular shapes.

RESTAURANT KITCHENS

Material for this section was supplied by Herman H. Siegel, Architect; Harry Greitzer, Viking Kitchen Equipment Co.; Samuel Greenspan, Nathan Straus-Duparquet, Inc., with all photographs from the latter. Data on ventilation and air conditioning is from Peter Frank, Armo Cooling & Ventilating Co.

Photo at right shows Garde Manger section in kitchen of the Mayflower Hotel, Washington, D. C., executed by Straus-Duparquet. Foreground: bread warmer; behind, sea food bar



Reni Photos

T has been said that the restaurant architect's job is to attract customers; after that it is up to the operator to hang on to them with good food and service. But the architect has a manifest responsibility here, too. Bad planning in this department results not only in loss of custom, but in excessive china breakage, loss of silverware, spoiled food, actions by the Board of Health, and numerous vexations to the help, with consequent loss of their efficiency and even hire.

Essentially every kitchen area, for all restaurant types, conforms to certain basic requirements, and to an ideal plan of layout and relationships among the indispensable functions: receipt and storage of food, preparation, cooking, service, and utensilry washing. It is difficult, however, to be statistical regarding proportions of total area required for these operations to total dining space. It should be obvious from the preceding Building Types Study that require-

ments at Sakele's, offering full-course menus of wide selection, are vastly different from those in Tropical Gardens, where food is almost an incidental service to liquor. It is possible simply to say that kitchen and service areas, in currently successful operations, are occupying between 50 and 100 per cent the total area of dining spaces, with increasing tendency toward the top figure, to accommodate all the provisions recommended by experts for smooth efficiency.

First consideration, in establishing the layout and relationships of kitchen and service areas, must be unimpeded one-way traffic of all personnel. Waiters should enter the kitchen from dining areas, and leave by separate doors, ideally operating by "magic-eye" in the one necessary direction. A waiter entering from the dining room, presumably with a load of dirty dishes, should come immediately upon the washing section, where he deposits his tray, proceeding then to pick up new orders. Next in line

should be the Garde Manger, or salad, sandwich, cold meat and sea food section. After this, the Hot Food Area, adjacent to ranges and cooking equipment, followed by the dessert, pastry and beverage section, the last before return to the dining room. Preparation, storage and receipt areas should be entirely distinct from all the above, with the latter adjacent to outside delivery entrances. However, all sections, distinct or integrated, must be closely related for convenience and efficiency, preferably contiguous or with adequate means of vertical communication.

Basic equipment for the Dishwashing Area includes: shelves or ledges on the soiled dish table to rest trays for unloading; preliminary soaking sinks; pre-flushing equipment to carry off the loosened swill, permitting longer operation of washing machines without change of water. Glass washing equipment should be of the brush type, with a series of gentle slides below table level to assist in

Below, left: Hot Food Area in Mayflower kitchen, with warming units in close-up. Right: Mayflower dish and glass washing



section, showing exhaust hoods over washing machines; stacking baskets for glasses. Service tables contain trays beneath



ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH



Left: washing equipment in Restaurant of Namm's Dept. Store, Brooklyn; Morris Lapidus, Architect; kitchen, Straus-Duparquet.



Note soaking sink and pre-flush for swill. Right: Mayflower preparation equipment; note vegetable parer at far end of sinks

basket-stacking of glasses as they emerge from the washer. A silver-washing machine is now available which cleans by means of a revolving barrel, filled with small metal pellets. In addition, this equipment sterilizes and burnishes, requiring no drying.

Efficient new equipment for the Garde Manger section includes mechanically refrigerated units for salad, cold meats and sea food, to be hooked in very economically with the main refrigeration system. Of great advantage here, as in other pick-up sections, are counterweighted units permitting the stacking within of dishes and trays; only the top two or three protrude above table level, regardless of the many or few pushing up from beneath. These units can be cooled or heated, and insure minimum

exposure of the dishes or travs contained.

For the Hot Food Area, incessant refinements in pressure cookers and kettles, baking and roasting ovens are more and more obtainable. Units to keep food warm until serving are almost indispensable; one type of shelf unit, for installation above the cook's table, is designed to hold complete orders. Its upper tier has an insulated core and convex bottom, returning heat from the lower tier on which the food is placed. Removable grease filters in range hoods are a great convenience in this section.

General provisions for kitchen and service areas should include: rounded corners and cove bases; welded stainlesssteel surfaces (nuts and bolts are great dirt collectors); ramps in place of steps, if changes in level cannot possibly be


avoided; impervious floors, walls, and even ceilings (see discussion of materials, pages 97-103); floor drains for daily hosings; at least 20 f.c. of light at working levels; such conveniences, where possible, as walk-in boxes with electrical germ-killing devices and magic-eye operation; and, of course, such employeemorale maintainers as locker-toilet-restroom facilities and adequate ventilation in all regions.

Ventilation and Air Conditioning

Prime purposes of a restaurant's ventilating system are the removal of foul air and heat from kitchen areas, and the prevention of these in dining spaces. Bad-air exhaustion should take place as close as possible to points of origin. Range hoods preferably should be no more than 6 ft. above the floor; dishwashing machines should have hoods over each opening. Construction of all hoods should be such that there is a narrow curtain of high velocity air around the exhaust perimeter.


With any extensive exhaust system, a positive supply of replacement air must be provided (relying for this, to any considerable degree, on haphazard filtration through doors and windows, makes many difficulties). A controlledintake balance should provide a little more air supplied than exhausted in dining areas, with the reverse holding for kitchens. This maintains a slight flow of air from the dining areas, in one direction toward the kitchen to repel odors, and in the other toward the street, to prevent drafts. Also, this replacement air should be heated. One method is simply preheating to room temperature, for preventing cold drafts; another is to make it the principal heat carrier, eliminating radiators. Protective measures


Below, left: Mayflower cooking equipment; soup kettle in left foreground; behind, pressure vegetable cooker; at right is box for prepared fish, with small drawer for scallops, etc. Photo at right shows unit for booth-service utensils, coffee, water, etc. at Namm's







George W. Nuckols Photo









Plan top, left, is kitchen and counter layout in Reed's Cafeteria (see also pages 99 and 106). Inset photo at top, right, with plan of Riker's (see also page 116), is actually equipment at Namm's, but illustrates means of intercommunication between counter and kitchen, essential to this type of operation. Drawing directly above, left, shows prevention of 'short circuiting' in operating air conditioning with counter-hood exhaust. Plan at right, directly above, is kitchen of Field's Restaurant and bar (see also pages 98–106)

must be taken to prevent freezing of heating-coil condensate at below 32° F.

Air-conditioning factors vary according to restaurant types. It is possible that in self-service and counter operations, temperature and humidity will be kept at lower general levels of difference, between inside and outside, than in

restaurants where patrons stay longer.

Automatic control is very important, particularly in cafeterias and luncheonettes, with their rapid changes of occupancy and short, heavy loads during peak periods. To meet these fluctuations, compressors are probably the type of refrigeration source most generally used.

It is usually good practice, when external conditions warrant, to use outside air entirely for conditioning systems. Otherwise, just enough outside air is introduced to maintain the balances described previously, with the main body recirculated. Replaceable-type filters are most practical for both air conditioning and ventilating purposes.

Inlets for air-conditioning and ventilation must be calculated carefully, not only to avoid drafts but to prevent short-circuiting of air-circulation to exhaust openings. Also general architectural schemes must be studied for harmony of outlets with room shapes and seating plans. A harmonious example, in this respect, is illustrated on page 101.

TECHNICAL NEWS AND RESEARCH

JULY 1947

ARCHITECTUAL RECORD

THE DRAWING OF ACCURATE CURVES

By Sterling M. Palm, Architect

The handling of curved and double curved surfaces has long been commonplace in the shipbuilding, automotive and airplane industries. Although such surfaces have not appeared so frequently in architectural design, they are becoming more and more apparent in contemporary design. It is not the intent of the present discussion to go into the method of such surface delineation, but a brief statement of the basic principle provides a good starting point.

A curved surface, to be a smooth surface, without humps or depressions, must be so formed that a section through the surface will be projected as a "smooth" regular curve in that plane. A curve to be "smooth" must be such that the rate of curvature, or radius, at any point does not change too rapidly with respect to the rate of curvature at any adjacent point. Any curve which will perfectly meet this requirement will be found to be a "conic" of some type, or a combination of conics. Thus a review of the characteristics of the conics is essential to the study of surfaces.

The study of these curves also provides a valuable tool for the delineation of curves of any type and have a number of practical applications in architectural or engineering work. One might venture to state that any curve which is pleasing to the eye would be a conic or combination of conics, which might in itself be inducement enough to invite some study.

A "conic" may be defined as any curve formed by the intersection of a plane with a right circular cone. Referring to Fig. 1, it is evident that an infinite variety of curves is possible, dependent on the slope of the sides of the cone, the slope of the cutting

PLANE "A"

(I TO AXIS)

CIRCLE

PLANE "B" (CUTS BOTH
SIDES OF CONE) - ELLIPSE

PLANE "E" (ANY INTERCONIC OF INTERMEDIATE PLANE)

PLANE "C" (PARALLEL TO
ELEMENT OF CONE) - PARABOLA

PLANE "O" (PARALLEL TO AXIS)
PLANE "O" (PARALLEL TO AXIS)
PLANE "O" (PARALLEL TO AXIS) -

plane, and the relation between the cutting plane and the axis of the cone.

All of the conics described by planes A to D in Fig. 1 are familiar curves, possible of simple mathematical description and analysis. There are, in addition, an infinite number of intermediate conics produced by the intersection of plane E with the cone, approaching one or other of the basic types, and each possible of mathematical analysis.

Although the mathematics of the conics forms an interesting study, no space will be devoted to it here. We are primarily interested in an understanding of the conditions differentiating one curve from another, and in a practical application of the principles involved. Fortunately these principles are extremely simple and entirely general in nature. To anyone familiar with the procedure it should no longer be necessary to refer to a handbook to refresh one's memory as to the method of constructing a parabola or hyperbola; for these, together with an ellipse or even a circle, can all be constructed by the same simple

In the latter part of this discussion I will, for the benefit of those interested, develop a proof of the method about to be described. However, for those who just wish something for ready reference, it will only be necessary to follow the procedure outlined in Figs. 3 to 7 inclusive. Fig. 2 is introductory, but shows clearly the entire procedure necessary for the determination of any one point on the curve, developed to greater length in Fig. 3.

It can be shown that every conic or second-degree curve can be determined, given any one of the following five sets of conditions:

Case I. One point and two pointslopes (direction of tangent).


Case II. Three points and one point-slope.

Case III. Five points.

Case IV. Two points and a point-slope-curvature.

Case V. A point-slope and a point-slope-curvature.

Cases IV and V will not be discussed as their treatment would require more space than warranted. Fig. 5 illustrates the method of determining a sixth point on a conic given five points (Case III). In practice it generally will be found that



one or two tangents are known, together with one or two points of tangency and with an additional point or points on the curve available, so that Cases I and II above will be found to be those most generally useful. These cases are illustrated in Figs. 3 and 4.

Referring to Fig. 2, we have two tangents, OA and OB, with two points of tangency, a and b. Point a on the tangent OA and point b on the tangent OB constitute two point-slopes. These are, in themselves, insufficient to determine a curve. If, however, we are given an additional point, such as point c, it will be seen that we have the previously listed first set of conditions, namely, "one point and two point-slopes."

In order to find any other point on the curve the procedure is as follows: Draw a line through a and c prolonged to intersect OB at 1, and a line through b and c prolonged to intersect OA at 2. Now through O draw any line, 3-4, known as a "ray," or in later reference, a "Pascal line." Designate as p the intersection of this ray with line a-1 and as q the intersection of the ray with line b-2. Draw lines through a and q and through b and p. These lines extended will intersect in a point, d, which is the point sought lying on the curve. Additional points on the curve are found by repeating the above process, after which the points are connected with a smooth curve by means of a french curve, ship curve or spline.

Fig. 3 illustrates merely an expansion of the above principle so as to determine a number of points on the curve. Fig. 4 illustrates the application of the method by the second set of conditions, namely three points (P, A and B) and one point-slope (point of tangency T on the tangent XY).

It will at times be found necessary to draw a tangent to a given curve at a given point. Figs. 6 and 7 illustrate the application of the foregoing principle, in reverse, in determining such tangents.

(Continued on page 127)

TIME-SAVER STANDARDS

ARCHITECTURAL Engineering

JULY 1947

ARCHITECTURAL RECORD

TECHNICAL NEWS AND RESEARCH

Fig. 3. TO CONSTRUCT A SECOND-DEGREE CURVE THROUGH A CONTROL POINT D AND TANGENT TO LINES OA AND OB AT POINTS A AND B:

- 1. Draw line BE through D and line AF through D.
- Divide DF into any number of spaces, e.g. four. This gives points G₁, G₂, and G₃.
- 3. Draw BG1, BG2, and BG3.
- 4. Draw OG_1 , OG_2 , and OG_3 , intersecting BE at H_1 , H_2 , and H_3 .
- From A, draw AH₁, AH₂, and AH₃, extended to intersect BG₁, BG₂, and BG₃, respectively, at points P₁, P₂, and P₃, which are points on required curve.
- 6. Additional points P₄, P₅, and P₆ are found likewise.
- 7. Curve fitted to these points is the required curve.

Fig. 4. TO CONSTRUCT A SECOND-DEGREE CURVE TANGENT TO LINE XY AT POINT T; GIVEN THREE OTHER POINTS ON THE CURVE, P, A, AND B:

- 1. Draw lines BT and PA extended to intersect at point 1.
- 2. Draw lines PB and TA, intersecting at point 2.
- Draw a line through points 1 and 2, extending to intersect tangent XY at point O.
- 4. Draw line OP, which will be tangent to the required curve.
- Having two tangents, OT and OP, two points of tangency, T and P, and a control point, A or B (whichever is more convenient), proceed as in Fig. 3 to find additional points on the curve.

Fig. 5. TO FIND A SIXTH POINT WHEN FIVE POINTS (1, 2, 3, 4, AND 5) ARE GIVEN:

- 1. Draw lines 1-3 and 2-4, calling intersection point o.
- 2. Draw lines 2-5 and 1-5.
- Draw any "ray," AB, through point o, cutting line 2-5 at p and line 1-5 at a.
- 4. Draw lines through 3 and p and through 4 and q, intersecting at point 6, which will be an additional point on the
- 5. Repeat procedure with different rays to find other points.

Fig. 6. TO CONSTRUCT A TANGENT:


(Given, second-degree curve OB, tangent to CO and CB at points O and B, respectively; tangent to be constructed at any point, P.)


- 1. Select any two points, M and N, on curve OB.
- 2. Draw PN and BM, intersecting at point D.
- 3. Draw PS and BN extended to intersect PS at point E.
- Draw a line through intersections D and E, extending it to intersect tangent BC at point R.
- 5. Draw a line through P and R, which will be required tangent.


Fig. 7. TO CONSTRUCT A TANGENT:


(Given, second-degree curve HJ; tangents to be constructed at any two points, P and T.)


- Select any three points, A, B, and C, located conveniently between points P and T.
- 2. From P, draw lines PA, PB, and PC
- 3. From point T, draw TA, TB, and TC
- 4. Extend PA and TC to intersect at E.
- 5. Extend TB to intersect PE at G.
- Call intersection of lines TA and PC, point D, and intersection of lines TA and PB, point F.
- 7. Draw lines DE and FG, extended to intersect at R.
- 8. Lines RP and RT are required tangents at points P and T.













ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

PRODUCTS for Better Building





Metal-clad curtain wall consists of insulated panels carried on steel channel studs

CURTAIN WALL

The steel or concrete skeletal construction of modern buildings has long been a challenge to develop a lightweight insulating skin that will take full advantage of a curtain wall system. (See "The Better Wall Is Coming," by Robert L. Davison, Architectural Record, November 1946.) Why use a heavy masonry wall, 13 in. thick, if thin metal-clad panels can be made to do the job as well, or better?

Now in the final stages of experimental research is the *Metal-Clad Insulated Curtain Wall*, developed by William Lescaze, Architect, and Robert L. Davison, Designer. The basic wall unit is a sandwich-type panel of insulating material, such as Foamglas, between an inner and outer face of ordinary steel and stainless steel. Other insulating materials under study are microporite and vermiculite, and for the metal skin, aluminum and copper.

Although these wall units are only $3\frac{1}{2}$ in. thick, it is claimed that they provide almost six times the insulation of a 13-in. masonry wall. The reduced wall thickness increases floor area considerably in a large building. A typical wall unit 52 in. square, weighs less than 200 lb., one-seventh to one-twelfth the weight of a wall in conventional brick, or brick and tile construction. Erection is simpler

and cheaper because a single panel replaces approximately 115 masonry units.

The wall system is horizontal. Two of the panels span from the ceiling of one floor to the ceiling of the next so that the wall is divided horizontally into two parts. The lower half is a line of solid units, bolted to the conventional concrete or steel frame. The upper half is arranged into various combinations of windows and wall.

Erection steps are as follows:

- 1. Vertical steel channel studs are bolted to anchors inserted in the spandrel beam on 4 ft. 4 in. centers, regardless of column spacing. Anchors are adjustable to permit exact alignment of the studs.
- 2. Continuous horizontal sill and head members are attached to the studs.
- 3. Wall panels are slipped in place. (In a variant, the panels are bolted to the studs, and sill and head members are then attached.) Vertical joint is sealed by a prefabricated spline.

4. Following completion of the spandrel panels, the window strip is installed. Windows may be placed at any point.

Development work was sponsored by New York Housing Trust in cooperation with Republic Steel Corporation (which may eventually place such a wall unit on the market) and Pittsburgh Corning Corporation.

FOLDING DOORS

Modernfold doors and partitions consist of a series of vertical semi-rigid accordion pleats on a steel frame, which slides along an overhead track. Covering material is Fabrilite, a Du Pont vinyl plastic coated fabric, said to be fireresistant, washable, and resistant to cracking. Pulls and handles are also of plastic. A lock or latch may be attached. Units are available in standard-size door widths; or custom-made to fit other openings. Fabrilite has been approved by the Board of Standards and Appeals for covering folding partitions in places of public assembly. New Castle Products, New Castle, Ind.

FLUORESCENT LIGHTING

The Surface-Attached Holoflux fluorescent fixture features a prismatic cover designed to give maximum illumination without glare below or strong shadows above. The units are designed to take either two or three lamps and may be installed singly or in multiples, mounted directly on the ceiling or suspended on stems. They are fully enclosed. Holophane Co., Inc., 342 Madison Ave., New York 17, N. Y.

ACOUSTICAL BOARD


Fiberglas acoustical board is dimensioned to fit between recessed fluorescent light troffers and thus form a suspended ceiling with sound-absorbing properties. The 1-in. thick board, made from specially processed glass fibers treated with thermosetting resins, reportedly offers other advantages of being noncombustible and non-warping. It will span 24 in. without sag or cross support; and is




Panels of acoustical Fiberglas fit between light troffers to form a suspended ceiling

cross-grooved to resemble tile, painted white at the factory. According to tests, its noise reduction coefficient is quoted as about 0.80; light reflection coefficient, 0.75 to 0.80; and weight, 0.75 lb. per sq. ft. Moisture reportedly produced no change in dimensions. Owens-Corning Fiberglas Corp., 718 Fifth Ave., New York 19.

(Continued on page 146)







Shown here are only a few of the many commercial and industrial buildings built better and faster with Celotex Cemesto Board.

Cemesto is perfect for speedy, low-cost construction of insulated buildings. It offers thermal insulation, weather resistance inside and out, structural strength and siding... all at *one low cost*. In addition, Cemesto core is Ferox-treated to resist dry rot, fungus growth and termites.

Cemesto comes in standard size sheets in 11/8", 1-9/16" and 2" thicknesses; can be easily cut to fit job conditions; can be attached by nailing to wood, by bolts or clips to steel.


Thus Cemesto is an ideal material for use in exterior walls, roof decks or interior partitions. It does not require painting, so maintenance costs are low.

Write the Architectural Sales Service Department for complete details illustrating several methods for applying Cemesto for roof decks, exterior walls or interior partitions.

If you wish to furnish plans to us, we will be glad to prepare shop erection drawings showing the exact size of Cemesto panels required, together with estimate on cost of material pre-cut to fit.

THE CELOTEX CORPORATION · CHICAGO 3, ILLINOIS





Look Before You Light

look for modern, functional fixture design look for lasting lighting efficiency look for easy, low-cost maintenance

VIZ-AID is attractively styled in quiet, good taste.
It is optically engineered to give years of highintensity, even, glare-free light. It is structurally
designed for quick, economical cleaning and servicing.
Send for Bulletin 10-B-1.

The VIZ-AID

For ceiling or suspension mounting—unit or continuous installation. Designed for two 40- or two 100-watt lamps. U. S. Patent Nos. D-138990, D-143641 and 2411952.

Day-Brite Lighting, Inc., 5465 Bulwer Avenue, St. Louis 7, Mo.

Nationally distributed through leading electrical supply houses.

In Canada: address all inquiries to Amalgamated Electric Corp., Ltd., Toronto 6, Ont.



IT'S EASY TO SEE WHEN IT'S

DAY-BRITE

CS VERY


TECHNICAL NEWS AND RESEARCH


JULY 1947

ARCHITECTURAL RECORD

THE DRAWING OF ACCURATE CURVES

(Continued from page 122)





Referring again to Fig. 2, it should be noted that the point c, which was selected somewhat at random in this case, is of particular importance, in that, with two point-slopes oa and ob given, the character of the curve will vary considerably depending on the location of the point c, known as the "control" or "shoulder" point. The extent to which the control or shoulder point influences the shape of the conic is illustrated in Fig. 8, in which, with two equal tangents, ob = oa, the control point d is so taken that cd = cb = ca. The resulting curve in this case will be, as expected, an arc of a circle.

If point e were to be used as a control point, the resulting curve would be a parabola or other conic, depending on the exact location of point e.

In Fig. 9, the control point D is determined by projecting down to diagonal oc from the intersection of circular arc ag with diagonal ec. With D as a control point, tangents ec and ec and points of tangency ec and ec a quarter ellipse would be anticipated. Following the procedure previously outlined and using the conditions

stated, it will be found that an accurate ellipse will result.


A parabola, hyperbola or other conic will be determined similarly when there is given, in addition to the point-slopes, a control point which is known to lie on the curve in question. Mathematically, the slope of the tangents can be determined once the equation of the parabola or hyperbola is known. In a great number of cases however the tangents will be given, so that it will be possible to construct these curves without recourse to mathematics.

PRACTICAL APPLICATIONS

There are many practical applications of the foregoing principles, among which might be included the following examples. In all, it should be noted that the process consists of determining two points of tangency on their respective tangents (i.e., two point-slopes) together with a control point. Following this, the method outlined in Figs. 2 and 3 is followed to determine points along the curve.

Possibly one of the most useful applications consists of transforming a curve, carefully determined by freehand methods, into a definite geometric figure which can be duplicated, enlarged or otherwise utilized. Such a curve thus becomes definitely tied down. Fig. 10 might represent a profile, a section of a surface or possibly a roadway.


The usual method of duplicating this curve would be to determine, by trial, a series of radii describing sections of the curve, or possibly a system of offsets from a traverse line might be established. Both of these methods or others of a similar nature are tedious, inaccurate, and crude as compared to the simple and direct method of conics. This principle, as applied to the case at hand, would consist of splitting the curve up into convenient sections, such as ab, bc and cd of Fig. 10. Tangents would then be determined at points a, b,




c and d and control points in each section, such as k_1 , k_2 , and k_3 . The curve is now definitely tied down and can be reproduced exactly. Some points on the curve should be checked by the method described in Fig. 3, and if discrepancies appear it will undoubtedly be apparent that the free-hand curve was not smooth at the point in question.

A similar application is illustrated in Fig. 11, which represents a street line consisting of two circular arcs AB and BC of radii such that the centers are inaccessible or off the drawing. The arc lengths being given, the central angles, I and 2, can easily be determined and consequently the tangents for both sections can be plotted. The distances O_1I and O_22 may then be computed, being in each case equal to R times exsec of half the angle. We would then have established for each section the two tangents and control point, after which points on the curve would be determined as previously described.

Fig. 12 illustrates the application of the principle to the construction of a moment diagram, such as might be required for use in the design of a plate girder. For the sake of simplicity, a uniformly loaded beam is taken, although the process can be applied to any system of loading. Inasmuch as the shear diagram gives the slope of the parabola representing the moment diagram at any point along the span, the slope at the two supports a and b are each equal to (Continued on page 129)





"There's a long, long trail"


The hot flue gases in an H. B. Smith Cast-Iron Boiler rise directly to the highest surface of the boiler, across to each side, to the front through the upper flue passages, then to the back through lower channels, and finally up the chimney. It's really a long, long trail . . . and not a straight one.

Actually, the gases would rather rush directly to the chimney, but the efficient "Mills" design hinders them at every turn. Instead, they're scientifically-directed along

paths which give them a chance to scrub against maximum heating surface and give up more heat.

That's the secret of Smith-Mills efficiency. The result is more heat per fuel unit . . . less fuel used . . . lower fuel costs.

It pays to specify H. B. Smith boilers for industrial, commercial, institutional and residential jobs. If you want to know more important H. B. Smith advantages, send for your free catalog.





CAST-IRON BOILERS

THE H. B. SMITH CO., INC., 62 Main Street, Westfield, Mass. Offices and Representatives in Principal Cities

TECHNICAL NEWS AND RESEARCH

JULY 19'47

ARCHITECTURAL RECORD

THE DRAWING OF ACCURATE CURVES

(Continued from page 127)

one-half of wl. The ordinate ce is thus equal to wl^2 divided by 4, while the ordinate de is half of this or wl^2 divided by 8. With w and l given, it is necessary only to plot, at some convenient scale, the two tangents ac and bc and the ordinate de locating the control point d, after which additional points on the curve are determined, as before. This method will, in a great number of cases, be found considerably simpler than the usual method of determining points by figuring moments at various points along the span.

Always bearing in mind that the two tangents and a control point fix definitely the shape of the curve, the principle outlined can be put to use in solving problems such as the intersection of surfaces of all types, vaulting and vault ribs, graphs and diagrams, or in fact any problem involving curves or curved surfaces. The examples just given have all fallen under the previously cited Case I, involving two tangents and a control point. It will be found in practice that these conditions are usually present or can be established. Where this is not possible it will only then be necessary to fall back upon one of the other applications, Cases II and III as illustrated in Figs. 4 and 5 respectively.

BASIC THEORY

It will possibly be of interest to some readers to follow the development of the relationship upon which the foregoing is based. This relationship, known as the "Pascal Theorem," is diagrammed in Fig. 13, and may be stated as follows: "If the extremities of any hexagram inscribed in a conic are numbered in consecutive order 1 to 6 as shown in the sketch, the intersection of the opposite pairs of sides 1-3 and 2-4, 4-6 and 1-5, and intersection of the diagonals 2-5 and 3-6 will always lie in a straight line, known as a 'Pascal line'." Thus the intersections o, p and q lie on a "Pascal line" ab.

A "hexagram" may be briefly described as a six-pointed star, and in Fig. 13 is clearly visible as such when the sides 3–5 and 2–6 (dotted) are drawn. The term "hexagram" is, however, possible of much broader application: the figure need not be regular in shape, nor is the curve in which the hexagram is inscribed limited, except in one respect — it must be a conic.


In Fig. 14, the same relationship is again indicated, the nomenclature of Fig. 13 being retained; the hexagram in this case being irregular in form and inscribed in an ellipse. In both Figs. 13 and 14, lines l-3 and 2-4 intersect at q, lines l-5 and d-6 intersect at q and lines d-6 intersect at d and lines d-6 intersect at d and d intersect at d in


Earlier in this article we stated as Case III the condition that five points on a conic curve were sufficient to determine the curve, or stated otherwise: five points on a conic are sufficient to establish a sixth point, also on the conic. A comparison of Fig. 14 with Fig. 5 will show that the procedure outlined in Fig. 5 is derived directly from the relationship shown in Fig. 14, the only difference being that in Fig. 5, with five points given, the Pascal line passed through the point o at random determines the two other intersection points p and q, which immediately determine the location of the sixth point as shown.


It will be observed that as the position of the fifth point varies the sixth will also vary, but the ensuing curve will be the same. Referring again to Fig. 5 it will be noticed that if point 3 is moved, but always remains between points 2 and 4, the intersection o will lie on the inside of the curve. If point 3 is moved, however, until it lies between points 1 and 2 the intersection of lines 2-4 and 1-3 will lie outside the curve. If now we assume that point 2 is rotated clockwise until it coincides with point 4, and point 3 is rotated counterclockwise until it coincides with point 1, indicating the combined points 2-4 and 1-3, as in Fig. 15, it will be seen that the lines joining points 1 and 3 and points 2 and 4 must be tangents to the curve at the combined points 1-3 and 2-4 respectively. As before, the intersection of these two lines will be indicated as point o.

It was previously indicated that the fifth point was not restricted as to position as long as it remained on the conic. Assume point 5, in Fig. 15, to be intermediate between the combined points 1-3 and 2-4. With this arrangement we would now have established the first set of conditions mentioned earlier: "One point and two point-slopes."

Proceeding as in Fig. 5, we draw







lines CD through points 2 and 5 and EF through points 1 and 5. If we then pass a Pascal line AB at random through point A and call the intersection of this line with line CD (or 2-5) the point p as before, and also the intersection with line EF (or 1-5) the point q, we will then have retained the same relationship of lines and points in both cases. Continuing as in Fig. 5, we will draw lines through points 3 and p and through 4 and q intersecting at point 6, which is the point sought. If we now compare Fig. 15 with Fig. 2, it will be seen that the procedure is the same as previously outlined.

Also, since the procedure followed in Figs. 5 and 15 was identical it is apparent that the method is general as to Cases I and III. A study of Fig. 4 will show that the procedure in Case II is likewise similar.

ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

MANUFACTURERS' LITERATURE

ELEVATORS

(1) Elevator Door Details; (2) Montgomery Hydraulic Elevators. Diagrams, dimensions and features of single swing, single sliding, two-speed sliding, center opening, freight elevator and dumbwaiter doors, and counterbalance hatchway safety grates for freight elevators (1). Specifications, engineering features, typical installations (2). 6 and 4 pp., illus. Montgomery Elevator Co., Moline, Ill.

FANS

(1) American Blower Axial Fans; (2) Ventura Attic Fan, Model C; (3) Type "V" Fans with Cast Iron Housings; (4) Corrosion Resisting Fans; (5) Heavy Duty Fan; (6) Hay Curing Fans. Series of catalogs giving full specifications, installation information, capacity tables, typical installations, etc. 32, 4, 40, 16, 70, and 28 pp., all illus. American Blower Corp., 811 Tireman Ave., Detroit, Mich.*

Emerson-Electric Fans for 1947. Catalog of a complete line of fans, with design and construction specifications, performance data, dimensional information. Included are various types of desk fans, air circulators, ceiling fans, kitchen ventilators, exhaust and cooler fans. 28 pp., illus. The Emerson Electric Mfg. Co., St. Louis 21, Mo.*

FLOORS

Norton Floors: Non-Slip, Wet or Dry. Folder describing alundum terrazzo aggregate floors, stairs and ramps. How made, where used, colors and sizes, specifications. Alundum cement floor aggregate, ceramic mosaic tile, stair and floor tile also included. 14 pp., illus. Norton Co., Worcester 6, Mass.*

GLASS BLOCK

PC Glass Blocks: A Modular Product. Typical applications of glass blocks in industry, hospitals, schools, etc.; technical and performance data; catalog of sizes and patterns available; layout tables; installation details; accessories; specifications; curved panel installation requirements with table of radii limits. 20 pp., illus. Pittsburgh Corning Corp., 632 Duquesne Way, Pittsburgh 22, Penn.*

GYM SEATING

(1) Modern Gymnasium Seating;
(2) Modern Gymnasium Seating
Capacity. Prepared for the Gymnasium

* Other product information in Sweet's File, 1947.

Seating Council by Harold R. Sleeper, A.I.A. Two bulletins giving detailed description of various gymnasium plan types and seating plans. Tables of dimensions and space requirements, advantages of folding seats, photos of typical installations (1); analysis of the need for gymnasium seating in various sections of the country and in schools of different sizes (2). 12 and 4 pp., illus. The Producers' Council, Inc., 815 15th St., N.W., Washington 5, D. C.

HEATING, VENTILATING

The American System of June-Aire, Winter Air Conditioning for Schools, Churches, Public Buildings. Description and diagrams of a heating and ventilating system featuring continuous ventilation of every room, controlled humidification, clean filtered air, automatic firing, thermostatic temperature control. 4 pp., illus. American Foundry and Furnace Co., Bloomington, Ill.*

Products for Heating, Ventilating, Air Conditioning. Catalog of a line of products used in a variety of installations from department stores and office buildings to aviation wind tunnel testing. Equipment includes Texrope V-belt drives, centrifugal pumps, a-c and d-c motors, a complete line of motor control, dry-type transformers and a-c and d-c welders. 12 pp., illus. Allis-Chalmers Mfg. Co., Milwaukee 1, Wis.

South Wind Sealed Heat. Brochure outlining the principles of a home heating unit, and describing the advantages claimed. Intended for consumers, it gives non-technical information about installation and operation. 6 pp., illus. South Wind Division, Stewart-Warner Corp., 1514 Drover St., Indianapolis 7.

KITCHENS

(1) America's Finest Gas Range; (2) A Brochure of Kitchen Planning Ideas; (3) A Guide for Buying Your Next Range; (4) Roper Gas Ranges Give a New Lift to Living. Four new booklets illustrating the current Roper line of gas ranges, describing in detail their various features, and giving general information. 64, 16, 16, and 32 pp., illus. Geo. D. Roper Corp., Rockford, Ill.

LATHING, PLASTERING

What You Should Know about Modern Lathing and Plastering. By Erwin M. Lurie. Basic facts and features assembled to show the advantages

of lathing and plastering. Includes modernization notes, painting suggestions, general information for lay consumption. 16 pp. Natl. Foundation for Lathing and Plastering, Inc., 173 W. Madison St., Chicago 2, Ill.

LIGHTING

Fluorescent and Incandescent Lighting Equipment (Catalog 47). Condensed catalog listing all current items in the Curtis line. Includes coefficient of utilization charts, specifications and full information on fluorescent and incandescent units, reflectors, fittings and accessories. Price list separate. 16 pp., illus. Curtis Lighting, Inc., 6135 W. 65th St., Chicago 38, Ill.*

G-E Lamp Bulletin: Incandescent, Mercury, Fluorescent. Comprehensive manual on the design and operation of incandescent, mercury and fluorescent light sources. Technical information, tables, charts, discussions, color temperature scale, characteristics, etc. 76 pp., illus. General Electric Co., Lamp Dept., 570 Lexington Ave., New York 22, N. Y.* 40 cents.

A Miracle of Light. Bulletin describing four classes of Lustra fluorescent tubes. Points out the features of the line, highlights construction details, and specifies recommended uses of each class. Also includes description of two types of Lustra fluorescent starters. 4 pp., illus. Lustra Corp. of America, 40 W. 25th St., New York 10, N. Y.

Rambusch "Aura." Folder describing a new lighting unit available in three standard lengths, convertible to give downlighting as well as indirect. Diagrams, specifications, features. 4 pp., illus. Rambusch, 2 W. 45th St., New York 19, N. Y.

PIPE UNITS

Specification Data for Engineers and Architects: Ric-wil Prefabricated Insulated Pipe Units. Specifications for underground pipe distribution systems employing prefabricated insulated pipe conduit. Data arranged in tabular form with supplementary diagrams and charts. Construction details of Ric-wil insulated pipe units and available accessories. 16 pp., illus. The Ric-wil Co., Cleveland, Ohio.*

PLUMBING

Toilet Compartments and Toilet Room Environments (Catalog 85). Catalog containing the latest structural and design improvements in five types of toilet compartments, shower stalls and shower cabinets. Complete specifications, construction details, available finishes. Color chart shows 15 standard (Continued on page 156)

Engineered for songer sife

... <u>new Richmond</u>
Winter Air Conditioner

NEW CAST-IRON-CHROME ALLOY

heat exchanger lasts longer under
higher temperatures.

MORE EVEN PERFORMANCE
... limit control prevents unit from overheating.

IT'S QUIETER . . . blower fan floats on rubber.

SPUN GLASS FILTER easily renewed.

You can specify the new Richmond Winter Air Conditioner with confidence. Its heart—the heat exchanger—gives greater protection against overheating . . . assures longer service life.

A single unit in a smart Dulux white enamel finish, completely packaged, it fits in home, office or store. Heats, humidifies, circulates, filters . . . comes in four sizes . . . occupies only about 4 to 6 sq. ft. Covered by both AGA approval and a one-year replacement guarantee. Write Richmond Radiator Company, 19 E. 47th St., New York 17, N. Y.



FACTORIES AT METUCHEN, N. J., MONACA, PA., NEW CASTLE, DEL., UNIONTOWN, PA. (2)



RICHMOND RADIATOR COMPANY

Affiliate Reynolds Metals Co.

Enameled Cast Iron Ware . Vitreous China . Perma-Gloss . Gas Boilers . Gas Winter Air Conditioners . Gas Gravity Furnaces . Radiators



FUNCTIONAL

THE BURT MONOVENT TRANSFORMS ROOF RIDGES INTO GIANT AIR VALVES

On plants equipped with Burt Monovent Continuous Ridge Ventilators, the roof ridge performs a new function. Installed along the entire length of the building, the Monovent transforms the ridge into a gigantic valve that exhausts heat, smoke, and fumes quickly and economically. Installation may also be made on flat roofs, on saw tooth construction and on roof slopes.

Special Burt designed brace frames and carefully engineered sheet metal construction assure strength and long life. Center hinge butterfly-type dampers combine with the Monovent's fixed top to form the cone-shaped airflow section that has been thoroughly proven in Burt's Free-Flow round ventilator.

Write for catalog and data sheets on the Burt Monovent. It is one of Burt's complete line of ventilators, which includes a size and type for every need.

WRITE FOR CATALOGS AND DATA SHEETS

The BURT MFG. Co.

48 E. South Street

Akron 11, Ohio, U. S. A.

VENTILATORS, LOUVERS, OIL FILTERS AND SHEET METAL SPECIALTIES

THE RECORD REPORTS

(Continued from page 16)

MATERIALS ROUNDUP

The continued high rate of building material production indicates an increasing flow of most materials, the Construction Division, Department of Commerce, states in its May Construction and Construction Materials Report.

March production of lumber, says CD, was estimated at 2,831 million board feet, 9 per cent over February. Total production during the first three months of this year was 7,967 million feet, nearly 20 per cent above the corresponding period in 1946. Stocks of lumber in the hands of wholesalers and retailers at the end of March totaled 3.6 billion board feet, a gain of about a billion feet over stocks on Dec. 31, 1946.

Also showing increases in March over February production according to CD were fabricated structural steel, common and face brick, clay sewer pipe, gypsum board and lath, portland cement, asphalt roofing materials, cast iron pressure pipe, concrete building block, wire nails and staples, cast iron radiation.

CD warns, however, that current reports indicate that the hardware trade will not be able to fill consumer needs before 1948. March output was about the same as in the previous two months, and distributors inventories are almost non-existent. Shortages throughout 1947 are to be expected also in insect screen cloth because of the limited supply of rods and wire for fabrication of mesh.

WHAT THEY SAY . . . About Rental Housing

Cooperative housing projects, even though financed under the GI Bill of Rights, are unlikely to prove an adequate substitute for the rental housing which so many veterans need. There are several apparent disadvantages implicit in most cooperative ventures. "One is the prospect of having to meet competition from lower priced rental quarters in the future. Another is the possibility of a general foreclosure because one or two of the cooperating parties may be unable to carry their part of the common burden." — National Committee on Housing, Inc., in Tomorrow's Town.

"Although the volume of rental housing under construction has increased somewhat as compared with last year, there still are far too few rental units being built to meet the veteran demand. It has been adequately demonstrated that the continuation of rent ceilings is the greatest obstacle in the way of this essential type of residential building. There still is time to start and complete

(Continued on page 134)



All over America architects, engineers, contractors and builders are planning ahead today for the homes and apartments of tomorrow. In each living unit they know there must be new features to increase beauty and utility. One feature every home and apartment should have is steel windows—because steel windows not only offer greater utility but add to the beauty and lasting good appearance of any type of architecture. So consider these eight advantages Ceco metal windows offer:

- Tighter weatherseal—precision engineering keeps out cold, dust, rain; keeps heat in.
- 2 Give more light—afford from 20% to 60% greater light area. Also increase wall space.
- 3 Lowest initial cost installed—with metal windows maintenance cost is cut to the minimum.
- 4 Easy to install—no weatherstripping. Less labor in installing hardware. No planing.
- 5 Controlled ventilation—up to 100%... catches stray breezes ... controls drafts.
- 6 Easier operation—always fit . . . no sticking, warping or swelling to worry about.
- 7 Fire safety—Ceco metal windows are fire resistive, reduce fire hazards.
- 8 Easily washed from inside—both sides of the windows can be washed from within.

CECO ALL-ALUMINUM STORM WINDOWS AND METAL FRAME SCREENS provide year 'round controlled ventilation in metal casements. New beauty and utility are combined with ease of installation . . . from the inside!

CECO STEEL PRODUCTS CORPORATION

GENERAL OFFICES: 5701 West 26th Street, Chicago 50, Illinois

STEEL


Offices, warehouses and fabricating plants in principal cities
Other Ceco products include—Meyer Steelforms, Reinforcing Steel, Steel Joists, Roof Deck, Metal Lath



133

In construction products CECO ENGINEERING makes the big difference

MICHAELS adjustable Astragals



Made of extruded bronze, aluminum or nickel, Michaels Adjustable Astragals compensate for the expansion or contraction of doors. By keeping doors closed as tightly as possible, you eliminate drafts, air currents, and help to keep out dirt and dust. These astragals are simple, practical, rugged...easily installed and adjusted, and are available in several styles for any type of door. Type "A" shown in the illustration at the top, may be applied to either wood or hollow metal bevel doors. Or as a stop bead, or at the bottom of doors. Type "E" shown in the second illustration may be applied to bull-nose hollow metal or wood double doors, or at the bottom of doors. Folder containing complete details and specifications will be sent on request. We shall also be glad to send you information on any or all of the other products manufactured by Michaels.

MICHAELS PRODUCTS

Fixtures for Banks and Offices Welded Bronze Doors Elevator Doors Elevator Enclosures Check Desks (standing and wall) Lamp Standards Marquise Tablets and Signs Name Plates Railings (cast and wrought) **Building Directories** Bulletin Boards Stamped and Cast Radiator Grilles Grilles and Wickets Kick and Push Plates Push Bars Wrought Iron and Bronze Lighting Fixtures Wire Work Cast Thresholds Extruded Thresholds Extruded Casements and Store Front Sash Bronze and Iron Store Fronts Bronze Double Hung Windows Bronze Casement Windows

THE MICHAELS ART BRONZE CO., Inc., 234 Scott St., Covington, Ky.

Member of the National Association of Ornamental Nonferrous Metals Manufacturers

THE RECORD REPORTS

(Continued from page 132)

thousands of additional rental units this year if ceilings are terminated now, whereas the number will be greatly reduced if no action is taken until Congress can fit this legislation into its crowded schedule." — DOUGLAS WHITLOCK, Chairman, Building Products Institute.

Architectural Design

"The war and the present housing shortage will have a tremendous influence upon architectural design. The necessity for the speediest possible construction has required most careful and efficient planning. Many standard materials were unobtainable so substitute materials had to be found and new, more scientific methods of construction adopted. The architect has been forced to experiment, to become more of an investigator. This is bound to have a tremendous influence upon the architecture of tomorrow. . . .

"New and better materials have been found and tested, such as glass brick, plastics and other synthetic products, old materials have been used in better ways, such as laminated wooden beams and trusses; improved methods of construction have been developed and the construction industry has become more mechanized and better organized."—
FREDERICK A. GODLEY, Professor of Architecture, Yale University.

NEW YORK BUILDS

Proposed construction expenditures in New York City amounted to \$68 million in March, almost twice as much as in February. The number of plans filed rose from 4752 in February to 4871 in March, according to a report submitted to Industrial Commissioner Edward Corsi by the Division of Placement & Unemployment Insurance.

The greatest expenditure planned in March was for the construction of residences: \$45,590,000 as compared with \$17,465,000 the previous month. The number of dwelling units provided in the 628 buildings for which plans were filed was 5549.

Estimated costs of plans filed for industrial and commercial building were more than three times greater than in February and the number of plans filed also increased. Nine public buildings were planned, five more than in February, but total dollar volume dropped more than a million dollars. More plans were filed for alterations and repairs, and estimated costs were higher.

MICHIGAN HOSPITALS

A report has just been published on a survey of Michigan's hospital needs, (Continued on page 136)



. . . Versatility of MAHON STEEL DECK Permits Myriad of Uses in Modern Construction

Mahon Steel Deck, rolled from high-tensile, low alloy Yoloy, was used for decks of the all-welded, all-steel constructed "Delaware Belle", of the Wilson Line, illustrated here . . . this is typical of numerous new applications by alert designers in which Steel Deck solved their problem of light weight construction with adequate strength and rigidity. You will find that Mahon Steel Deck, due to its basic design, with narrow, vertical-leg stiffening ribs, lends itself to a broader range of uses in modern construction. See Mahon's Insert in Sweet's File for complete information, specifications and latest construction details, or consult a Mahon representative.

THE R. C. MAHON COMPANY


Home Office and Plant, Detroit 11, Michigan Representatives in all Principal Cities

Manufacturers of Steel Deck for Roofs, Sidewalls, Ceilings, Floors, Partitions and Doors. Also Roof Sumps and Recesses, Rolling Steel Doors, Grilles, and Underwriters' Labeled Rolling Steel Doors and Fire Shutters.

The all-welded, all-steel constructed "Delaware Belle". All three of the upper decks are Mahon Steel Deck rolled from high tensile, low-alloy Yoloy.

MAHON

HOTELS



The voice that says it's modern!

The kind of modern planning hotel men expect from architects today! Every convenience, every safety precaution must be included in your designs. Of these, a natural-voice Stromberg-Carlson Sound System is a basic requirement. It makes profits, too! Invites customers into restaurant and cocktail lounge. It protects while it entertains, clearing any section of the hotel in case of emergency.

What's more, it fits into your architectural plan unobtrusively, efficiently. Speakers may be supplied with a coin-operated device to provide additional


revenue for the hotel.

Consult your local Stromberg-Carlson Sound Equipment distributor.

He is listed in your phone book. Or write for free booklets describing Stromberg-Carlson Sound Equipment for hotels \square schools \square churches \square offices \square industrial buildings \square . (Check information desired). Address: Stromberg-Carlson Co., Sound Equipment Division, Dept. A-7, 100 Carlson Road, Rochester 3, New York.

The heart of any modern hotel sound system. Stromberg-Carlson Standard Sound System Model 750. Compact glacier gray cabinet contains AM-FM radio receiver, record player, all controls and amplifiers. Allows central control of maximum volume.













STROMBERG-CARLSON

NATURAL-VOICE



SOUND SYSTEMS



THE RECORD REPORTS

(Continued from page 134)

made by the Commission on Hospital Care to establish a pattern for other states to follow in meeting the requirements of the Hospital Survey and Construction Act. Findings of the Commission include:

- 1. Michigan has 71 natural hospital areas, which subdivide into 20 regional and 51 community hospital centers, the latter grouped around the regional centers to form an integrated hospital system. Local health centers would be provided for the still smaller rural communities.
- 2. Michigan now has 292 general and "allied special" hospitals, providing care and treatment for the acutely ill and injured. These 292 institutions have 19,361 beds, of which 14,567 are in permanent structures suitable for continued used in the communities they serve. About 11,000 beds should be provided as replacements or additions in this type of institution.
- 3. The state should have 181 local health centers, with diagnostic facilities and facilities for emergency treatment.
- 4. No general hospital exists now in three rural hospital areas. In 14 other rural areas the existing hospitals should be abandoned and replaced. In still others the existent institutions require modernization and enlargement.

CONFERENCE PLANNED

The Massachusetts Institute of Technology has announced that its 10th annual Conference on City and Regional Planning will be held from Sept. 15–27, 1947. Sponsored jointly by the Institute and the American Society of Planning Officials, it will be open to men and women who have had practical experience in planning or in a related professional field, including planning technicians, members of state or municipal planning commissions and housing authorities, and staff members of engineering or public works departments.

Seminars will be held each morning and afternoon, and will cover principles and techniques of planning and planning legislation and administration. Emphasis will be placed on technical and administrative procedures and the application of approved planning standards rather than on a generalized discussion of the various planning problems for which solutions are needed.

The staff for the Conference will again consist of Prof. Frederick J. Adams, head of the Department of City and Regional Planning, and Mr. Flavel Shurtleff, lecturer on Planning Legislation and Administration at M.I.T. and counsel to the American Planning and Civic Associations. Visiting lecturers on special

(Continued on page 138)



HOTEL ROWE, GRAND RAPIDS, MICH. B. K. Gibson, Architect

Decoration

OFFERS WHAT YOU WANT MOST IN A WALL FINISH

Color and design are generally considered primary factors in the selection of materials for finishing interior walls.

While attractive appearance is important, it is of equal importance that the decorative treatment be practical, economical and as permanent as possible to serve adequately through the many years the building is in operation. FABRON—the fabric-plastic-lacquer wall covering, engineered to meet the architects' standards—performs the dual function of a decorative finish and a structural agent. It not only conforms to your every requirement as an architect, but also, due to its durability, its easy maintenance and its economy, meets the subsequent needs of those for whom the building is planned - your clients.

CONTRAST THESE FABRON FEATURES AGAINST OTHER WALL FINISHES

- It offers a wide range of colors and designs to answer every decorative need.
- It reinforces plaster, conceals imperfections and prevents cracks.
- It is non-porous, waterproof, thoroughly and easily washable requires a minimum of maintenance.
- It is sunfast and sanitary.

Name

- It resists scuffing does not scale.
- It withstands hard wear and can be invisibly patched.
- It is permanent eliminates periodic redecorations. After many years of service, when it has outlived its original decorative function, it offers an ideal base for paint or any subsequent wall finish.
- FABRON prevents fire spread listed and approved by the Underwriters' Laboratories, Inc.

All these features combined make FABRON the most economical and desirable wall and ceiling finish for hotels, institutions, etc., from the angle of both the architect and his client.

230 PARK AVENUE, NEW YORK 17, N.Y. FREDERIC BLANK & CO., INC. Established 1913



		FREDE	
Hospitals		230	P
**		In	re
Hotels	1 1	: f	

Schools |

Theatres

FREDERIC BLANK & Co., Inc.
230 Park Ave., New York 17, N. Y.
In reference to type of building checked please send further information about Fabron.

Address _____ Zone____ State ___

□ Offices

☐ Apartments

☐ Residences







HEALTHFUL WARMTH from wall to wall—from floor to ceiling

Designed and engineered to meet modern construction requirements. Easily installed—piping is run around the inside of the exterior wall of the house or building and is concealed behind attractive baseboard.

Heating sections (fin radiation), replacing parts of the piping in the attractive baseboard, with concealed louvres, provide clean, comfortable warmth to the room.

DUNHAM HEAT	TING MEANS BETTER	HEATING!	
C. A. DUNHAM COMPANY 450 E. Ohio St., Chicago 11, Illinois	GENTLEMEN: Send me Bulletin A. R. so that I may have complete details about the new Dunham Baseboard Heating System. B-7472/E		
Name		2 3 . 2	
Title			
Company		* 1	
Address			
City	ZoneState		

THE RECORD REPORTS

(Continued from page 136)

topics will assist in the conduct of the seminars.

Applications should be sent to Prof. F. J. Adams, Massachusetts Institute of Technology, Cambridge 39, Mass., not later than Sept. 2nd.

NEW YORK CHAPTER,

A.I.A. ELECTS

Harold Reeve Sleeper was elected president of the New York Chapter of the A.I.A. at its annual meeting last month. For the past two years Mr. Sleeper has served as chairman of the technical committee of the Chapter.

Elected to serve with him are Daniel Schwartzman, vice president; Francis W. Roudebush, secretary; and William Potter, treasurer.

U. N. COMPETITION URGED

The A.I.A. has formally proposed to the United Nations that an architectural competition be held in the designing of one or more of the major buildings which will make up the U.N. Center in New York City, according to Douglas W. Orr, Institute president.

"It is our recommendation," Mr. Orr said, "that the competition be open to architects from all nations participating in the U.N. A committee of the Institute is being appointed to confer with U.N. officials regarding the possibility of such a competition.

"It is our understanding that it will not be possible to conduct competitions for the design of all U.N. buildings, because competitions necessarily require somewhat more time than the usual methods of design and because the first buildings must be completed at the earliest possible date in order to provide suitable permanent administrative quarters for the staff.

"Nevertheless, it is entirely feasible to select one or more of the central buildings as subjects for an international competition, which should be open to all architects everywhere."

AT THE COLLEGES

Industrial Design Course

The California Institute of Technology, Pasadena, has added to its curriculum a professional course in industrial design on the graduate level. Instruction will be by Harry R. Greene and Salvatore Merendino, both members of the Pasadena firm of Industrial Design Associates.

New Head for R. I. School

Max W. Sullivan, dean of the Rhode Island School of Design for the past year, has been named president of the (Continued on page 140)



Koppers coal tar pitch roofs give similar protection to buildings. Water may stand for long periods on roofs . . . and if those roofs are constructed of Koppers Old Style Pitch and Tar-saturated Felt, the water has practically no damaging effect.

That's why Koppers roofs are good for flat roofed homes, and for commercial buildings, many of which utilize the roof for cooling purposes in summer. And that's why, also, that Koppers roofs withstand the severity of rains and snows throughout the years.

Sun's rays, too, are less damaging to a Koppers coal tar pitch roof, because of its property of "cold-flow" by which cuts and cracks heal themselves.

When you specify roofing, consider these advantages of Koppers Old Style Pitch and Tar-saturated Felt.

KOPPERS COMPANY, INC. PITTSBURGH 19, PA.

Naturally, a Koppers roof for long life



ROOFING & WATERPROOFING

Refer to your Sweet's Catalog or write us for complete specifications

School to succeed Mrs. Murray S. Danforth, who resigned early in May.

Mr. Sullivan, a graduate of Western State Teachers' College at Kalamazoo, Mich., holds a Master of Arts in the teaching of Fine Arts from Harvard University. He was formerly instructor in arts and crafts at the Cranbrook School at Bloomfield Hills and at the Middlesex School, Concord, Mass. He will be succeeded in the post of dean at Rhode Island by Albert E. Simonson,

architect and former instructor in architectural design and history at the Cambridge School of Architecture, Smith College, and the Harvard Architectural Summer School.

Farmhouse Planning

Basic farmhouse plans will be developed at the University of Illinois under a new project to be carried on by the College of Agriculture in cooperation with the Small Homes Council.



Robert Benninghof (center) shows his prize-winning model home in University of Minnesota competition to fellow architectural students James Hirsch (left) and Ted Sugano (right). The three shared a \$100 award by the Home Institute, Northwestern National Bank, Minneapolis

The project is to be carried out and reported by late summer. Among those directing it will be Professors Deane G. Carter and Keith Hinchcliff, agricultural engineers; Prof. Henry W. Gilbert, landscape gardening expert; Miss Margaret Goodyear, home economist; Prof. William H. Scheick, coordinator of the Small Homes Council; and Robert P. Simon, architectural designer of the Small Homes Council staff.

Department Reorganized

Changing emphasis in the field of landscape architecture and the need for trained men in the closely allied field of urban planning has been recognized at Michigan State College by reorientation of the former Department of Landscape Architecture.

A major curriculum has been added for the study of urban planning, and the name of the department has been changed to the Department of Landscape Architecture and Urban Planning.

Students working in the field of city planning will study methods of collecting and using basic data, appropriately arranging the different kinds of land uses, devising and applying protective regulations, traffic control and arranging systems of major thoroughfares, and planning law pertaining to zoning, platting and housing.

The landscape architecture curriculum has been changed to broaden the training and afford greater professional opportunities to graduates. This is in line with the modern conception of landscape architecture as the art of arranging land uses, requiring a thorough knowledge of engineering and architecture. Professor Harold Lautner is head of the reorganized department.

ized department.

EXHIBITIONS Architectural League

An exhibition preview of 25 projects in the process of planning or construc-(Continued on page 142)





HERE'S A REAL improvement in the single main method of forced circulating hot water heat. The Thrush Adjustable Tee greatly increases heating efficiency by diverting just the right amount of water to each radiator and simplifies the balancing of the system after installation. The curved diverter in this Tee may be moved to accurately adjust the amount of hot water passing from the main through the radiator, giving control of radiator temperature and making it possible to obtain uniform heat in every room. Flow of water through the main is increased . . . not throttled . . . when branch flow is cut down by this method. For more information, write Department J-7 or see your wholesaler.

H. A. THRUSH & COMPANY · PERU, INDIANA

tion — "Tomorrow's Buildings" — is on view at the Architectural League of New York, 115 E. 40th St., through September 15.

Described as a "flexible review of architectural progress in 1947," the exhibit is confined to projects in the planning or construction stage; at three-week intervals throughout the summer the projects shown will be replaced or added to, so that the exhibit will reflect progress during the summer months.

Featured in the opening group of projects last month were 11 original perspective drawings showing various preliminary schemes studied by the Board of Design Consultants responsible for the planning of U.N. headquarters.

Museum of Modern Art

The summer season at the Museum of Modern Art, New York City, opened on June 11th with a large double exhibition filling two floors, "The Alfred Stieglitz Exhibition: His Photographs and Collection." One section is devoted to the modern paintings, sculpture, drawings and prints assembled by Stieglitz, and the other to a retrospective showing of Stieglitz' own photography. The former will be on view until August 31st, the latter through September 21st.

On June 25th the Museum opened three smaller exhibitions, all of which will remain on view through the summer months. "Two Cities: Planning in North and South America" shows the Michael Reese redevelopment scheme for seven square miles of Chicago's South Side slums and the building of an entirely new city in Brazil 25 miles from Rio de Janeiro. "Robert Maillart: Engineer" is the first presentation in New York of the bridges and buildings designed by Robert Maillart, Swiss engineer (see ARCHITECTURAL RECORD, June, 1947, pp. 84-87). "Boris Aronson: Stage Designs and Models" presents the results of years of experimentation with techniques on stage lighting developed by Boris Aronson.

PHILADELPHIA PLANNING

An elaborate and unusual city planning display, the "Better-Philadelphia Exhibition," will be on view at Gimbel Bros., Philadelphia, from September 8th through October 15th, and will later be moved to permanent quarters.

Under the official sponsorship of the city, the exhibition will present changes and improvements recommended by the City Planning Commission - projects scheduled for 1947 to 1952, at an estimated total cost of \$302,400,000. Features of the exhibit will be a 28 by 22-ft. diorama showing the city as it will look when all the proposed improvements have been accomplished; a circular theater 50 ft. in diameter with four stages showing how Philadelphia has grown from William Penn's "Greene Countrie Towne" to a metropolis, how neighborhoods decay, what will happen if decay is not checked, and how proper city planning can arrest decay and redevelop; and a three-dimensional model of the downtown area of the city, 440 sq. ft. in size, with rotating sections to transform it from its present-day to its future appearance.

OFFICE NOTES

Offices Opened, Reopened

Joseph Di Stefano, Jr., has opened an office for the practice of architecture at 230 Boylston St., Boston, Mass.

Evans & Davis (F. A. Evans, Jr., and John T. Davis), Architects-Engineers, have announced the opening of an office for the general practice of architecture and engineering at 403 Fulton St., Troy, N. Y.

(Continued on page 144)



Barcol OVERdoor

IS WEATHERTIGHT AND EASY-WORKING...



1

Test I. EASY-WORKING. The simplest and surest way to tell how well the Barcol OVERdoor works is...work it. Raise it... lower it. Note the "floating balance". Note the roller-bearing glide of the sections... upward and downward. No other overhead door works any easier!



2

Test 2. WEATHERTIGHT. To keep out weather, a door must close snugly . . . and a really snug door won't rattle. So . . . take hold of the handle on that same door that closed so easily . . . and try to rattle it. You can't . . . because the exclusive closing action of the Barcol OVERdoor insures all-around weathertightness . . . and easy operation!

See our Catalog
in SWEET'S

"Barber-Colman Company"

102 MILL STREET . ROCKFORD . ILLINOIS

ACTORY-TRAINED SALES AND SERVICE REPRESENTATIVES IN PRINCIPAL CITIES

Granite gives Character to a building_

CHARACTER THAT'S RETAINED THROUGHOUT ITS LIFE!

Eleven colors and textures are available in The Rainbow Line of Granites. Architects throughout the Nation are using these granites to establish individuality, dignity and character to their designs. Granite affords a permanency that is otherwise difficult to achieve. Engineering advancements and


quarrying and fabricating now bring installation costs within attractive range. Polished surfaces stay clean with simple washing; no other maintenance, for there is no moisture absorption; no expansion

or contraction to these hard, northern, non-porous granites.

Thin, polished granite (veneer) is popular for both new construction and for refacing of old buildings. Other thicknesses and dimensions to economically meet every speci-

fication. Inquire of a Cold Spring representative near you or write The Cold Spring Granite Company, Cold Spring, Minnesota.

The Rainbow Line















COLD SPRING GRANITE COMPANY

COLD SPRING · MINNESOTA

Sweet's file $\frac{4a}{4}$ shows color reproductions.



1. East Branch First National Bank, Portland. Barrett and Logan, Architects. 2. Federal Building, Los Angeles. Gilbert Stanley Underwood, U. S. Supervising Architect; W. E. Reynolds, U. S. Commissioner of Public Buildings. 3. State Bank of Welston, Mo. Bernard Bloom, Architect. 4. St. Louis Daily Record. Mauran, Russell and Crowell, Architects. 5. Southwest Life Building, Dallas. Lang and Witchell, Architects. 6. Boilermakers Union, Portland. Pietro Belluschi, Architect. 7. Carl Greve Jewelers, Portland. Pietro Belluschi, Architects. 8. Bankers Life, Des Moines. Tinsley, Higgins and Lighter, Architects.

Edward B. Kirk, Inc. has opened offices at 2 Park Ave., New York City, to resume practice as lighting consultants. Mr. Kirk has just returned from long military service.

Victor B. Spector, R.A., and H. Eugene Montgomery, Associate, announce the opening of new offices for the general practice of architecture at 1057 W. Broad St., Falls Church, Va.

Wayman and Stuermer (Leonard Wayman and Ray Stuermer), Architects and Engineers, have announced the opening of offices at 37 S. Wabash Ave., Chicago 3, Ill.

New Addresses

The following new addresses have been announced:

Andrews & Clark, Consulting Engineers, 305 East 63rd St., New York 21, N. Y.

Elm Contracting Corp., Mason and General Contractors, 64 Metropolitan Oval, Parkchester, Bronx 62, N. Y. Friedman, Alschuler & Sincere, Architects and Engineers, Brooks Bldg., 223 W. Jackson Blvd., Chicago 6, Ill.

Garfield, Harris, Robinson & Schafer, Architects, 1740 E. 12th St., Cleveland 14, Ohio.

Firm Changes

Victor A. Frid, A.I.A., of the firm of Ebbets and Frid, and Commander T. Merrill Prentice, U.S.N.R., A.I.A., formerly of the firm of Adams & Prentice, have announced the formation of a partnership for the practice of architecture under the firm name of Ebbets, Frid & Prentice, with offices at 862 Asylum Ave., Hartford, Conn.

John M. Morse and Fred Bassetti have announced the formation of a partnership under the firm name of Bassetti & Morse, Architects, with offices at 509 Fourth and Cherry Bldg., Seattle 4, Wash. Mary Bassetti is associated with the firm for the design of interiors.

Reinhard & Hofmeister, Architects (L. Andrew Reinhard, A.I.A., and Henry Hofmeister, A.I.A.), of 145 E. 32nd St., New York 16, N. Y., have taken into partnership John A. Walquist, R.A., an associate for 15 years, and have changed the name of their firm to Reinhard, Hofmeister & Walquist, Architects. Richard H. Granelli has been made an associate in the firm.

Edward K. Schade has become an associate member of the firm of Mitchell & Ritchey, Architects, 524 Fourth Ave., Pittsburgh, Penn.

Preston S. Stevens, James R. Wilkinson and Associates, formerly engaged with the late Flippen D. Burge in the practice of architecture and engineering as Burge and Stevens, have announced the change of the name of their firm to Stevens & Wilkinson, Inc., with offices in their new building at 157 Luckie St., N.W., Atlanta, Ga.


Peter J. Trolio, A.I.A., and Jay T. Liddle, Jr., A.I.A., have announced the formation of a partnership under the firm name of Trolio & Liddle, Architects, with offices at Jackson, Miss.

ELECTIONS

Adrian N. Langius, of Lansing, has been elected president of the Michigan Society of Architects. Elected to serve with him are: first vice president, Earl W. Pellerin, Detroit; second vice president, Julian R. Cowin, Detroit; third vice president, Robert B. Frantz, Saginaw; secretary, Arthur J. Zimmermann, Lansing; treasurer, Lyle S. Cole, Detroit; executive secretary, Talmage C. Hughes, Detroit.

Austin Drewry, of Gunnison Homes, Inc., has been elected president of Prefabricated Home Manufacturers' Institute.

IMPLEMENT OF ARCHITECTURE



Schlage locks offer security, privacy, utility and convenience. The standardized Schlage cylindrical chassis allows locks to be interchanged as door usage conditions change. The cylindrical design affords a variety of lock functions to provide the perfect operation for every door. For further information see your builders' hardware man, or write direct to Schlage Lock Company, P. O. Box 3324, San Francisco.



SL-12

ORIGINATORS OF THE CYLINDRICAL LOCK

"WE CUT STEAM COSTS 48%

—and paid for conversion in 10 months"*



YOU SAVE 3 WAYS WITH ENTERPRISE Oil Burners EFFICIENCY, CLEANLINESS AND ECONOMY

Cutting steam costs by almost half seems unbelievable. Yet this is but one of innumerable conversion jobs from oldfashioned, uneconomical combustion systems to Enterprise Oil Burners that proves the rule of exceptional savings in fuel costs, minimum upkeep, and continuous efficiency under the most exacting requirements.

A leader in the field, Enterprise manufactures rotary oil burners in a wide range of heavy-duty models - with a flexibility of application to meet the needs of modern building and industry in all its branches. Enterprise burners are furnished in Manual, Semi-Automatic and Fully-Automatic Models in combination with modulating fire control or any desired special combinations.

Whether you are considering combustion equipment for a new installation or as a replacement of obsolete units, plan to investigate Enterprise Burners. A call to your nearest Enterprise distributor, or a letter to the Combustion Equipment Division in San Francisco, will bring a prompt answer to questions regarding your particular problems.

* From a statement by the Director of THE DOCTORS HOSPITAL in Seattle.

Installed by Superior Engineering Co. of Seattle, two of these Model H2P Semi-Automatic Enterprise Oil Burners operate 24 hours a day producing 4,000 pounds of steam per hour for The Doctors Hospital heating, sterilizing and laundry needs.





ENTERPRISE Dil Burners distributors in principal cities

COMBUSTION EQUIPMENT DIVISION OF ENTERPRISE ENGINE & FOUNDRY CO. 18TH AND FLORIDA STREETS, SAN FRANCISCO 10, CALIFORNIA

DIESEL ENGINES . PROCESS MACHINERY . OIL BURNERS . HEAVY MACHINERY

ARCHITECTURAL ENGINEERING

(Continued from page 124)

FIRE ALARM SYSTEM

A quick means of detecting fires is offered by DetectoMaster, a thermostatic alarm system that sounds a klaxontype horn whenever extreme temperature fluctuations are encountered in a guarded zone. An indicator needle on the panel board points to the number representing the affected area. The standard DetectoMaster covers 15 areas, but as many as 300 thermostatic detectors may

be used in each area without overloading the capacity of the central control. In addition to detecting fires, this thermostatic alarm system may be used to give warning of low temperatures in areas where freezing is a hazard. Lord-Taber Co., Inc., Canandaigua, N. Y.

MORE STORAGE SPACE

Designed to provide about 30 per cent more storage space in the same size closet, Revolvo-Door turns on a central



Entire closet rotates for easy access

axis to expose a semicircular hanger rod and shelves for wearing apparel. The central core, located behind a mirrored door, has shelves for linen, or folded clothing and accessories. The closet requires a space 6 ft. wide, 6 ft. 8 in. high, and 3 ft. deep. Hardware is chrome throughout, including rods, pulls, and hinges. Coast Store Fixture Mfg. Co., Dept. AR, 142 N. LaBrea Ave., Los Angeles, Calif.

AUTOMATIC COAL BURNER

The Unifeed coal burner unit for stoker-fed furnaces is confined for the most part within the heating plant in order to save furnace room space. Fan, transmission, and motor are mounted together on a steel plate so that the mechanism becomes a "drawer" that slides into a steel compartment under the furnace. Coal is fed automatically from bin to fire, with a capacity of 15 lb. of bituminous coal per hour. Direct drive eliminates sheaves and belts. An automatic air-measuring device is provided. Stoker Div., Link-Belt Co., 307 N. Michigan Ave., Chicago 1, Ill.

UNIT HEATER

The Shafco Suspended Unit Heater is oil-fired and installed in single or multiple units on steel channel supports from building wall or roof trusses. The units are completely self-contained horizontal forced warm air furnaces, and require no separate furnace room, boiler house, or basement. The manufacturer suggests their use wherever floor space is at a premium; particularly in garages, stores, shops, factories, warehouses, salesrooms, and public buildings. Shafeo Distributing Corp., 1354 Book Building, Detroit 26, Mich.

DDT WALLPAPER

DDT-treated wallpaper has been announced for children's rooms, designed to provide protection against disease-(Continued on page 148)



Our April advertisement in these pages featured the Fiberglas* fabrics in the public rooms of the famous BELLEVUE-STRATFORD Hotel in Philadelphia. This installation—which includes dramatic wall coverings, window curtains and draperies to assure maximum fire-safety to patrons-was designed by Geisert, Henon & Winge and made by R. F. Mooney & Co. for Lit Brothers. We humbly apologize for the wrong credit line in that advertisement.

Fiberglas fabrics are woven entirely of finely-spun inorganic glass filaments; will not emit asphyxiating smoke or fumes if exposed to flame. Endorsed by all public safety officials.

WRITE FOR SAMPLES AND INFORMATION

FIBERGLAS* Listed by Underwriters' Laboratories, Inc., as "Non-Combustible Fabrie"; approved by the Bureau of Standards and Appeals, City of New York.

ARCHITECTS BUILDING, 101 PARK AVENUE, NEW YORK 17, N. Y. LEXINGTON 2-0711 Sales representatives or recommended workrooms in: BOSTON, BUFFALO, CHICAGO, CINCINNATI, CLEVELAND, DENVER, DETROIT, LOS ANGELES, NEW ORLEANS, OAKLAND, PHILADELPHIA, PITTSBURGH, RICHMOND, SAN FRANCISCO, ST. LOUIS, TOLEDO, WASHINGTON

*T. M. Reg. U. S. Pat. Off. Owens-Corning Fibergias Corp.



"Controlled Working Conditions covering light, air, temperature, dust and noise plagues," a leading industrial management editor states, "came into their own during the war... cutting labor turnover, increasing labor output, and achieving closer control over work standards."

Highest on List is Better Lighting...lighting which conforms to the latest and highest standards ①... is one of the most important of the tools to control working conditions to the benefit of the employee while at the same time more than paying its way in increased production profits. ②

Small wonder, then, that today industrial management is placing lighting highest ③ on the list of things-to-be-done to achieve the happier working conditions which contribute so importantly to Better Employee Relations.

4 Free Reports to Aid Your Planning. To aid management in its consideration of all the phases of Lighting as a tool to control working conditions to the benefit of the employee . . . to the end that fatigue may be reduced . . . accidents minimized . . . happiness on the job increased . . . Benjamin Electric has just issued a series of four Reports:

Report 1. Profiting from War Production Experience with Lighting—How light solves problems of increased production, fatigue, over-age, deficient vision, safety, etc.

Report 2. How to Use Light and Color to Im-

prove Plant Lighting—An appraisal of the use of Color to improve lighting, seeing and safety conditions.

Report 3. Lighting...the No. 1 Tool in Controlled Lighting Conditions—A check-list of Things-to-be-done in a plant improvement program. **Report 4.** Procedures for the Correction of Plant Seeing Conditions—Contains a plant lighting score card for rating your lighting; uncovering needed lighting improvement; correction of improper lighting and maintenance methods.

- (1) American Recommended Practice of Industrial Lighting, American Standards Association.
- ing, American Standarus Association.

 (2) Case Reports by Illuminating Engineering Society, "Value of Good Lighting in War Production".
- According to a recent poll by two leading industrial management magazines.
- National Safety Council estimates 15% to 25% of all accidents are due to insufficient or improper lighting.

BENJAMIN Lighting Equipment

Distributed Exclusively Through Electrical Wholesalers

Benjamin Electric Please send ARCHITECTURAL	Mfg. Co., Dept. Q-1, Des Plaines, III. the four bulletins on Lighting as announced in RECORD.
NAME	
COMPANY	
ADDRESS	
CITY	STATE24125

ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

(Continued from page 146)

carrying insects. The insecticide is said to be harmless to humans and pets, will not rub off or wash off, and is guaranteed effective for one year. Designs are by the Walt Disney Studios. Trimz Co., 610 Merchandise Mart, Chicago 54, Ill.

FLOOR SEALER

A new varnish-type floor sealer, Tuf-Seal, has been developed for dance floors, gymnasium floors, and any wood flooring that receives abnormal traffic wear. This finish reportedly preserves the wood by sinking into its surface and preventing drying out and splintering. Gillespie Varnish Co., Dey St., Jersey City 6,

ALUMINUM WINDOWS

A new line of aluminum windows, called Stormtite, features tubular construction and welded corners. This construction is said to give increased strength, as evidenced by the windows



Aluminum window for glass-block walls

designed for glass block walls which will carry the weight of glass blocks without lintels. Regular casement-projected windows are designed with elements that interlock during assembly. Also marketed are aluminum screens and storm windows. Albert Storms & Co., 101 Park Ave., New York, N. Y.


HOME LAUNDRY

The All-Automatic Washer is announced as the first washing machine with completely automatic operation from the time it is started until it has completed its 45-minute soak-washrinse-flush-dry cycle. Washing is done by an activator which soaks, flexes, and rubs the clothes 3 to 20 min., depending upon time selected. In the 8-min. drying cycle, clothes are spun at high speed. If desired, the machine can be controlled manually, in order to skip or repeat any operation in the cycle. It is a rectangular top-opening machine, 36 in. high, without exposed moving parts, and controlled by an automatic water shut-off in the event of power failure. Home Laundry Equipment Div., General Electric Co., 1285 Boston Ave., Bridgeport 2, Conn.

SOUND SYSTEM

Especially designed to provide factories, plants, and large offices with an address system as well as recorded "music at work," the Model P-20 Console combines in a single cabinet all central control elements needed for a system of up to 50 watts. "One-button" control permits the announcer to speak from any microphone location without going to the central control. The record changer handles either 10- or 12-in, recordings, and turns off automatically at the end of a series. Dimensions of the console are $26\frac{1}{4}$ in. long, 171/8 in. wide, and 40 1/8 in. high. Executone, Inc., 415 Lexington Ave., New York 17, N. Y.

(Continued on page 150)



Blowers...built to serve and serve!

Heavy gauge steel, hydraulic riveting, and feather-sensitive balance all help to make good, long-lasting blowers. But the factor that makes usAIRco blowers exceptionally long-lived and trouble-free cannot be seen in the frame, the cone, the blades, the backplate, or the bearings. That factor is engineering follow-through.

In specifying usAIRco blowers, you buy much, much more than merely fine machinery. You get shrewd, expert knowledge of air-movement. You have as working partners men who know the job and will help you see it through. Call us in on your next blower installation, and see what this means!

UNITED STATES AIR CONDITIONING CORP. Minneapolis 14, Minnesota

Factory Representatives in Principal Cities



TESTED AND PROVED

Before any usAIRco blower goes to the shipping dock it must pass every test established by usAIRco design engineers. You can depend on usAIR co blowers to meet your needs with extra margins of performance.




Plus

Cooperative Engineering Counsel

Available to your air conditioning, heating or ventilating problems is the advice and counsel of the engineering staff of usAIRco. With a back-ground of nearly twentyfive years, it is one of the most experienced in the industry. We invite you to use it freely and fully.

GOOD-LOOKING · LESS MAINTENANCE · QUICK INSTALLATION



Speed construction, reduce costs by including windows of Alcoa Aluminum in your specifications. Attractive, rustproof, they require no painting. Light in weight, delivered complete, they are easily handled with a minimum of labor.

Corrosion-resistant, they withstand industrial

atmospheres; will give years of economical, trouble-free service.

For detailed information on windows of Alcoa Aluminum for every type of installation, write to Aluminum Company of America, 1867 Gulf Bldg., Pittsburgh 19, Pa. Sales offices in leading cities.

MORE people want MORE aluminum for MORE uses than ever

ALCOA FIRST IN ALCOA ALUMINUM

JULY 1947 149

ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

(Continued from page 148)

RADIATOR TEE

An adjustable tee, for use with onepipe forced hot-water heating systems, offers a means of varying radiator temperatures in different rooms. The tee is installed in the single main to the supply branch of each upfeed radiator, and has a diverter that is adjusted by moving a small lever. The flow through the main is increased rather than throttled when branch flow is cut down. The diverter is not limited to two or three settings,

but permits a full range of adjustments. When completely closed, sufficient circulation remains to prevent freezing. H. A. Thrush & Co., Peru, Ind.

ORIENTATION AID

Sunspotter Chart was designed by William Briggs, industrial designer, to provide a ready means of plotting the direction of shadows cast by the sun at different hours of the day throughout various months of the year. In this way,



Sunspotter Chart for plotting solar angles

it is claimed, buildings can be oriented scientifically and quickly with reference to the sun exposure. Floor plans are superimposed on the chart, from which can be computed the amount of sunlight an interior will receive, depending upon window location and size, at different times of the day throughout the various months of the year. The standard chart is for 40° N. Lat., but other charts are being prepared for other latitudes. Williams Methods, Box 40, Redding, Conn.

INSULATION

Infra Insulation is made up of thin aluminum foil with an accordion-like inner construction providing dead air space; designed for laying in floors or on overhung ceilings, over steel or concrete beams, and for stapling between joists or studs. This insulation is reported to turn back about 95 per cent of invisible. infra-red heat rays, and is remarkably light in weight, 1000 sq. ft. weighing only about 60 lb. Infra Insulation, Inc., 10 Murray St., New York, N. Y.


ALUMINUM TUBING

Production of one line of flexible aluminum tubing for connecting gas appliances to house piping has been resumed following discontinuance during the war. This tubing, supplied in both straight lengths and coils, ranges in outside diameter from 1/4 in. to 11/8 in., with varying wall thicknesses. Nominal weight is from 0.026 to 0.257 lb. per lineal ft., said to be about one-third that of similar copper tubing. Aluminum tubing should be used with aluminum compression-type fittings for connections. Reynolds Metals Co., 2500 S. Third St., Louisville 1, Kv.

FLASHING ANCHOR

A new line of reglets for the installation of counter flashing has been announced. These reglets are set within the concrete or masonry wall and provide a channel in which to anchor the flashing, after which the opening is sealed with lead rope calking. Fry Reglet Co., Dept. AR, 1725 N. Pennsylvania Ave., Bremerton, Wash.

(Continued on page 152)





Macomber All Steel V-Type Nailer Purlins. Shown above are various types of roof decking nailed directly to V Purlins. Specify them for short-cuts to occupancy from standard steel joist loading tables. This modern aid to building is also

available in V-type Floor Joists and Studs. For

further information write us.



A NT

MEMBER OF THE STEEL JOIST INSTITUTE

Hotels need CLEAN, UNFAILING, ECONOMICAL HEAT

-and get it with Petro!

A hotel's reputation rests largely on service — including clean, unfailing heat at all times. Goodwill must not be lost by jeopardizing the comfort and health of guests. Nor can any but the most economical heating system be installed, for heating represents a significant item in operating costs.

Architects like Mr. Roth who have specialized in designing hotels agree that a Petro oil-fired system best meets exacting hotel needs. Cleanliness, the elimination of noise and dirt you can take for granted. Engineered simplicity results in continuous operating reliability. And Petro's sustained, over-all economy has long been a matter of record to cost-conscious architects, engineers and hotel executives.

Back of every Petro system — for any commercial, industrial or domestic use — stands an organization recognized as the nation's largest, most experienced, exclusive manufacturer of oil burning equipment. It's your assurance that a Petro incorporates every modern, tested improvement in automatic oil heating . . . lives up to your recommendation in full.



cuts steam costs



Many of America's finest hotels and apartments, including the Ritz Tower, St. Moritz, Dixie and Belmont Plaza Hotels in New York, and the St. George Hotel in Brooklyn, were designed by Emery Roth, senior member of the architectural firm of Emory Roth & Sons. Mr. Roth, an expert on hotel planning and design of many years' experience, has found Petro "thoroughly reliable and satisfactory."

INDUSTRIAL MODELS: No. 5 or No. 6 fuel oil; manual, semi-automatic or automatic operation; 8 sizes to 450 bhp. Thermal Viscosity preheating.

DOMESTIC MODELS: No. 3 or lighter oils; "conversion" and combination-unit types, 7 sizes. Patented "Tubular Atomization."

FULL DATA on Petro Industrial Burners are in catalog files of Sweet's and Domestic Engineering. Details on Petro Domestic Burners available in separate catalog. Copy of either sent gladly on request.

PETROLEUM HEAT AND POWER CO. · Makers of Good Oil Burning Equipment Since 1903 · Stamford, Connecticut



ANCHOR CHAIN LINK

FENCE rates a top spot on your "spec" list for features like these! To your clients, they mean extra years of all-out protection. And they are your assurance of specifying the best in fencing for factory, institution and home alike.


WRITE TODAY for your copy of "Anchor Protective Fences." It's both a catalog and specification manual for your A.I.A. File 14-K. Contains structural diagrams and specification tables, installation photos, many types and uses of Anchor Chain Link Fence. Just ask for Book No. 110. Address: ANCHOR POST FENCE DIV., Anchor Post Products, Inc., 6600 Eastern Ave., Baltimore 24, Maryland.



ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

(Continued from page 150)



Neon switch handle glows in the dark

GLOWING LIGHT SWITCH

A small neon light is incorporated in the switch handle of a new type of electric wall switch. When the switch is in the "off" position, it glows with a soft light to enable it to be found quickly in the dark. The switch is of the single-pole type and reportedly will fit any standard receptacle for this type of switch. The glow lamp is said to last two years and to use less than two cents worth of current per year. Roberts-Glo-Switch, 700 Jamaica Ave., Brooklyn 8, N. Y.

OIL FURNACES

Duo-Therm fuel oil furnaces never shut off completely during the heating season, in contrast to the "stop" and "start" type of furnace operation. It is claimed that this feature eliminates stratification or "cold 70" and provides a ready supply of heat whenever the thermostat drops a fraction of a degree below the desired temperature. There are 11 models with Btu capacities ranging from 50,000 to 108,000, and offering a choice of both gravity and blower types with either manual or thermostatic controls. Blowers are located either in a tailored rear compartment, or underneath the furnace to save space in small utility rooms. Duo-Therm Division, Motor Wheel Corp., Lansing, Mich.

DRAFTING TRAY

The Wayne Drafting Tray is designed as a handy receptacle for the work tools that usually clutter up drafting tables. The tray slides horizontally above the table on a mounting bar attached to the

(Continued on page 154)

VAPOR Condensation Child's Play Here



A 4-way Evil Within Walls

Moisture condensation on windows may be "child's play," but it can cause these costly evils within walls:

- 1. Soggy, inefficient insulation
- 2. wall staining
- 3. paint peeling
- 4. structure rot

A sure way to lick this 4-way evil of "in-wall" condensation is with a separate vapor barrier. Standard with architects everywhere is Bird Neponset Black Vapor Barrier. Applied on the warm side of insulation, Bird Neponset Black repels vapor, keeps insulation at peak efficiency, ends the other "in-wall" evils. Low cost—only about \$20 to protect a \$10,000 building. See Sweet's Architectural file, 9b-2. For sample, write Bird & Son, inc., 177 Wash. St., East Walpole, Mass.



BIRD NEPONSET BLACK VAPOR BARRIER

BIRD & SON inc., E. WALPOLE, MASS.
CHICAGO NEW YORK SHREVEPORT

Specific Need... Standard Window

-A TYPICAL MONEY-SAVING SOLUTION WITH FENCRAFT



This school training shop exemplifies the versatility of Standard Fencraft Windows. It calls for abundant daylight . . . plenty of ventilation and good control of it. The use of medium size panes is recommended for easy, low-cost glass replacement. Sill vents that discourage leaning out of windows are desirable.

Standard Fencraft Windows provide these benefits—and more. Their trim beauty enhances both inside and outside appearance. They provide permanently easy operation, safe cleaning, lasting weather-tightness, firesafety and low maintenance costs.


Standardization means economy... in first cost and installation. Use of uniform installation details, plus co-ordination of window dimensions with those of wall materials, result in minimized installation costs.

All three types of Fencraft Windows—Casement, Projected or Combination—fit the same size openings. Window openings can be drawn into early plans, permitting later selection of window type without redrawing of plans.

Fencraft Windows are built by craftsmen of America's oldest and largest steel window manufacturer. Quality appearance highly recommends them for the finest of buildings. Standardization economies make them practical for buildings of all types. For details, see Sweet's (Section 16a-9). Or mail coupon.



In a school workshop, achieve large daylighting areas and excellent ventilation control with combined units of Fencraft Intermediate Projected Windows, such as Type 418 (illustrated).



Detroit Steel Products Company Dept. AR-7 2252 East Grand Blvd.,

Detroit 11, Michigan

Please send me data on types and sizes of the new
Fencraft family of Fenestra Windows:

Name_

Company

Address_



OPENED OR CLOSED—or in action—Kinnear Rolling Doors offer greater efficiency "from top to bottom."

They open straight upward, coiling compactly above the doorway out of reach of damage by wind or vehicles. They clear the entire doorway, leaving all surrounding space fully usable at all times.

When closed, Kinnear Rolling Doors offer the extra protection of all-steel construction—against wind and storm damage . . . theft or intrusion . . . fire or explosion.

The rugged Kinnear Motor Operator can be added to any Kinnear Rolling Door for maximum speed and ease of operation, with push button controls at any desired point.

Kinnear Rolling Doors are built in any size, for new or old buildings. Write for new catalog.

The KINNEAR Manufacturing Co.

1860-80 Fields Avenue • Columbus 16, Ohio 1742 Yosemite Ave. • San Francisco 24, Calif.

Offices and Agents in all Principal Cities



ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

(Continued from page 152)

table front by four screws; it can be adjusted as to angle and height above the table. The tray has a crackle-lacquer finish, and mounting bars are cadmiumplated. A. Wayne Nunemaker, 103 S. Wells St., Chicago 6, Ill.

DISHWASHER

The Kaiser dishwasher operates without motors, wiring, belts and gears. Instead, it is powered by water pressure direct from the house hot-water line. Venturi jets, which multiply the normal water pressure four times, perform the dual operation of spraying the dishes and spinning the basket. After automatic rinsing, the lid is lifted to admit room air which dries the dishes while the basket continues to spin by its own momentum. There are two models: the DeLuxe, which has an hydraulic lift to raise the basket from the cabinet; and the Standard, without the hydraulic lift. Both models are furnished either in a white enameled cabinet or in a chassis to be built into the sink cabinet of the kitchen. The dishwasher requires only two connections - to the hot water supply and the drain. Kaiser Fleetwings, Inc., Dept. AR, Kaiser Bldg., Oakland, Calif.

HARDWARE


A number of hardware items for installation in theaters, restaurants, and night clubs have been announced. These include crowd-control posts and ropes, stair railings, push bars, and door grips. Hupp Metal Works Co., 1123 Broadway, Room 307, New York 10, N. Y.


WATERPROOF FINISH COAT

A single brush coat of Agraseal is said to do a protective and sealing job on porous masonry surfaces. For more intense color value and smoother finish, a second coat may be applied. Application is by ordinary scrub brush or by paint brush. Agraseal is made in white, ivory cream, light buff, natural stone gray, yellow, and light green. Tamms Silica Co., 228 N. LaSalle St., Chicago 1.

DOOR CLOSER

The Hydro-Hinge automatic door closer has spring and hydraulic units completely concealed within a specially designed butt hinge, and is installed the same way as the conventional butt hinge. It can be adjusted for varying speeds, positive latching, or silent closing. Bakewell Products, Dept. AR, 1201 Rio Vista Ave., Los Angeles 23.





sewer systems uniform. A recent nationwide survey proves that Clay Pipe is the choice for nine out of ten sewers. Engineers in 123 cities report that of 37,219 miles of sewers in their communities, 33,168 (89%) are Clay Pipe.



Sewer connections are an important part of the over-all sanitary system, and deserve to be made of the same high quality of materials as the main lines. 89% of all sewer mains are Clay Pipe!* The advantages of Clay Pipe are responsible for its preference by leading sanitary engineers. Nine times as much Clay Pipe as any other material is used by American municipalities. The advantages of Clay Pipe for sewer systems make it the best material for connections.

NATIONAL CLAY PIPE MANUFACTURERS, INC.

111 W. Washington St., Chicago 2, Ill. 522 First National Bank Bldg., Atlanta 3, Ga. 1105 Huntington Bank Bldg., Columbus 15, Ohio 571 Chamber of Commerce Bldg., Los Angeles 15, Calif.



20-Year Record of Heating Comfort



Hecht Brothers Department Store, Baltimore, Md. Heated by Webster Steam Heating System since 1927.

This is the 20th year of Webster heating service at Hecht Brothers Department Store in Baltimore, where management has long recognized that heating comfort is an important factor in successful department store operation.

In 1927, when the present home of Hecht Brothers Department Store was built, a Webster Vacuum System of Steam Heating was specified by Abbott, Merkt & Co., Inc., New York, Architects and Engineers. Riggs, Distler & Co., Inc., Baltimore, were the heating contractors.

In 1941, Hecht Brothers decided to discontinue their coal-burning boiler plant and purchase street steam from the Consolidated Gas Electric Light & Power Co. On the recommendation of the Gas and Electric Company, they decided to convert the installation to a Webster Moderator System, then as now recognized for comfort at low cost.

Sam Hecht, President of Hecht Stores, and William P. Calhoun, Store Manager, look upon their Webster Heating System as an investment in customer satisfaction.

If you are interested in heating comfort at low cost backed by the experience of long-service Webster Representatives, write us.

WARREN WEBSTER & CO., Camden, N. J. Representatives in principal U. S. Cities :: Est. 1888 In Canada: Darling Brothers, Limited, Montreal



ARCHITECTURAL ENGINEERING

TECHNICAL NEWS AND RESEARCH

(Continued from page 130)

colors offered. 20 pp., illus. The Sanymetal Products Co., Inc., 1701 Urbana Rd., Cleveland 12, Ohio.*

Wall Closet Fittings (Supplement 46-3). Catalog of a line of wall closet fittings featuring a patented carrier made with the closet plates attached to the fitting by means of four yoke bolts, the heads of which fit into slots on the face plate. Four types described; typical layouts; diagrams; full dimensions and specifications. 12 pp., illus. J. A. Zurn Mfg. Co., Plumbing Division, Erie, Penn.*

WIRING

Q-Floor Wiring Data Manual. General data on Q-Floors and Q-Floor wiring, products listings, layout design and installation data, dimensional drawings, typical applications. Manual gives complete information on every phase of installation, and specifications for each product in the line. Chapter on installation data especially complete. 106 pp., illus. General Electric, Appliance and Merchandise Dept., Bridgeport 2, Conn.*

WOOD CONSTRUCTION

Modern Building with Wood. Pictorial booklet presenting a wide range of light and heavy frame wood structures employing the Teco connector system of construction, Lamella construction, and glued laminated construction. Included are church interiors and exteriors, dining and recreation halls, houses, towers, hangars, etc. Also included are miscellaneous wood products and information on Teco connectors, termite shields and framing anchors. 40 pp., illus. Timber Engineering Co., 1319 18th St., N.W., Washington 6, D. C.

LITERATURE REQUESTED

The following individuals and firms request manufacturers' literature:

Lighting by Feder, 1199 Park Ave., New York 28, N. Y.

Weldon J. Fulton, Architect, 601 Wilshire Blvd., Santa Monica, Calif.

Hughes Aircraft Co., Plant Engineering Dept., c/o H. A. Sullwold, Florence Ave. at Teale St., Culver City, Calif.

Henry F. Manganiello, Architect, First Natl. Bank Bldg., Mount Vernon, N. Y.

R. V. McCann, Architect, 606 Syndicate Bldg., 84 S. 6th St., Minneapolis 2, Minn.

Dillard P. Spangler, Architect, 1313 S. 1st St., Temple, Texas.

Joseph Di Stefano, Jr., Architect, 230 Boylston St., Boston, Mass.

The RESTORATION of COLONIAL WILLIAMSBURG

A Reprint
of the December, 1935
Issue of

ARCHITECTURAL RECORD

104 pages, bound in cloth \$2.00 per copy

The Colonial Williamsburg Number of ARCHITEC-TURAL RECORD—issue of December 1935—was sold out soon after publication but the entire editorial contents have been reprinted and bound in permanent book form with blue cloth covers.

Many thousands of these Williamsburg reprints have been sold but the demand continues unabated.

ARCHITECTURAL RECORD 119 W. 40th Street, New York, N. Y.

Enclosed is \$......for which send...... copies of your reprint, *The Restoration of Colonial Williamsburg*, bound in cloth, at \$2.00 per copy.

Name




...this was a 4-11 fire alarm... necessitating a 4 hour fight, with 43 separate lines of hose and 32 pieces of equipment...temperatures rose to 1600°...yet not a spark of fire nor a drop of water entered this great H-H-M Vault, around which tons of water were poured for 4 hours.

One of the worst bank fires in Chicago's history started at 2:15 a.m., March 31, in the Central National Bank, 728 West Roosevelt Road. Two minutes later, when the fire department arrived, the entire structure was a sizzling inferno. Immediately, two lines of fire hose were played on the H-H-M 7" Steel Vault Entrance and eight other lines of hose bombarded the top of the vault. Without interruption, for nearly four hours, tons of water were poured onto and around the vault each minute. Part of the roof and crumbling sidewalls fell onto the vault, as the entire building was soon reduced to disintegrated rubble. Temperatures surrounding the vault were as high as 1600° F. Yet on April 3rd, the vault entrance was opened under combination — and inside the vault you'd never know there'd been a fire. Over a million in cash, all books, all bank records, were delivered 100% intact.


NOW AVAILABLE!


Herring-Hall-Marvin engineers have prepared an illustrated series of Specifications on the H-H-M 16", 12", 10", 7½", and 3½" Rectangular Vault Entrances. These Specifications present the most advanced principles of vault entrance construction available to the bankers of the world. Any banker, any recognized architect, may view the findings in these manuals by appointment with an H-H-M engineer. Why not write us—today?

HERRING-HALL-MARVIN SAFE CO. HAMILTON, OHIO



THERE'S A REASON WHY HOME OWNERS APPROVE







*We mean Convection Heating

Performance . . . appearance! Two customer demands that determine satisfaction with heat distribution systems. And these are the factors that have "sold" more and more prospective home owners on heat by convection, Tuttle & Bailey Convectors. They have found by experience that—on both counts — T&B units will meet even their most exacting requirements, better.

Here are a few of the performance statistics that have impressed home-owners, that will interest prospects in the planning stage. Start with the principle of convection heating as provided by Tuttle & Bailey Convectors. It means transference

of heat by circulation . . . even, more comfortable room temperatures.

Tuttle & Bailey heating elements—constructed entirely of copper—mean faster response to thermostat control, quicker transmission of heat from fuel to rooms, fuel cost savings.

Appearance — the second important consideration in selecting heat distribution equipment — is another Tuttle & Bailey "first." Neat, trim units harmonize with the most modern home furnishings. Space-saving recessed type, exclusively designed for recessed installation, provides front panel plaster overlap feature.

These are important facts. It will pay you to keep them in mind when your customers ask advice.


TUTTLE & BAILEY



Standardized COPPER CONVECTORS

ASK YOUR JOBBER TODAY

For detailed facts that will aid specifying and installing Tuttle & Bailey Convectors, send for a copy of Catalog C6R. WRITE....
Tuttle & Bailey, Inc., New Britain, Conn.



Let this Manual Answer Your Questions on PLANNED DAYLIGHTING FOR SCHOOL CLASSROOMS

It is easier for the architect to design a school if he has this book at his elbow and easier for a school administrator to answer many questions that come up in connection with natural daylighting.

How bright is a clear sky in winter?—What is the pattern of brightness of an overcast sky with respect to azimuth from the sun and with respect to altitude from the horizon?

What brightness ratios may one hope to get with daylighting constructions available today? How far are windows typically shaded under various conditions of outside lighting? (More than 1,500 classrooms examined to get this information.)

What reflectances are recommended for different interior surfaces? What task brightnesses may be expected with bilateral lighting? What effect does ceiling height have on task brightnesses?

What task brightness may be expected when the child is reading from a book lying horizontal on a desk farthest from the fenestration in a south room on March 21st in Seattle? In New Orleans? In Denver?—In any city in the United States, for any time of day for any room orientation and for a bright or overcast sky?

These are some of the questions answered by the data in this book, "Daylight in School Classrooms." There are hundreds of other questions answered too. The tables are complete enough to permit you to work out many special problems of your own, problems that have never occurred to anyone else but you or problems that are peculiar to your north latitude, or a particular orientation of the classroom that may interest you.

FREE to architects, school administrators, educators, teachers, lighting engineers and others interested in the problems of classroom lighting. Write for your copy today.

OWENS - ILLINOIS

OWENS - ILLINOIS

OWENS - ILLINOIS

OWENS - ILLINOIS

OWENS-ILLINOIS	GLASS COMPANY
	Division, Dept. D-7
Toledo 1, Ohio	
Gentlemen:	
Kindly send me,	at no cost, Daylight In School Classrooms
Kindly send me,	at no cost, Daylight In School Classrooms
	at no cost, Daylight In School Classrooms
Name	at no cost, Daylight In School Classrooms



Machines Work Better, Too with ENGINEERED AIR CONDITIONING

Air conditioning does a far bigger job than merely keeping people comfortable on hot days—though that job alone pays rich dividends to commercial establishments of all kinds in increased patronage, and to employers in greater output and higher work efficiency.

In addition to cooling, true air conditioning heats, humidifies, dehumidifies, filters, ventilates, and circulates air. By performing all of these functions, air conditioning does a year-round job, not only in increasing human comfort, but also in process applications—from drying automobile bodies in a paint tunnel to cooling oil for huge diesel engines. No matter whether the problem is simple or complex,

Trane Engineered Air Conditioning provides the smooth-functioning, trouble-free operation of products that are designed and built together for use together.

Trane heating systems and air conditioning systems—made possible by the complete line of Trane products—are designed for each application by architect, engineer, or contractor. 85 Trane field offices are ready to help them.

The Convector-radiator—modern successor to the old-fashioned iron radiator—has been engineered by Trane for universal application to steam and hot water heating systems, and is being produced in quantity so you can now secure it from local distributors' stocks.

TRANE COMPANY, LA CROSSE, WISCONSIN • Also TRANE COMPANY OF CANADA, LTD., TORONTO, ONTARIO

TONCAN RON

Combines Molybdenum with Extra Copper



It's a proved fact that long-lasting Toncan Iron offers the highest rust-resistance of all ferrous material in its price class. Why? Three reasons: (1) The highly refined open-hearth iron, which is its basic ingredient. (2) Extra copper content—actually, twice that of copper-bearing steel and iron. (3) The addition of molybdenum, which multiplies the effectiveness of the alloyed copper.

For nearly 40 years, Toncan Iron has provided low-cost, unfailing rust protection in thousands of different sheet metal installations. It repeatedly has proved itself to be uniformly ductile, easy to fabricate and weld by all methods. And it has demonstrated that it is unaffected by shearing, bending, punching, corrugating, riveting and other cold working.

Complete information on request. Write to:

See SWEET'S FILE

— or write us for detailed information on these Republic Steel Building Products: Pipe—Sheets—Roofing

Enduro Stainless Steel Toncan Enameling Iron Electrunite E.M.T. Fretz-Moon Rigid Steel Conduit Taylor Roofing Ternes Berger Lockers, Bins, Shelving, Berger Cabinets for Kitchens Truscon Steel Windows, Doors, Joists and other building products

REPUBLIC STEEL CORPORATION GENERAL OFFICES CLEVELAND 1, OHIO

Export Department: Chrysler Building, New York 17, New York

Republic REPUBLIC STEEL TONGAN MOLYBDENUM IRON

—for ducts, gutters, conductor pipes, roofing, siding, tanks, ventilators, skylights, hoods and other sheet metal applications requiring rust-resistance—and for corrugated metal drainage products

A TIP ON CONSTRUCTION FROM THE MEN ON THE JOB

CONDUIT FOR CONSTRUCTION SPEED!



Men who work with rigid conduit know what it takes for real construction speed. That's why they like to work with easy-handling General Electric conduit. It threads easily, bends true, lasts long. These advantages make General Electric conduit important to you-important, because it helps get jobs done fast, helps get them done right. For security and speed in wiring installations, remember to specify General Electric conduit.

AND CONDUIT GOES IN TO STAY

GENERAL ELECTRIC WHITE is hot-dipped inside and out with highquality zinc. Laboratory and field tests prove that this finish gives the best protection against atmospheric corrosion. In addition, G-E White is coated with a baked-on Glyptal* lacquer finish, to form a smooth, hard surface for easy wire pulling.

GENERAL ELECTRIC BLACK, coated with a heavy, enamel finish, is a rigid conduit specifically made to resist the attacks of chemical corrosion. It's ideal for installations where liquid chemicals, fumes, acids, and oils are a threat, and where humidity is low.

Get complete details from your General Electric Distributor, or write to Section C57-75, Appliance and Merchandise Department, General Electric Company, Bridgeport 2, Connecticut. *Trade-mark Reg. U.S. Pat. Off.

GENERAL & ELECTRIC

RACEWAYS ROUND-UP



Merchandise Distributor

For everything in raceways, your best bet, as always, is General Electric. You can rely on this complete line to meet any construction need-for big jobs as well as small ones. When you need information on raceways and accessories, your General Electric Merchandise Distributor is always ready to help you. If you want engineering assistance on underfloor distribution, you can get it from one of General Electric's field force of underfloor experts. Get the habit of calling on General Electric for latest raceways information.




Now you can put an end to the annoying need for specifying several types of bar hangers. The General Electric S-type bar hanger fits anywhere, goes in place easily where studs are on centers up to 24 inches. Users say the General Electric S-type hanger speeds and simplifies box installation.



For wiring flexibility in concrete office buildings, plants, hospitals, and for other construction jobs where provisions must be made for varying wiring needs, look into the advantages of Fiberduct underfloor raceways. These nonmetallic, corrosionproof ducts permit installation of new outlets anywhere in the duct at any time. Buildings equipped with Fiberduct stay electrically young. See us for detailed information





Only one boy or girl in six goes directly from high school into a trade or industry. Yet all go directly into an environment more and more influenced by industry—an environment in which a high percent of their neighbors are engaged in industry. That is why our schools include industrial education departments.

Here is one of the many facets of modern life with which the architect is primarily concerned. The modern school does not have just one old-fashioned "manual training" shop. It has vocational shops and shops for general education; shops covering one field intensely, such as welding—and shops covering a whole field, such as electricity.

The architect no longer supplies merely a floor, four walls, and a lighted ceiling. He supplies a series of work areas, each planned in advance for its specific job. His selection of equipment and its allocation are as important as the building design per se.

He must know where wood flooring is required and where concrete flooring; where clean work is to be done and where dirty work. Where and how shall metals and acids and clay and electrical supplies be stored? Shall the lumber stored for shop work lie down or stand up? Shall tools be kept in a general bin or in separate cabinets? The ratio of window area to floor area is important, as are matters of direct and indirect lighting and every logical safety precaution.

Nine articles in a recent issue of Architectural Record dealt with the many ramifications of planning and specifying for industrial education. All the articles were fully illustrated with photographs, floor plans and diagram details.

Here is another example of comprehensive treatment by Record edi-

tors of a subject largely neglected by contemporary publications. The consistent use of Dodge Reports enables Record editors to know what types of projects currently face their readers—and to shape their editorial program accordingly.

Three important facts result from this policy. First, the Record has more architect and engineer subscribers than any other business or professional paper. Second, at all times at least 80% of all current planning for investment building is on the boards of Record subscribers. Third, the Record is the practical, everyday, workbook of the architects and engineers who select and specify building materials, equipment, furnishings and services.

This is the market place in which to keep your story told.

• We have gathered from many sources and compiled a check list for advertisers entitled, "Pointers on Writing Architectural Copy." Your copy will be mailed on request.

ARCHITECTURAL

RECORD

119 WEST 40TH STREET, NEW YORK 18


OTHER DODGE SERVICES

DODGE REPORTS AND DODGE STATISTICAL RESEARCH SERVICE SWEET'S FILES HOME OWNERS' CATALOGS

REAL ESTATE RECORD & BUILDERS' GUIDE








"Modern steel windows help the architect avoid
that 'factory look' in industrial buildings. He can
design for appearance as well as functional utility."



L. Rossetti Chief Architect for Giffels & Vallet, Inc., L. Rossetti Detroit

For your copy of the Mesker Book of Industrial Windows, write to Mesker Brothers, 4338 Geraldine, Saint Louis 15, Missouri



HIGH SPEED

HIGH EFFICIENCY

IN HEATING OR COOLING...

AEROFIN

Aerofin is sold and sold and sold advertised only advertised of nationally apparatus. for system request.

For exceptionally fast heat transfer at a material saving in fuel, power and valuable space, install Aerofin fin-type coils. Famous for the accuracy of its published ratings, Aerofin can be installed to its full rated capacity. Metal-to-metal bonding and complete tinning maintain full capacity throughout the life of the installation.

Complete range of types and sizes. Expert engineering service available on request.

AEROFIN CORPORATION

410 South Geddes St., Syracuse 4, N. Y.

NEW YORK . CHICAGO . CLEVELAND . DETROIT . PHILADELPHIA . DALLAS . MONTREAL

Now we can

MEET THE HUGE DEMAND

for

FINE WELDWOOD HARDWOOD PLYWOODS



For the first time since before the war, Weldwood Plywood is available in large supply . . . in a wide variety of fine cabinet hardwoods!

And you'll find eager acceptance for Weldwood all through your clientele.

Why? Because . . . even in the face of serious shortages . . . we've carried on a vigorous national advertising campaign to sell Weldwood to homeminded Americans. As a direct result of this advertising, almost half-amillion prospective users have written for more complete information.

We've told them all the entire Weldwood story. They know, for instance, that Weldwood has striking decorative beauty plus high structural

strength. They know, too, that Weldwood can be installed easily and economically . . . either for remodeling or new construction.

And your clients know this: Weldwood's first cost is the last. It's guaranteed against splitting, cracking or warping for the life of the building in which it's installed

Take advantage of this knowledge... and the acceptance that comes with it. Specify Weldwood. It's a modern material of proved quality and demand.

You can get detailed information on the wide variety of sizes and veneers now available from your nearest USP office or representative.

WELDWOOD Plywood

Weldwood Plywood and Mengel Flush Doors are products of UNITED STATES PLYWOOD CORPORATION THE MENGEL COMPANY New York 18, N. Y. Louisville 1, Ky.

Distributing units in Baltimore, Boston, Brooklyn, Chicago, Cincinnati, Cleveland, Detroit, Fresno, High Point, Los Angeles, Newark, New York, Oakland, Philadelphia, Pittsburgh, Rochester, San Francisco, Seattle. Also U.S.-Mengel Plywoods, Inc. distributing units in Atlanta, Dallas, Jacksonville, Louisville, New Orleans, Houston, St. Louis. In Canada: United States Plywood of Canada, Limited, Toronto. Send inquiries to nearest point.

Weldwood* Hardwood Plywood Douglas Fir Weldwood Mengel Flush Doors Douglas Fir Doors Overhead Garage Doors Molded Plywood Armorply* (metal-faced plywood)

Tekwood* (paper-faced plywood) Flexmetl* Weldwood Glue*and other adhesives Weldtex* (striated plywood) Decorative Micarta Flexwood* Flexglass* Firzite *Reg. U.S. Pat. Off.



Plastics and Wood

Waterproof Weldwood for exterior use is bonded with phenol formaldebyde synthetic resin. Other types of water-resistant Weldwood for interior applications are manufactured with extended urea resins and other Welded for Good approved bonding agents.

STAINLESS STEEL



Don't Peek Over His Shoulder

If you'd like to keep up-to-date on the multitude of uses for stainless steel you may have a copy also. For Electromet Review will bring this news to you in quickly readable form. And since the publication covers everything from motor boats to pots and pans, your special interest is bound to be in there, too. So if you wish us to add your name to the 23,000 other industrial executives, designers, and architects who receive Electromet Review free of charge each month, just drop us a note, to Department A-7, Room 308.

ELECTRO METALLURGICAL COMPANY

Unit of Union Carbide and Carbon Corporation 30 East 42nd Street Wew York 17, N. Y.

PRODUCERS OF ALLOYS THAT MAKE STEEL STAINLESS

Beautiful Enduring Strong Tough

reasons why you should specify

WIRE AND CABLE INSULATION MADE FROM

GEON plastics

for industrial, domestic, manufacturing and utilities wiring

Resistance to ozone, wear, sunlight, water, chemicals, and most other normally destructive factors

14 colors including NEMA standards

More conductors in a given space

Excellent electrical properties

Thin coating of insulation

Ease of handling

Easy stripping

Light weight

Be sure to specify wire or cable insulated with GEON in order to get all these advantages. Or, for information regarding special applications please write Department N-7, B. F. Goodrich Chemical Company, Rose Building, Cleveland 15, Ohio. In Canada: Kitchener, Ont.



B. F. Goodrich Chemical Company


A DIVISION OF HE B. F. GOODRICH COMPANY

GEON polyvinyl materials • HYCAR American rubber • KRISTON thermosetting resins • GOOD-RITE brand chemicals

CONTEMPORARY SHOPS in the United States

By EMRICH NICHOLSON

Second and Enlarged Edition, 1946



CONTEMPORARY SHOPS
IN THE UNITED STATES
was published to supply an
insistent demand. Many merchants — many designers —
many people deeply interested
in modern architecture — knew
how much fine work had been
done in this field. They demanded a book which should
show examples of such work,
recently carried through in the
United States.

Including the supplement of 24 pages, over 400 illustrations, plans, etc., showing 113 shops, large and small, handling many lines of merchandise, located from coast to coast, designed by 70 leading designers and architects. 216 pages. 8½ by 11. \$10.00

The above book will be mailed postpaid on receipt of price. Send your order and payment direct to

Book Department, Architectural Record 119 West 40th Street, New York 18, N. Y.

Please send	сору	s)	C	O N	T	E A	M F	0	R	A I	RY	5	S H	0	P	S	11	N	T	Н	E	U	N	L	TE	D)	S	T	A	TI	E S	•	
Money order or	check fo	or \$			er	nclo	se	d.	(A	dd .	2%	Sa	les	Ta	x f	or l	New	Yo	rk	Cit	y c	leli	ver	у.	• • •		. \$1	0.	20)				
Name		٠.									٠.						•						•					•				•		
Address												•					• •	٠.						•										
City												. 7	Zc	n	е					S	t	a	t e		•									

A.R.-7-47

No cartoons — No claims — No coupons —

Just facts for architects!

Like cartoons? We do! But there's no place for them in American Blower Bulletins. You won't find any coupons or advertising claims in them, either.

But you will find them packed with authoritative data on air handling, air conditioning, heating, cooling, ventilating and



allied subjects. These Bulletins have been compiled by American Blower engineers after extensive research. We believe they will save you both time and trouble.

Drop us a card today. The Bulletins shown, or any of our other Bulletins, will be sent promptly without obligation.



Bulletin No. 2314

Aeropel Home Ventilators

This compact, complete unit whisks out odors, greasy fumes, smoke. Keeps kitchens fresh as a daisy. Reasonably priced, easy to install, economical to operate. Also ideal for bathrooms, bedrooms, nurseries, laundries, recreation and utility rooms, small stores and offices.



Bulletin No. 3205

Hay Curing Fans

This complete handy bulletin covers the subject of hay curing with electric ventilation in complete detail—effect of hay drying on quality, how to cut crop losses, cost of installation, operation, design and installation of equipment. A complete and comprehensive discourse on the subject.



Bulletin No. 3723

Capillary Air Washers

For industrial and commercial air supply systems, etc., where a high degree of air purifying at moderate cost is desired. Complete line. Three types—sizes and capacities from 8,800 to 132,000 CFM. Also excellent for mould and spore removal, evaporative cooling, humidifying, cooling and dehumidifying.



Bulletin No. 1241

Corrosion Resisting Fans

These fans are built exclusively to handle corrosive gases, vapors, fumes and smoke from industrial and chemical operations. Covers the subjects of rubber-covered, lead-coated, and lined fans. Also mild corrosion protection coating for fans of standard designs.



Bulletin No. A 703

HS Heavy Duty Fans

American Blower Series 82 Fans are adaptable to a wide variety of heavy duty applications in power plants and industry. Available in 3 classes with capacities from 1,800 CFM to 330,000 CFM. Bulletin contains 72 pages of data on these fans and their application.

AMERICAN BLOWER

AMERICAN BLOWER CORPORATION
DETROIT 32, MICHIGAN

In Canada: CANADIAN SIROCCO CO., LTD., Windsor, Ont.

Division of AMERICAN RADIATOR & Standard Sanitary corporation



The difference between showing a profit or a loss often depends on the use of leftovers. With the new PITCO FRIALATOR leftovers can be quickly converted into profitable fried dishes that will bring your customers back for more. For your profits sake, install



This super-modern fryer has everything a good fryer should have, including automatic heat control and patented cool zone. It saves fat, saves fuel, saves food from burning or charring. So simple in operation, any inexperienced operator can turn out perfect dishes. Fire hazard has been completely eliminated — maintenance reduced to an absolute minimum. Send for new folder showing a PITCO FRIALATOR for every frying need.



THE ORIGINATORS OF THE MODERN DEEP-FAT FRYER

Current models are available today through your Gas Company and equipment supply house.



J. C. PITMAN & SONS SALES CORP.

Sole Manufacturers of Pitco Frialators
711 BROAD STREET LYNN, MASSACHUSETTS





speed up construction

When you use Homasote Insulating and Building Board, you save construction time in two different ways. First, because Homasote means dry-wall construction, you save the time of cleaning up after the plaster application and of waiting for the plaster to dry. Second, you soon discover that Homasote's big sheets (up to 8' x 14') require fewer handlings and many fewer nailing operations.

Homasote combines great structural strength with high insulating value in a single material that is weather-proof. And for interior appearance—Homasote provides a fine-textured, crackproof base for paint or paper . . . does away with unsightly wall joints and batten strips. One big sheet of Homasote often covers an entire wall

or ceiling area; for larger rooms, you plan breaks to occur at doors or windows.

Use this quality building and insulating board for modernization and for new construction. Use it for interior and exterior walls, roof and sidewall sheath-

ings, sub-flooring and ceilings.

We invite architects and builders to send for a copy of our new booklet describing some of the many uses for weatherproof Homasote. The book gives physical characteristics, performance charts, specification data and application instructions. Write for your copy today.

HOMASOTE COMPANY, Trenton 3, N. J.




.FOR MANY MEDIUM SIZE HOMES

... FOR MODEST BUDGETS

THE NEW, IMPROVED, GAS-FIRED

Janitrol Gravity Furnace

IS THE MOST PRACTICAL



GRAVITY warm air has always been a popular method of heating small and medium homes. Now it has been brought up to date by the newly designed, completely automatic Janitrol Gas-Fired Furnace.

Versatile for Many Floor Plans

Especially suited to small basements, this new Janitrol takes little floor area, eliminates the need of space for fuel storage. It's good looking too, with attractive gray casing and neatly rounded corners...looks as modern as its design.

Low Initial Cost and Operation

The Janitrol Gravity Furnace is economical... to install... to use. It gives a gentle, continuous flow of warm air to each room, without blowers or motors. Operation is fully automatic, furnace requires no attention... simplicity of design and

unique construction means low installation and maintenance costs.

IMPORTANT TO REMEMBER! You do not sacrifice quality when you install Janitrol...it's a product backed by 35 years of successful experience, devoted exclusively to the development of the finest gas heating equipment.

Installations are made by factory trained Janitrol dealers, fully qualified to recommend, lay out and service the most practical heating system for any particular type of new construction or remodeling.


Your Janitrol Dealer can show you the way to give your clients all the benefits of modern heating the most economical way.

Write today for the new Heating Guide File A.1A 30B. Architects, Builders, and Contractors will find it most useful.



H&H OUTLETS

SPECIAL-PURPOSE



These Outlets serve special purposes in addition to those served by ordinary receptacle types. Their extra-utility has durable basis in right design, rugged parts, reliable workmanship. Ask for complete specification-data.

HART & HEGEMAN DIVISION

ARROW-HART & HEGEMAN ELECTRIC COMPANY, HARTFORD 6, CONN., U.S.A



Now, lagging material on pipes, ducts, boilers and hot water tanks can be secured firmly and given a sized finish in a single operation.

Apply the canvas, asbestos, fiberglas or other non-conductor-using Arabol Lagging Adhesive as the bond. The adhesive dries in 4 to 6 hours; the job is completed. No paint need be used on the sized finish-unless you prefer to add one coat for appearance. The Arabol method eliminates the time-consuming task of sewing; lowers labor costs. Maintenance is simplified-grease, oil, soot and dirt wash off easily. And the adhesive is vermin-proof . . . fire-retardant, too.

Arabol Lagging Adhesive has successfully passed rigorous tests by independent laboratories. The results show that it retains its adhesive powers despite exposure to extreme temperatures, to immersion in water, and to live steam.

Write us today for detailed facts and figures. Don't place open specifications on lagging workask for Arabol Lagging Adhesive. You can depend on it to fill your most exacting requirements for both utility and appearance. Also, ask about our cork cement for adhering cork to cork on refrigerator lines.

THE ARABOL MANUFACTURING CO.

Executive Offices: 110 East 42nd St., New York 17, N.Y.

CHICAGO—54th Ave. & 18th St. SAN FRANCISCO—30 Sterling St. Branches in Principal Cities. Factories in Brooklyn, Cicero, San Francisco




Adhesives?... ARABOL!

Kimpreg*... **Plastic Armor** for Plywood



LIGHTWEIGHT; WATERPROOF. Kimpreg* plastic surfacing material is an insoluble substance fused to plywood by manufacturers who produce Kimpreg plus plywood, a light, strong material. It repels rain and snow, defies parasites and decay ... is long-wearing and washable.

ARMOR-SURFACED; WORKABLE. Kimpreg surfaced plywood is a versatile, hardworking product. Certain types are suitable for concrete forms, factory storage bins, inspection or wrapping tables, flooring



PERMANENT; ECONOMICAL. Abrasionresistant, scuffproof Kimpreg has many possibilities. Mail the coupon today for complete information about this material-and the names of manufacturers making plywood surfaced with Kimpreg. If you cannot get all the Kimpreg-surfaced plywood you need, please be patient until the resin supply is more plentiful.

PLASTIC SURFACING



Kimberly-Clark Corp., Nee	enah, Wis. Please send me the free Kimpreg book and the names of manufacturers making plywood surfaced with Kimpreg.
	NameAR-747
A PRODUCT OF Kimberl	
Clark	Type of Business
OFF. RESEARCH	Address
URFACING	City, Zone, State

An Owner can't buy Steel Joist Construction later the permanent benefits of

Open Web Steel Joists specified for new construction provide:


- Clear areas
- Fire resistance
- Freedom from plaster cracking
- Rigidity
- Space for service lines


LACLEDE STEEL COMPANY

GENERAL OFFICES

ARCADE BUILDING

ST. LOUIS, MISSOURI





Frick Freon-12 Compressors Air Condition an Office Building

Whether You Need Ammonia or Freon-12 Equipment, You Get What You Want with




Frick Ammonia Compressor


As builders of both ammonia and low-pressure systems, we are in an unbiased position in filling your requirements.

For the ultimate in satisfactory cooling equipment, put your problems up to the nearest Frick Branch or Distributor.





FrickFreon-12Compressor



On't let skimpy electrical systems tie up your plant. Don't let too little power cause too little production when suddenly increased output is demanded.

Adequate Wiring is the only adequate answer. It means copper (or aluminum) enough in the conductors to provide for future load increases and circuits enough in the system to provide outlets whenever and wherever needed. It includes specific steps such as installing higher voltage cables wherever feasible, and using unit sub-stations more widely at locations where loads are great. And Adequate Wiring alone can give you full electrical

efficiency and meet all your present and future lighting and power requirements at the lowest cost per kilowatt consumed.

ADEQUATE BACKGROUND COUNTS

and ceilings. The Okonite Company, Passaic, N. J.

OKONITE

5178

insulated wires and cables for adequate wiring at its best



Today, more than ever, there is necessity for planning far in advance of your client's present needs.

CHAMPION PAPER scheduled Cafeteria Opening 25 Months Ahead!

Like many a restaurant leader . . . Mills, S&W, Colonnade, Stouffer, etc. . . . when The Champion Paper and Fibre Company finds it is going to need a kitchen, right then it calls in John Van. The new cafeteria at their Canton, North Carolina, mill is an example.

With plenty of advance notice, 25 months in fact, Van was ready to install the kitchen and cafeteria right on the dot on Champion's time-table. The early call gave Champion high priority on Van's crowded production schedule and all of the benefits of deliberate, careful kitchen engineering, design, manufacture.

EQUIPMENT FOR THE PREPARATION AND SERVING OF FOOD

DIVISION OF THE EDWARDS MANUFACTURING CO.

Branches in Principal Cities

429 CULVERT STREET

CINCINNATI 2, O.

... You can cut time losses, reduce spoilage and increase production with better ventilation . . .

Swartwout **Roof Ventilating Equipment**

helps you achieve profitable results with economical installations

XPERIENCED engineers of this company are at your service without obligation to you to assist you in the proper solution of your building interior atmospheric problems. They will check your requirements and make recommendations and suggestions for practical solutions with economy. Substantial savings are often effected in this manner, and you have the assurance of the proper equipment for the most satisfactory performance.

Write, wire or phone the factory for name of

nearest representative.

Swartwout Sales Engineers are located in these cities

Atlanta, Georgia Bloomington, Ill. Boston, Mass. Buffalo, New York New York, N.Y. Charleston, W.Va. Omaha, Nebraska Chicago, Illinois Cincinnati, Ohio Cleveland, Ohio Davenport, Iowa Dayton, Ohio Denver, Colorado Detroit, Michigan Great Falls, Mont. Hastings, Neb. Houston, Texas Indianapolis, Ind. Jackson, Miss. Kansas City, Mo. Los Angeles, Cal. Lynchburg, Va.

Albany, New York Memphis, Tenn. Milwaukee, Wis. Nashville, Tenn. New Orleans, La. Orange, New Jersey Philadelphia, Pa. Pittsburgh, Pa. Portland, Oregon Saginaw, Michigan St. Louis, Missouri St. Paul, Minnesota Salt Lake City, Utah San Francisco, Cal. Seattle, Wash. Sioux City, Iowa Syracuse, New York Washington, D.C. Waverly, Pa. (Scranton District)

The Swartwout Company



EQUIPMENT FOR EFFECTIVE ECONOMICAL VENTILATION OF INDUSTRIAL BUILDINGS I'm strong for radiant heat!






I'm strong for convection heat!

Modine gives you BOTH of these great heating principles blended into one!






RADIANT HEATING

Mild, radiant heat in just enough quantity to offset heat loss from window areas — that's what those arrows represent, coming from the Modine Convector Panel below the window. To this we add . . .

CONVECTION HEATING

Warmed air circulated by Convection Heating. Hot water or steam passes through copper heating unit which draws cooler, floor-line air into bottom of convector where it's warmed, rises and then passes out through grille.

Result: Dependable new heating comfort for moderate cost homes and apartments... distinctive room charm and cleanliness without unsightly radiators! Yes, Modine Convector Radiation provides a modern, blended heating system for modern living—a heating system that makes possible individual room control—that responds almost instantly to sensitive automatic controls—that gives you gentle air circulation without the use of moving parts that wear out. If you're planning to build or modernize, think of Modine Convector Radiation... look for Modine's representative in the "Where-to-Buy-it" section of your phone book... or send in coupon below for new, free Convector Booklet! MODINE MANUFACTURING CO., 1773 Racine Street, Racine, Wisconsin.







PRICED FOR TODAY'S HOMES AND APARTMENTS

Modine

CONVECTOR RADIATION

The Modern "proved by use" heating method

173 Ret Re Book

Bire Had on John Dane of Dets



Sheehan and Krech, Designers and Builders
Air Conditioning by Schwerin Air Conditioning Corporation

Simply designed air diffuser blends with interior

Provides complete air conditioning comfort by eliminating drafts, noise, hot or cold spots.


In addition to their unobtrusive appearance, Kno-Draft Adjustable Air Diffusers are specified for installations like the one pictured here in the offices of Schwarzenbach-Huber Co. because they combine all the advantages of scientific air diffusion plus adjustable features which assure positive air pattern control.

Kno-Draft adjustability increases efficiency and economy.

Diffusers improve occupant comfort by delivering conditioned air gently and thoroughly. Drafts and noise so often experienced with grilles, registers and other louvered devices are eliminated. Economy is increased. Diffusers handle greater air velocities and greater temperature differentials. This means less air volume, smaller, simpler ducts and fewer outlets.

To those advantages, Kno-Draft adds adjustment features that increase both the efficiency and economy of the air diffusion principle and a simplicity of design that blends with any decor.

Kno-Draft Direction Adjustment assures positive air pattern control by affording any angle of air discharge from vertical to horizontal that is needed to accommodate ceiling heights, individual or seasonal requirements. Volume adjustment is made with a patented damper that regulates the amount of air without affecting the velocity or diffusion pattern.



Pat. & Pat. Pending

Send for FREE handbook that simplifies the selection and installation of diffusers. Write Dept. S-14 on your letterhead.

W. B. CONNOR ENGINEERING CORP.

AIR DIFFUSION AIR PURIFICATION AIR RECOVERY

112 East 32nd Street



New York 16, New York

IN CANADA: Douglas Engineering Co., Ltd., 1405 Bishop St., Montreal 25, P.Q.

Murphy Cabranette Kitchens

Full kitchen convenience in minimum space

Welded steel throughout. Exposed surfaces of genuine vitreous porcelain.

Made in 4 widths. Add Utility Cabinets (with shelves) and Implement Cabinets for more storage space. Murphy Cabranette Kitchens never require repainting —upkeep is negligible.

No. 39

Ultra-compact. Storage, deepbowl sink, electric cookery and refrigerator for efficiency apartment or bachelor suite. 39 inches wide and 23 inches deep, it fits in tiny space.



Full kitchen convenience in two by four feet. Gas or electric range with oven, electric refrigerator, sink and storage cabinets.

Nos. 60 and 66

Full-sized electric or gas range with oven, full-sized sink, larger refrigerator and more storage space. 60 and 66 inches wide respectively.

Utility and Implement Cabinets

In 15-inch & 2 1 - i n c h widths.

Maybe added to all size kitchens.







DWYER PRODUCTS CORPORATION

Dept. AR547 Michigan City, Indiana

When you insulate with FOAMGLAS ... you insulate FOR GOOD!

PC Foamglas has won a wide reputation as the *permanent* insulation. And the reason is that Foamglas is just what its name implies: glass foam, made up of millions of air-filled, sealed glass cells.


Being glass, Foamglas is moistureproof and vaporproof. Extensive tests have conclusively proved that water cannot get into it or through it, that vapor cannot penetrate it.

Being glass, Foamglas is unaffected by exposure to extreme humidities, acid atmospheres, wide variations in temperature. It won't check, rot, swell, shift, shake loose or pack down. Rodents and insects cannot eat it or nest in it.

In fact, the elements which so frequently reduce or entirely destroy the insulating efficiency of other insulating materials, are completely powerless to harm PC Foamglas. Foamglas is the one truly permanent insulation... for roofs, walls, floors, ceilings of all kinds of buildings. It is the insulation that never grows old. When you insulate with Foamglas, you insulate for good!

We invite you to send for complete facts about this amazing material. Just check and mail the convenient coupon. No obligation. Pittsburgh Corning Corporation also makes PC Glass Blocks.







FOR	ADDITIONAL	INFORMATION	SEE	OUR	INSERTS	IN	SWEET'S	CATALOGS

Pittsburgh Corning Corporation Room 455, 632 Duquesne Way Pittsburgh 22, Pa.	
Please send me without obligation, your free booklets on insulation for: Roofs Walls Floors	
Name	
Address	
City	State

PC FOAMGLAS Waterproof INSULATION
T.M. REG. U. S. PAT. OFF.

These Doors Extend Announcing Cordial Welcome





HOTEL STATLER Washington, D. C. Holabird & Root Architects

Leading hotels throughout the nation have found ELLISON BALANCED DOORS the right answer to their entrance problems. Their attractive appearance and effortless operation give a friendly welcome to the hotel's

patrons. They swing open easily and smoothly with finger tip action due to their exclusive Ellison Balanced Construction. They are pivoted in such a way at the top and bottom that wind pressures are equalized, an important factor in the operational ease. Counter balanced, they require but a slight spring action to close.

This effortless action facilitates traffic flow. Since the doors swing on a shorter radius the door projection is reduced 40 to 45%. Ellison Balanced Doors are made in bronze, aluminum, stainless steel or full plate glass in completely prefabricated units, ready to install. This includes the door, frames, mullions, trim, saddles and necessary hardware. A wide range of standard sizes and types are available or they may be built to your special specifications.

Write for our new 12 page booklet giving additional specifications and illustrations, or see our section in SWEETS

ELLISON BRONZE CO., INC.

JAMESTOWN, NEW YORK

Representatives In All Principal Cities

BALANCED DOORS

in a new, revised, 1947 edition . . .

THE MODERN HOUSE

by F. R. S. YORKE, A.R.I.B.A.

This home building classic, with its collection of the finest examples of modern residential architecture, from the United States, England and Continental Europe, has undergone an up-to-the-minute revision.

Photographs, plans and construction details of most recent, most interesting, most successful modern houses have been added, and an entire section is devoted to systems of prefabrication.

FOR ARCHITECTS, STUDENTS, HOME BUILDERS

Although it is illustrated with hundreds of fine photographs, this book is no mere collection of startling pictures. Materials and construction methods are analysed for each house, and preliminary chapters discuss walls, windows, roofs and planning in relation to twentieth century homes. Architects, students and home owners alike will find this new edition of THE MODERN House a source of ideas and inspiration.

Because it is published in England (by the Architectural Press) under severe manufacturing difficulties, only a limited number of copies of THE Modern House will be available for some time to come. To make sure of securing your copy, order it now from ARCHITECTURAL RECORD, sole distributor, using the coupon below. Price: \$6.50

THE ABOVE BOOK WILL BE MAILED POSTPAID ON RECEIPT OF PRICE Send your order and payment direct to

Book Department, Architectural Record 119 West 40th Street, New York 18, N. Y.

Please send

copy(s)

THE MODERN HOUSE

enclosed Money order or check for \$ (For N. Y. City Delivery add 2% Sales Tax-\$6.63 in all)

Name	· · · · · · · · · · · · · · · · · · ·		
Address			
City	Zone	State	
			A.R. 7-47



air conditioning puts new tenants in old buildings

Tenants of older commercial buildings are always on the lookout for newer, more modern space. This means lower occupancy for the aging building and often a less desirable type of tenant. Carrier air conditioning not only checks the drift of tenants away from older buildings . . . it attracts new ones, and makes even poorly located space rentable.

Year-round air conditioning by

Carrier can be adapted to any type of existing commercial structure . . . office and loft buildings, hotels, apartments, department and retail stores, hospitals and others. Tested design assures proper temperature, humidity and circulation . . . freedom from objectionable dust and street noises . . . and provides positive, draft-free ventilation. Carrier systems are compact, quiet and economical.

The design and manufacture of dependable air conditioning systems and room units demand years of experience. Carrier engineers are the most experienced in the air conditioning field. They created air conditioning . . . and have teamed up for years with architects and consulting engineers to bring modern, efficient air conditioning to buildings of every type. Carrier Corporation, Syracuse, N. Y.



JULY 1947

183




Where, oh where, is the right color? You'll find a quick answer in the Moleta COLOR GUIDE. This handsome COLOR GUIDE gives a selection of 150 beautiful colors to show your clients...each tint displayed on a large page (9" x 15") and shown in true-life, right-on-the-wall effect... every tint from the palest to the darkest. And on the reverse of each sheet is given the exact mixing formula.

Write for your copy of the Moleta COLOR GUIDE—\$5.00, delivered anywhere in the U. S. A. MONROE, LEDERER & TAUSSIG, INC. 606 N. American St. Phila. 23, Pa.



FLAT OIL PAINT
THE TRULY WASHABLE FLAT PAINT





mind you that Nathan Straus-Duparquet's food service engineers are at your service — to assist you in your kitchen and cafeteria problems.

Ninety years of experience has proven Duparquet's superior design and equipment.

CHINAWARE • SILVERWARE • GLASSWARE • DUPARQUET KITCHEN EQUIPMENT • REFRIGERATION • FURNITURE & FURNISHINGS • UTENSILS

NATHAN STRAUS-DUPARQUET, INC.

Now Located At 33 EAST 17th ST. (Union Square North), N. Y. 3, N. Y.

BOSTON • NEW HAVEN • CHICAGO • MIAMI

EMPLOYMENT OPPORTUNITIES AVAILABLE

ARCHITECTURAL DRAFTSMAN — JR. For design and layout. Should have training from accredited school in fundamental principles of construction. Write, stating educational background, experience, and salary desired. University of Chicago, Chicago 37, Illinois.

WE HAVE OPENINGS in our permanent organization for two Senior Draftsmen, with good educational background and experience in Working Drawings other than residential, such as hospitals, schools, churches, commercial, etc. Golemon & Rolfe, Architects, 915 Woodrow St., Houston, Texas.

THERE ARE MANY EXCEPTIONAL opportunities for graduate architectural and architectural design draftsmen in Philadelphia, Harrisburg and nearby Southern States that will pay anywhere from ninety to one hundred and thirty-five dollars per week, and we have a large number of definite leads. Write Executive Employment Service — Technical Department — 37 South 13th Street, Philadelphia 7. 'Phone Locust 7-2828.

MANUFACTURERS' REPRESENTATION DESIRED by experienced and successful promoter of building materials, highly trained in architecture and construction. Have unusually numerous and valuable contacts in both fields. Exclusive West Coast representation preferred. Los Angeles married veteran. Highest recommendations. Box 242, Architectural Record, 119 W. 40th St., New York 18, N. Y.

SERVICES EXCHANGED: Experienced Architectural and Structural Draftsman — (girl — employed) will type specifications free for one year, for instruction to write same. Do not reply if jobs are 60% residential. Must be Chicago Loop or North suburb — or my home. Box 244, Architectural Record, 119 W. 40th St., New York 18, N. Y.



AVAILABLE IMMEDIATELY

Add together the savings in initial equipment cost, operating expense and maintenance charges obtainable with Dravo Heaters and you have gone a long way in helping to offset the unusually high cost of building today.

And Dravo Counterflo Heaters have other money saving advantages too: the interchangeability of gas burners with oil burners; the combination gas-oil burning arrangement available at purchaser's option; the large capacities ranging upward from 400,000 Btu output; control and fan systems arranged for summer ventilating service; stainless steel chamber for extra long life.

Since Dravo Heaters are available immediately in stock, you can use the summer ventilating feature now and be prepared for comfort heating next season. Write for Bulletin FE-516 for full description.

DRAVO CORPORATION

Pittsburgh

Philadelphia

Detroit


Atlanta


Cleveland

New York Wilmington











4007 FARNAM STREET

OMAHA 3, NEBRASKA

HAYNES PRODUCTS CO.

.

2nd Printing

The Complete ...

Authoritative up-to-the-minute Handbook

by Charles Butler, F.A.I.A., and Addison Erdman, A.I.A.

A Case-Study Analysis of **Modern Hospitals**

With tremendous energy and insight Charles Butler and Addison Erdman, distinguished architects and hospital consultants, have made a nation-wide survey of the current adaptation of hospital architecture to changing practices in hospitalization.

> The fruits of their study are set forth in "Hospital Planning" — a completely new treatise of present-day practices, based on a painstaking study of hundreds of institutions from which have been selected fifty-one modern hospitals, representing the creative efforts of more than thirty architectural firms, for illustration and discussion. "Hospital Planning" presents a textual summation of the

outstanding problems in hospital architecture and shows how these problems have been met in actual practice. Generous use of illustrations, including perspectives, floor plans, elevations and photographs, make solutions abundantly clear and afford sound, applicable principles for innumerable problems to come.

For Hospital Administrators . . . Superintendents ... Doctors ... Architects

This 232-page, fully-illustrated volume, carefully organized for both reading and reference, is designed for architects and hospital groups alike. It will help trustees, administrators and doctors to visualize their problems in terms of their community needs . . . show how others are meeting similar problems . . . provide them with a basic understanding of hospital architecture so that they may intelligently discuss their problems with the architect.

It will help architects and engineers to learn of the great ad-

vances made in hospital architecture ... to acquire a working knowledge of medical problems and hospital procedure . . . to avoid the many pitfalls which beset the hospital planner.

Order Your Copy Now

With this second printing "Hospital Planning" is again temporarily available at the price of \$15. It is offered with the full knowledge that it may be worth incomparably more to you than its cost — so much more that cost is no valid consideration.

So use the convenient coupon below to make sure to get your copy of "Hospital Planning" before the second printing is sold out. The book will be sent promptly, prepaid.

A FEW of the architectural firms whose works were selected for discussion and illustration include...

Coolidge, Shepley, Bulfinch and Abbott Samuel Hannaford & Sons Schmidt, Garden and Erickson

Jamieson and Spearl Charles B. Meyers James Gamble Rogers Mayers, Murray and Phillip Eggers and Higgins Crow, Lewis and Wick

Address.... City......Zone.....State......

---- Mail this coupon today ----

ARCHITECTURAL RECORD BOOK DEPARTMENT

119 West 40th Street, New York 18, New York



"Hospital Planning" presents the plans of fifty-one selected modern hospitals . . . represents the creative efforts of 30 architects. Includes 32 photographs . . . 11 site plans . . . 187 floor plans . . . 38 special unit plans of rooms, wards and departments... numerous construction details.

THE AUTHORS—Perhaps no other two authors are so well qualified by background and experience to write a volume of such broad scope and magnitude as those selected for this authoritative and technically difficult work.



Charles Butler has been closely associated with hospital planning throughout his broad professional career. As architect or consultant, his works include St. Luke's International Medical Center, Tokyo; War Demonstration Hospital at Rockefeller Institute; Goldwater Memorial Hospital.




Addison Erdman, holder of the A.I.A.'s Langley Fellowship for two successive years, is a consultant on hospitals for a number of architectural firms. His works include the Mobile Hospital Unit for the British Army in Egypt, the Private Patient Pavilion, Methodist Hospital of Brooklyn. Recently appointed as one of the five architects consultants for the Veterans Administration.

HOSPITALS selected for illustration include — Cornell-New York Medical Center, New York; Goldwater Memorial Hospital, Welfare Island, New York; Methodist Hospital, Brooklyn; General Hospital, Cincinnati; Saint Vincent's Hospital, New York; Community Hospital, Enter Creek; Saint Mary's Hospital, New York; Community Hospital, Battle Creek; Saint Mary's Hospital, Rochester, Minnesota; American Memorial Hospital, Reims, France; Mallinckrodt Institute of Radiology, Saint Louis; Royal Victoria Hospital, Montreal; Rochester Municipal Hospital, Rochester, New York; Potts Memorial Hospital, Livingston, New York; Fort Sill Hospital, Fort Sill, Oklahoma. Saint Luke's Hospital, Spokane, Washington; Massachusetts General Hospital, Boston and many more.

See us at Booth 11, Grand Central Palace, New York, July 7th to 12th






IMMEDIATE DELIVERY

AMERICAN BOWSTRING WOOD TRUSSES
REDUCE BUILDING COSTS

Your builders won't have to look for scarce labor... or hard-to-get materials. For American has the skilled truss men... finest materials... and the production capacity to deliver immediately or on the date you specify.

Send for Architects Data Sheet Free

25th Anniversary



AMERICAN ROOF TRUSS CO.

Phone PLAza 1772 6844 STONY ISLAND AVE. CHICAGO, 49 Phone ADams 1-4379
292 W. SANTA BARBARA AVE.
LOS ANGELES, 37



Rooms with a variety of uses! That's the modern trend... and how well Modernfold fits in with today's emphasis on efficiency, convenience and flexibility. For instance, this accordion-type door can be used to divide large rooms into smaller ones, each one employed for its specific function. But when the homeowner needs a large room... it is easy to fold these beautiful, fabric-covered, metal-framed closures to the wall. Write for full details on these efficient doors today... see how they save space, eliminate the swing area of conventional doors.

NEW CASTLE PRODUCTS • NEW CASTLE, IND.

Dealers in All Principal Cities in the United States and Many Foreign Countries

In Canada: Raymond Manufacturing Co. 719 Imperial Street, N. W., Montreal, P. Q.

DELANY FLUSH VALVES





THE HEATER SENSATION OF THE YEAR!

ELECTROMODE

WITH THE EXCLUSIVE, PATENTED SAFETY-GRID

O wonder homemakers everywhere are choosing Electromode, the only all-electric heaters with the Safety-Grid — an exclusive, patented castaluminum heating element that has no exposed hot wires or glowing coils . . . that won't, can't cause fire, shock or burn!

Architects, too, are choosing Electromode as the safe, cost-saving answer to many heating problems. This complete, quality-built line of electric heaters includes attractive built-in models for homes... many standard and specialized unit heaters for factories, stores, and offices. Investigate now!

A COMPLETE LINE—MANY APPLICATIONS FOR HOME, FARM, INDUSTRY!



PORTABLE ROOM HEATER. A sturdy "quality" heater that's completely safe for children. Combines lightness with compactness. Plugs in anywhere.



BILT-IN-WALL SMALL-ROOM HEATER. Easily installed in bath or any small room; requires no special wiring.




BILT-IN-WALL ROOM HEATER for homes or offices. Employs unique Down-Flo principle of warm air delivery. Manual or thermostatic control.



PORTABLE ROOM HEATER for home and office. Gives high BTU output; circulates warmth by Down-Flo principle.



STANDARD UNIT HEATER for industrial use. One of a complete line of Electromode standard and specialized industrial unit heaters.



X-Ray view of Electromode Portable Heater shows the exclusive cast-aluminum Safety-Grid.

READ ABOUT THE OUTSTANDING AD-VANTAGES OF ELECTROMODE HEATING

New 24-page booklet, "Plan for Perfect Heating", describes the benefits of Electromode home heating, and shows how Electromode Heaters can effect real savings in new-home construction. Also, new Industrial Heater Bulletin contains valuable technical information on industrial space heating . . . tells about Electromode Heaters for factories, stores and offices. Get these two booklets from your Electromode supplier, or write to Electromode Corporation, Dept. A-77.



ELECTROMODE CORPORATION . 45 Crouch St., Rochester 3, N. Y.

WORLD'S LEADING EXCLUSIVE MANUFACTURER OF ALL-ELECTRIC HEATERS







TATTNALL SQUARE BAPTIST CHURCH

"The set of Maas Chimes in the belfry of our church has been by common consent declared a great blessing to our community."

THE MORAVIAN CHURCH Sturgeon Bay, Wisconsin

"We are pleased beyond expectations with our Maas Chimes. Their beautiful clear tones add much to our worship services."

FIRST BAPTIST CHURCH Childress, Texas

"I think every person in our church appreciates this addition to our worship program. The chimes are invaluable to the music program and serve to call attention to spiritual worship."

ST. RITA'S CHURCH Santa Rita, New Mexico

"My congregation and the public of Santa Rita in general, are simply thrilled with the beauty and performance of your Maas Chimes."

BAY SHORE COMMUNITY CONGREGATIONAL CHURCH Long Beach, California

". . . my tests and personal analysis and observations convince me beyond a doubt that the Maas Cathedral Chimes are superior to anything else on the market."


CATHEDRAL CHIMES

Room 21, 3015 Casitas Ave., Los Angeles 26, Calif.

Write for descriptive literature

(Specify organ you have





A highly magnified section of Duraplastic concrete would look something like this. The two large black areas represent small portions of coarse aggregate; small black spots represent sand; gray area represents cement paste; white dots represent entrained air bubbles.

Duraplastic cement provides the proper amount of entrained air by intergrinding with the cement the precise amount of air-entraining material needed for satisfactory field performance.

It requires less mixing water and reduces segregation and bleeding.

It makes the concrete more workable, more plastic, more cohesive, more uniform and more durable.

For almost any type of concrete work, Duraplastic cement makes better concrete at no extra cost. It complies with ASTM and Federal specifications, and sells at the same price as regular cement.

Send for further information. Write to Universal Atlas Cement Company (United States Steel Corporation Subsidiary), Chrysler Building, New York 17, N. Y.

OFFICES: Albany, Birmingham, Boston, Chicago, Cleveland, Dayton, Des Moines, Duluth, Kansas City, Minneapolis, New York, Philadelphia, Pittsburgh, St. Louis, Waco.

AR-D-52

ATLAS DURAPLASTIC HARK REG.

AIR-ENTRAINING PORTLAND CEMENT


MAKES BETTER CONCRETE AT NO EXTRA COST




"THE THEATRE GUILD ON THE AIR"-Sponsored by U. S. Steel-Sunday Evenings-ABC Network










For competent, authoritative assistance... Quick!



YORK V/W "the compressor that never wears out"

York V/W Compressors are so constructed that all parts which may be subjected to wear can be removed easily for inspection or replacement. Hence, it may truly be said that York V/W Compressors for air conditioning and refrigeration applications, as units, will never wear out.

Cylinder liners, for example, may be readily removed and replaced . . . after long, efficient service. Liners are centrifugally cast of nickel iron and honed to a mirror finish. Drilled ports provide for suction and unloading.

The cylinder liner is but one of the many exclusive design features of the York V/W Compressor and is representative of the thoroughness of York engineering throughout its complete line of refrigeration and air conditioning equipment.

York Corporation, York, Penna.

seasoned York Engineer near you

There's a

All over the United States, experienced York-trained engineers are assisting architects, consultants and contractors in their refrigeration and air conditioning problems . . . in planning, purchasing, installing and maintenance.

In the St. Louis area, for example, District Manager Edwards and his staff of 12 sales engineers devote their full time to the problems of York customers in this region.



E. F. EDWARDS

District Manager

C. S. McDORMAN
Sales Manager

Assisted by Fred Downs

E. A. Froese

J. C. McDonald

H. W. Meinholtz

H. E. Miller

P. O'Daniel

O. A. Rohner

C. G. Skinner

H. W. Walling

E. F. Weber, Jr.

W. Wilder



Every Architect should have these STEWART CATALOGS

Catalog 82, Standard Iron Fences (with Channel Rails, Gates and Arches)

Catalog 80, Standard Iron Fences (with Angle Rails)

Catalog 83, Standard Chain Link Wire Fences and Gates

Catalog R-38, Railings, Pier Lanterns, Interior Gates, Veranda Work, etc.

Catalog W-40, Window Guards, Wire Mesh Partitions, Folding Gates, etc.

Catalog 1-42, Industrial Fence Specifications Manual

These catalogs contain complete information on Stewart Iron and Wire Products. Check your file of Stewart literature. If you do not have all the catalogs listed above, we shall be glad to send them to you. Stewart also manufactures the following jail and prison equipment: Steel Cells, Bunks, Hinge and Sliding Type Doors, Locks and Locking Devices, Iron Stairways, Gratings, etc. Complete information on request.



IRON THE STEWART TRE IRON WORKS CO., Inc. 1465 Stewart Block CINCINNATI 1, O.


Meet the Demand

for cool, refreshing, drinking water with HAWS Electric Water

Coolers!

Specify them for all types of business, large and small. The distinctive, modern-designed, all-metal cabinet with its smart stainless steel top harmonizes with any surroundings. HAWS Electric Water Coolers are dependable, economical, silent in operation . . . and amply provide fresh, cool drinking water with complete safety. You can depend upon HAWS! WRITE TODAY for more information on HAWS Sanitary Drinking Fountains and ..





WATER COOLERS

HAWS DRINKING FAUCET CO. 1808 HARMON STREET (SINCE 1909) BERKELEY 3, CALIFORNIA Agents and Sales Representatives in All Principal Cities



FOR NON-FADING COLORS Specify CABOT'S

Cabot's Collopakes come in a wide variety of fresh, lively colors which will not fade or lighten, even under severe exposure. Collopakes have great hiding power, long lasting gloss, and produce a surface free from brush marks. All this will give years of beauty and protection to any house you design.

Write today for color card and complete information.

SAMUEL CABOT, INC. 1294 Oliver Bldg.,




Available



Again

TIME-SAVER STANDARDS

Architectural Record's ten-year collection . . . all in one volume



IN RESPONSE to insistent demand for more copies, here, reprinted again in one volume of encyclopedic size, are virtually all the Time-Saver Standards ever published - 277 of them - exactly as they appeared originally in Architectural Record and American Architect during the past ten years - with one 12-page master index!

Just off the press, for immediate delivery to you, is this work of 656 pages, with a mailing weight of 41/2 lbs., containing a complete collection of these now famous authoritative monographs on technical aspects of construction dealing with

- Architectural Design
- Materials Technology
- Engineering Data
- Building Practice

Designed for the practical guidance and every-day use of architects, engineers, specification writers and building technicians, TIME-SAVER STANDARDS will bring you a wealth of detailed information on design and building practice . . . carefully selected from the works of the nation's leading building designers and engineers.

Well-Organized 12-page Index

This wealth of data is carefully organized and painstakingly presented. It is so thoroughly indexed that there are 1,856 references and crossreferences . . . occupying twelve pages of closely set print.

Experience shows that a single item in TIME-SAVER STANDARDS can well save hundreds of dollars in economy construction . . . save many hours of your valuable time. Yet you can now place this concise and well-organized planning data at your command for the nominal sum of \$12.00 - provided you act now.

Order Your Copy Now

The first printing of TIME-SAVER STANDARDS last November was sold out almost before publication. Now an unanticipated flood of reorders - for extra copies and multiple copies - on top of new orders indicates the second printing will soon be snapped up.

So get your copy now. Don't get caught on a long waiting list. Simply fill out the coupon at right, attach your check or money order for \$12.00, and mail today. Your copy wil lbe rushed to you without delay.

These telescopic outlines of only a very few of the 277 Standards give a quick idea of the detailed treatment accorded each subject.

As = M (FT, KIPS)

Dry-wall Construction. Materials applicable. Fiber board. Fiber Dry-wall Construction. Materials applicable. Fiber board. Fiber insulation board. Planks and tileboards. Hardboard, Gypsum wallboard. Plywood. Cement asbestos. Plastics. Composite and self-supporting walls and partitions... Advantages. Handicaps. Costs. Terminology. Classifications and sizes. Framing and furring. Joints. Nailing and cementing. Flexible fasteners. Finishing. Simplified practices. Uses. Applications. References.

Heating—Unit Heaters. Typical Heat sources. Boiler capacity. Characteristics. Location. Selection data. Capacities. Controls. Characteristics. Location. Selection data. Capacities. Controls. Fresh Air connections. Pipe connections. Louvres. Grilles. De-

Basement Waterproofing. Impermeability of concrete cracks and joints in masonry. Hydrostatic pressure. Recommended concrete mixtures. Effect of curing time on permeability. Integral and membrane methods. Plastic and iron coating. Cement-base coatings.


Folding Partitions. Center hung doors. Pair-operated doors. Pockets. Passage through closed partitions. Door construction and soundproofing. Rolling partitions. Folding fabric partition.

Lighting. Recommended levels of Illumination. Fixtures for filament and mercury lamps. Luminaire spacing. Room index. Coefficients of illumination. Layout suggestions. Conformity with structural design. Computed values of illumination. Lumen output of lamps.

Noise Reduction Acoustical Materials. A rule-of-thumb answer to what noise coefficient to use. Special applications. Materials for plastic application. Costs. Appearance. Design. Fire resistance. Light reflection. Heat transmission. Lighting. Pre-cast materials. Effect of paint. Acoustical Units: Wood framing; metal suspension systems.

sh	er for copies of
STANDARDS at \$1	of the 656-page TIME-SAVER 2.00* a copy. I enclose \$
* Add 24 cents for New York	City delivery — \$12.24 in all.
Name	The second second
Address	
City	Zone





ockwood

IDENTIFIES QUALITY IN BUILDERS' HARDWARE

LOCKWOOD identifies its Builders' Hardware with this famous Trade Mark. You will find it on cylinder locks and keys, on mortise locks, on door closers . . . a symbol of enduring quality since 1882.

To the Architect the name LOCKWOOD also signifies a line of Builders' Hardware embracing all requirements, characterized by steady advancement in feature and design . . . and a company that never hesitates to give full and prompt co-operation.

We aim to keep it that way.

LOCKWOOD HARDWARE MFG. COMPANY

Division of Independent Lock Company

Fitchburg

Massachusetts



a new approach to office lighting

Specifically designed for eyesight protection, Wakefield's new Over-ALL lighting provides smooth, pleasing, diffused light over all . . . makes for fewer errors, less eyestrain, more cheerfulness. Based on lighting results where they count. Ask your Wakefield distributor or power company lighting engineer about Over-ALL lighting—or write for new booklet. The F. W. Wakefield Brass Co., Vermilion, Ohio.

The STAR

Combines both fluo-rescent and luminous rescent and luminous indirect light. User-checked to give ex-tra assurance of sim-ple, sturdy construc-tion, easy mainte-nance. Ideal for office, school or drafting school or drafting room. Ask for details.

The Wakefield Star

LIGHTING EQUIPMENT FOR OFFICE, SCHOOL AND DRAFTING ROOM

One little house was Better




Once upon a time there were a lot of little houses...cute little houses, all in a row.



Each little house had a red brick front, a nice slate roof, a comfy little porch . . . and standing in a row they looked as alike as so many peas in a pod.



And people came to look at these cute little houses . . . and they looked and looked until they came to one little house. Then they stopped and said . . . "WoW!"




They said "WoW" because this house was different. This little house had a kitchen with class . . . a kitchen that looked ever so much better than the kitchens in the other little houses . . . because this kitchen had a Tracy sink . . . in lifetime stainless steel.



And when the people saw the beautiful new Tracy sink they quickly recognized the built-in quality of its stainless steel top. Then the entire house began to look like a better value and the people said: "This is the house we want."







CUT BUILDING COSTS

Cross loading docks and ramps off your plans by specifying Oildraulic Levelators for modern commercial and industrial buildings. Floors can be poured on grade instead of at railway car or truck bed height. You save space and give clients more efficient buildings at lower cost. Oildraulic Levelators lift loads (up to 50,000 lbs.) quickly to trucks, freight cars or different building levels. Installation simple and inexpensive. Write for Catalog RE-201.



ROTARY LIFT CO., 1008 Kentucky, Memphis 2, Tenn.

Rotary LEVELATORS



HENEY INDUSTRIES, Trenton, N. J.

cause today Cheney Flashing is no longer a specialty—it's

a standard commodity.



COSTS LESS Latest electronic manufacturing methods plus high volume production put Olsonite ahead of the field both in low unit cost and in speed of delivery.

LOOKS BETTER Olsonite will not chip or mar and resists acid or cigarette burns. Non-corrosive brass hinges are covered with Olsonite so that no metal is exposed.

LASTS LONGER Solid homogeneous plastic construction has no core to split or warp. There are no joints, seams or crevices to give way.

WRITE DEPT. AR 7 FOR INFORMATION

WE WE SHAPE OF THE STEEL COMPANY

PLASTICS DIVISION
B 5 61 BUTLER RUENUE • DETROIT 11, MICHIGR




LONE STAR CEMENT CORPORATION

Offices: Albany • Birmingham • Boston • Chicago • Dallas • Houston Indianapolis • Jackson, Miss. • Kansas Citv, Mo. • New Orleans • New York Norfolk • Philadelphia • St. Louis • Washington, D. C.

WRITE FOR

DESCRIPTIVE FOLDER Dept. R



Makers of Fine Pencils since 1889

67 FLEET STREET



JERSEY CITY 6, N. J.

CREO-DIPT

Mean MORE PROFITABLE **BUSINESS FOR YOU!**

Through home and housekeeping advertising . . . through trade jourand consumer literature... Creo-Dipt has been creating a greater public appreciation of the beauty,

durability, and true economy of Creo-Dipt stains . . .


In your association with Creo-Dipt, you become a partner in the goodwill of the company, the quality reputation earned by its products since 1909 - ever since Creo-Dipt created the first pre-stained shingle.

Creo-Dipt invites your inquiry.

"Plus" Values ONLY CREO-DIPT GIVES YOU

A World of Color
The New Beauty of "CREO-DIPT'S Outside Look"
The Long Life of CREO-DIPT'S Preserving-Oil Stains
Promotional and Merchandising Service
National Trade Paper and Consumer Advertising
Unprecedented Public Acceptance and Demand
The "Know How and Show How" of America's First Stained Shingle Manufacturer.

NORTH TONAWANDA, N. Y., U.S.A. CREO-DIPT OF CANADA, LTD., VANCOUVER, B. C.



The Colored Spots are our Trade Mark, Reg. U.S. Pat. Off.

SPOT SASH CORD

WITH WEIGHTS AND PULLEYS

— the one method of hanging windows that has been proved by generations of actual use to provide perfect and permanent balance.

SAMSON CORDAGE WORKS . BOSTON 10, MASS.

DIFFUSION



IX Important New Features!

- 1. Smart new functional design
- 2. No streaks on walls and ceilings
- 3. Installation costs drastically cut
- 4. Balancing becomes quick one man job
- 5. Branch quadrants eliminated
- 6. Manual shut-off aids fuel saving

MINNEAPOLIS-HONEYWELL REGULATOR CO.

2600 FOURTH AVENUE SOUTH . MINNEAPOLIS 8, MINN.

INDEX TO ADVERTISEMENTS

Catalogs of concerns marked (s) are filed in Sweet's File (1947)

5	Adam, Frank, Electric Company 43	General Controls
	Aerofin Corporation	s General Electric Cor
	Air Reduction	s General Electric — L
s	s Allied Chemical & Dye Corporation	General Pencil Com
	Aluminum Company of America	s Goodrich, B. F. Cher
	American Air Filler Co., Inc.	s Great Lakes Steel Co
	American blower Corporation	3 Olean Eakes Sicon C.
	s American brass company	
1	s American Flange & Munoracioning	s Hart & Hegeman Di
	American Gas Association	s Haws Drinking Fau
	American Roof Truss Company	Haynes Products Co
	s Anaconda Copper Mining Co	s Herring-Hall-Marvin
	s Anchor Post Products, Inc	s Hoffman Specialty
3	Arabol Manufacturing Co	Homasote Company
	Architectural Record	s Horn, A. C., Compo
	s Armstrong Cork Company24–25	s Horn Brothers Comp
	s Arrow-Hart & Hegeman Electric Co 174	
	5 Allow-lian a riegenian	s Imperial Brass Mfg
	s Barber-Colman Company 142	s Independent Lock C
	s Barrett Division	s Insulite Division
	Benjamin Electric Mfg. Co	s International Steel
	s Bethlehem Steel Company	
	s Bird & Son, Inc	Jenkins Bros
	Bituminous Coal Institute	s Johns-Manville
	s Blank, Frederic, & Co., Inc	s Josam Manufacturi
	Blodgett, G. S., Co., Inc	
	Books156-170-182-189-197	s Keasbey & Mattiso
	Brasco Mfg. Co 194	s Kimberly-Clark Con
	s Bryant Electric Company	Kinetic Chemicals,
	s Bull Dog Electric Products Company 21	s Kinnear Manufactu
	Burnham Boiler Corporation 196	s Koppers Company
	s Burt Mfg, Co	
	Byers, A. M., Co 4	s Laclede Steel Comp
,		s Libbey-Owens-For
	s Cabot, Samuel, Inc	s Lockwood Hardwa
	s Carrier Corporation	Lone Star Cement
	Case, W. A., & Son Mfg. Co3rd Cover	s Louisville Cement
	s Ceco Steel Products Corporation	
	s Celotex Corporation	Maas Organ Comp
	\$ Century Lighting, Inc	s Macomber, Incorp
	Cincinnati Fly Screen Co 184	s Mahon, R. C. Com
	s Cold Spring Granite Company	s Martin-Parry Corp
	Committee on Steel Pipe Research	McQuay, Inc
	Connor, W. B., Engineering Corp	s Mengel Company
	s Coyne & Delany Company	s Mesker Brothers
	Crane Co	Michaels Art Bron
	s Creo-Dipt Company, Inc	Miller Company
	s Cutler Mail Chute Co	s Minneapolis-Hone
		s Minnesota & Onta
	s Day-Brite Lighting, Inc	s Modine Manufact
	s Detroit Steel Products Company	Monroe, Lederer 8
	s Dravo Corporation 187	Marie Co.
	s Dunham, C. A., Company	s National Chemica
	s Dwyer Products Corporation 180	National Clay Pipe
		s National Gypsum
	Electro Metallurgical Company 168	s National Radiator
	Electromode Corporation	s Nelson, Herman C
	s Ellison Bronze Co 182	s New Castle Produ
	Employment Opportunities 186	Norfolk & Western
	Enterprise Engine & Foundry Co	
	Faber, A. W., Inc	Okonite Company
	Faber, Eberhard	s Otis Elevator Com
	Fedders-Quigan Corp	s Owens-Illinois Gl
	s Fiat Metal Mfg. Company	s Ozalid Products D
	s Fir Door Institute	
	\$ Fitzgibbons boner company, mental	
	s Flintkote Company	
	Frick Co	NEW YORK III
	THER CO	NEW YORK — H. Ju Benton B. Orwig, Cr
	Golort C R Company	CHICAGO - Jack C
	s Gelert, C. R., Company	ANGELES - Bob We

General Controls	198	s Petroleum Heat & Power Company	151
s General Electric Company — Appliance			172
chandise Dept			181
s General Electric — Lamps		3 I Illiandi di Colinia de la Colora de la C	20
General Pencil Company	1000	s Pittsburgh Plate Glass Company	
s Goodrich, B. F. Chemical Company		3 TOWERS REGistrate Company	194
		Propellair Division	16
s Great Lakes Steel Corporation			
		s Radio Corporation of America	13
s Hart & Hegeman Division	174	s Republic Steel Corporation44-	161
s Haws Drinking Faucet Co		s Revere Copper & Brass, Inc	46
			55
Haynes Products Company		s Reynolds Metals Company	
s Herring-Hall-Marvin Safe Co		Ricilliona Radiator Company	131
s Hoffman Specialty Co., Inc		Rittling Corp	154
Homasote Company, Inc		Robbins & Myers, Inc	16
s Horn, A. C., Company, Inc		s Roddis Lumber & Veneer Co	18
s Horn Brothers Company	192	s Rotary Lift Co	200
		s Ruberoid Co	68
s Imperial Brass Mfg. Co			184
s Independent Lock Co		s Russell, F. C., Company	109
s Insulite Division			
s International Steel Company	194	Salter, H. B., Mfg. Co	12
		s Samson Cordage Works	201
Jenkins Bros	67	Schlage Lock Company	144
s Johns-Manville		s Seaporcel Porcelain Metals Inc	163
s Josam Manufacturing Co			
s Josam Manufactoring Co		Servel, Inc5	
		s Sloan Valve Company4th C	
s Keasbey & Mattison Company	The state of the s	s Smith, H. B. Co., Inc	128
s Kimberly-Clark Corp	175	s Stanley Works	23
Kinetic Chemicals, Inc		s Stewart Iron Works Co	196
s Kinnear Manufacturing Co		s Stran Steel Division	15
s Koppers Company, Inc	29-139	Straus, Nathan-Duparquet, Inc	186
			136
to the Stant Community	176	Stromberg-Carlson Co	
s Laclede Steel Company		s Surface Combustion Corporation	173
s Libbey-Owens-Ford Glass Company.		s Swartwout Company	178
s Lockwood Hardware Mfg. Co		s Swedish Crucible Steel Co	200
Lone Star Cement Corporation			
s Louisville Cement Company, Inc	39		192
		s Taylor, Halsey W. Co	
Maas Organ Company	192	s Thrush, H. A. & Company	14
s Macomber, Incorporated		Thortel Fireproof Fabrics	14
s Mahon, R. C. Company		s Tile-Tex Co., Inc	2
s Martin-Parry Corporation		Tracy Manufacturing Company	19
McQuay, Inc		s Trane Company	16
s Mengel Company		s Truscon Steel Company	4
s Mesker Brothers			15
		Tuttle & Bailey	13
Michaels Art Bronze Company, Inc Miller Company			
		Union Carbide & Carbon Corporation	16
s Minneapolis-Honeywell Regulator Co	201	s United States Air Conditioning Corp	14
s Minnesota & Ontario Paper Company		s United States Gypsum Company	
s Modine Manufacturing Co		s United States Plywood Corporation65	5-16
Monroe, Lederer & Taussig, Inc	186	United States Rubber Company	5
		s United States Steel Corporation Subsidiaries19	9-19
s National Chemical & Mfg. Co	188	s Universal Atlas Cement Corporation	19
National Clay Pipe Manufacturers, In		s Universal Atlas Cemeni Corporation	17
s National Gypsum Company			
s National Radiator Company		s Van Range, John Co	17
s Nelson, Herman Corporation			
s New Castle Products		Wakefield, F. W. Brass Company	19
Norfolk & Western Railway		s Webster, Warren & Co	15
Morroix & Hesierii Kuii Way		s Wing, L. J. Mfg. Co	
		s Worthington Pump & Machinery Corporation	
Okonite Company	177		
s Otis Elevator Company	185	Wurlitzer, Rudolph Co	0
s Owens-Illinois Glass Company			
s Ozalid Products Division		s York Corporation	19

NEW YORK — H. Judd Payne, General Manager; Robert F. Marshall, Business Manager; Tom Tredwell, Advertising Mgr.; Benton B. Orwig, Creative Service Manager, 119 West 40th Street; BOSTON — Harry M. Horn, Jr., 855 Park Square Bldg.; CHICAGO — Jack Casey, C. B. Riemersma, 700 Merchandise Mart; CLEVELAND — John C. Jackson, 321 Hanna Bldg.; LOS ANGELES — Bob Wettstein, Room 816, 816 West 5th 5t.; PHILADELPHIA — Tom Tredwell, 1321 Arch St.; SAN FRANCISCO — Bob Wettstein, 1085 Monadnock Bldg., 681 Market St.



MUSCATINE HIGH SCHOOL, MUSCATINE, IOWA

Architect: Keffer & Jones — Des Moines, Iowa
Engineer: B. E. Landes — Des Moines, Iowa
Heating Contractor: Sanitary Plumbing & Heating Co. — Muscatine, Iowa

N grade schools, high schools, colleges and universities all over the country, comfortable and healthy air conditions are maintained by Herman Nelson Heating and Ventilating Products.

Because the average man spends about 80 per cent of his entire lifetime indoors, it is important that all buildings in which he goes to school, works and plays be properly heated and ventilated.

For over 40 years, The Herman Nelson Corporation has been building quality heating and ventilating equipment for public, industrial and commercial buildings of all types. Leading Architects, Engineers and Contractors, as well as Owners, know that the use of Herman Nelson Products will assure maintenance of desired air conditions.



THE HERMAN NELSON CORPORATION

Since 1906 Manufacturers of Quality Heating and Ventilating Products

moline, illinois



"From sea to shining sea ..."

America is one?

Not just a coalition of states but a union of land and people. Speaking with one tongue, standing for one ideal. Free to go anywhere over three million square miles of beloved land, without a barrier, from sea to shining sea.

And go we do, on business or pleasure bent, over countless ribbons of railways, highways, waterways, and skyways... the most mobile nation under the sun.

Transportation has forged our unity.

A southern drawl in Boston or a New England twang in Seattle is no more unusual than California oranges on Maine breakfast tables, or Florida strawberries in Indiana shortcakes. Each is the result of more and better transportation facilities.

Contributing immeasurably to our advanced development of transportation has been the plentiful production of durable, reliable steel pipe. Pipe to convey liquid or gaseous fuels, steam, water, compressed air, electric wiring . . . the motivating forces of all transportation.

It is no coincidence that the amazing progress of all forms of

transportation in this century parallels the no less astonishing growth of steel pipe production. For, with transportation, as in so many other developments of American life, steel pipe makes it possible!

The interesting story of "Pipe in American Life" will be sent upon request.

Committee on Steel Pipe Research

AMERICAN IRON AND STEEL INSTITUTE

350 FIFTH AVENUE, NEW YORK 1, N. Y.

STEEL PIPE MAKES IT POSSIBLE!

... better living through pipes of steel for plumbing and heating purposes.